0056172

DISTRIBUTION UNIT MANGERS' MEETING

095596

200 AREA GROUNDWATER AND SOURCE OPERABLE UNITS

Bryan Foley	DOE-RL RP (A5-13
Marvin Furman	
Ellen Mattlin	
Mike Thompson	
Arlene Tortoso	
Lisa Treichel	
Dennis Faulk	EPA (B5-01)
Brenda Becker-Khaleel	WDOE (Kennewick) (B5-18
Zelma Maine	
Tina Masterson-Heggen	WDOE (Kennewick) (B5-18)
John Price	
Matt Mills	WDOE (Kennewick) (B5-18)
Lynn Curry	BHI (H0-19
Garrett Day	
Bruce Ford	
Alison Kent,	BHI (H0-21)
Greg Mitchem	
Joan Woolard	
Tim Lee	CHI (H9-02)
Virginia Rohay	CHI (H0-19)
L. Craig Swanson	
Mary Todd	
Curtis Wittreich	•
Stuart Luttrell	PNNL (K6-96)
Mark Sweeney	
Administrative Record (2)	BHi (H0-09)

Please inform Alison Kent – BHI (372-9192) of deletions or additions to the distribution list.



EDMC

HANFORD PROJECT OFFICE

DEC 18 2002

U.S. EPA

Revised 06/28/01

Meeting Minutes Transmittal/Approval Unit Managers' Meeting 200 Area Groundwater and Source Operable Units

3350 George Washington Way, Richland, Washington May 24, 2001

APPROVAL:	Bryan Foley, 200 Area Unit Manager, DOE/RL (A5-13)	_ Date	11/7/01
APPROVAL:	Arlene Tortoso, Groundwater Unit Manager, DOE/RL (H0-12)	Date	11/25/01
APPROVAL:	Dennis Faulk, 200 Area Unit Manager, EPA (B5-01)	_ Date	12-20-01
APPROVAL:	Jønn Rrice, 200 Area Unit Manager, Ecology (B5-18)	_ Date	4-JAN-02

095596

Meeting minutes are attached. Minutes are comprised of the following:

Attachment 1		Agenda
Attachment 2		Attendance Record
Attachment 3		200 Area Current Action Log
Attachment 4		200 Area UMM Minutes - May 2001
Attachment 5	~	Graph of Carbon Tetrachloride Concentrations
Attachment 6		Comparison of Maximum Carbon Tetrachloride Rebound Concentrations
Attachment 7		Suggested Changes to 200-PW-2 Work Plan to Incorporate 200-PW-4 RCRA TSD Units
Attachment 8		Remedial Investigation Data Quality Objectives Summary Report for the 200-PW-1 Operable Unit Phase I Representative Waste Sites (BHI-01477, Rev. 0)

Prepared by:

Alison Kent, BHI GW/VZ Integration Project (H0-21)

Concurrence by:

Bruce Ford, BHI GW/VZ Integration Project (H0-19)

095596

UNIT MANAGERS' MEETING AGENDA

3350 George Washington Way May 24, 2001

9:00 a.m. – 11:00 a.m. <u>200 Area</u> Room 2A01

General (10 minutes)

- Outstanding Action Items (attached)
- Review of the 200 Area Ecological Assessment briefings
- Review of the Land Use Workshop schedule
 - June HAB Presentation
- DOE-GJO/MACTEC-ERS 200 Area Geophysical Logging Program

Groundwater Operations (5 minutes)

•

200-UP-1 (10 minutes)

• Operations Status

200-ZP-1 (10 minutes)

- Operations Status
- PFP Well Status

200-ZP-2 (PW-1) (10 minutes)

- Operations Status
- Z-9 Well Deepening Status
- SVE Status and Data
- Monthly Vapor Monitoring Status and Data

200-PW-1 Plutonium/Organic-Rich Process Waste OU (10 minutes)

- Work Plan Status
 - Draft A Work Plan due to regulators 12/31/01
 - M-13-00L TPA Change Package in preparation
- Dispersed CCl4 plume DQO process
 - Schedule technical discussion meeting the week of 5/28
- Delivery of DQO Summary Report (Phase I)

200-CW-1 Gable/B Pond and Ditches Cooling Water OU (5 minutes)

• Status request for regulator approval of the RI Report

200-CS-1 Chemical Sewer OU (5 minutes)

• Status of 216-A-29 sampling activity (Support to CHG)

200-TW-1 Scavenged and 200-TW-2 Tank Waste OUs (10 minutes)

- Approval of revised Waste Control Plans to support borehole geophysical logging
- Review of upcoming drilling activities
- Status Ecology approval of Work Plan

200-PW-2 Uranium-Rich Process Waste OU (5 minutes)

• Status of the workplan and TPA change packages

Groundwater and Source Operable Units Unit Managers' Meeting Official Attendance Record – 200 Area May 24, 2001

095596

Please print clearly and use black ink

PRINTED NAME	ORGANIZATION	O.U. ROLE	TELEPHONE
Arlene Tortoso	DOE-RL	200- Area Groundwater	373- 9631
John Price	Ecology	Unit Mgr	736-3029
Matt Mills	Ecology	Cs-Iun	736-5721
BRYAN L. FOLEY	DOB-RL	2000 tea	376-7087
Virginia Rohay	ERC	cely tech support	372-9100
Bruce Ford	BHI	200 Area	372-9105
Mark Byrnes	BHI	200-NP-1 Task Lead	372-9267
Greg Mitchem	SHI	appro land	377-9381
Bunda Junten	Ecology	200-CW-1	734-5707
Moses Jarajes	BUI	COARGA STANDOODS	372-9242
Tim Lec	CHI	CXI GW	372-9362
Chris Cearbox	C #=7	200 Aven	372-9638
Curt Withreich	CHI	Z00 A	372-9586
Dennis Faulk	SPA	RPM	6-8631
Dib Goswani	800/097	sitevial Gw	736-3015

200 Area Unit Managers' Meeting OPEN ACTION ITEMS & TRACKING

S. A.		:	1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1	is determine		18 11441111	o filiting a state of the	
	· <u></u>				de james e marrier i			
	15	200	Area Implementation Plan Ecology comment	Bryan Foley, RL	John Price,	01/18/2000	TBD	
1		resp	conse letter		Ecology	·	i i	}
ı		l l					,	
L				<u> </u>				

MEETING MINUTES 200 AREA GROUNDWATER AND SOURCE OPERABLE UNITS UNIT MANAGERS' MEETING - 200 AREA May 24, 2001

095596

Attendees: See Attachment #2

Agenda: See Attachment #1

Topics of Discussion:

1. General

 Outstanding Action Items – The response to comments letter for Ecology comments on the 200 Area Implementation Plan Ecology was sent to Ecology on April 30, 2001.

- Review of the 200 Area Ecological Assessment Briefings The briefings went well. The draft approach was presented and new ideas were requested. A two phase activity was proposed. Phase I would be a compilation of data resulting in a report. Information will be evaluated and the central plateau will be divided into "ecounits", waste sites will be imposed on "ecounits". The Nez Perce ER/WM Program was given an invitation for a briefing. A briefing with the Hanford Natural Resource Trustee Council (NRTC) is scheduled for September 1, 2001.
- Review of the Land Use Workshop Schedule The kick-off of the Central Plateau Workshops on land use and end states is scheduled for June 5, 2001. There is a meeting with U.S. Department of Energy, Richland Operations Office (DOE-RL) and Office of River Protection (ORP) scheduled for May 30, 2001.
 - June Hanford Advisory Board (HAB) Presentation A three-hour presentation will be given at the HAB meeting on June 12, 2001. John Morse (DOE-RL) is the lead for this.
- DOE-GJO/MACTEC-ERS 200 Area Geophysical Logging Program The Memorandum of Understanding is being sent to MACTEC today, May 24, 2001.

2. 200-UP-1

Operations Status – The system is operating at greater than 50 gallons per minute (gpm). A low-level effort continues on Engineering Design for converting the injection well into an extraction well. Efforts continue on the Feasibility Study for technetium 99. Drilling is on schedule and is to begin June 18, 2001. Mountain States Energy (MSE) representatives were training on site last week. There is a weekly conference call for interested parties every Thursday from 10:30 a.m. to 11:30 a.m. in conference room 2D33 of the Bechtel building at 3350 George Washington Way, Richland, WA.

3. 200-ZP-1

- Operations Status There are five (5) wells operating at about 175 gpm total. An outage is scheduled for June 5, 2001, to change out the granular activated carbon and perform system maintenance. Modifications to the flow control valves of the wells will be made.
- Plutonium Finishing Plant (PFP) Well Status Procurement of the drilling subcontract will begin June 19, 2001. Drilling is to begin August 6, 2001. The work shift is from 5:30 p.m. to 4:00 a.m. Ground penetrating radar surveys were performed last week at the preferred and alternate locations. There is a lot of piping and an evaluation will be done to determine if there is a need to move to the alternate site. The Data Quality Objective (DQO) and Sampling and Analysis Plan is being prepared. EPA stated that the S&T data needs need to be captured in the Sampling Analysis Plan. The Waste Management Plan is being revised. The draft Innovative Treatment Remediation Demonstration (ITRD) Report is out for review. Comments are due back by June 18, 2001. A conference call is scheduled to discuss the proposals. NETL awarded the proposals for the deep and difficult access carbon tetrachloride technologies to Applied Research Associates (ARA) and General Electric. EPA asked if the NETL work (especially the ARA work) could be integrated into the PW-1 Work Plan. The Draft Work Plan needs to go to regulators by December 31, 2001.

4. 200-ZP-2

- Operations Status 100% availability. Wells are operating at 450 cfm with an average concentration of 29 parts per million (ppm) out of the eight wells.
- Z-9 Well Deepening Status Activity began on May 22, 2001, and the first well is at a depth of 122 feet at this point. Ten split spoon samples have been taken and recovery is excellent. Vapor samples have been taken at 105 feet, 114 feet and 122 feet. Carbon tetrachloride concentrations at those depths are 5 ppm, 95 ppm and 174 ppm. Chloroform concentrations at those depths are 4 parts per million by volume (ppmv), 4 ppmv and non-detectable. Vapor samples are planned for approximately every 20 feet.
- SVE Status and Data Tables ("Comparison of Maximum Carbon Tetrachloride Rebound Concentrations Monitored at 200-PW-1 (200-ZP-2) Soil Vapor Extraction Sites FY 1997 – FY 2001" and "Carbon Tetrachloride Rebound Concentrations Monitored at 200-PW-1 (200-ZP-2) Soil Vapor Extraction Sites July 1999 – April 2001") were distributed.

5. 200-PW-1 Plutonium/Organic-Rich Process Waste OU

Work Plan Status

Draft A Work Plan Due to Regulators 12/31/01 –

 M-13-00L TPA Change Package in Preparation – EPA requested a copy of the draft.

• Dispersed CC14 Plum DQO Process

- Schedule Technical Discussion Meeting the Week of May 28, 2001 U.S.
 Environmental Protection Agency (EPA) requested a detailed report of the NETL work be included in this meeting.
- <u>Delivery of DQO Summary Report (Phase I)</u> EPA indicated that the timing of this
 work may be influenced by the work that will be planned for the dispersed plume
 investigation.

6. 200-CW-1 Gable/B Pond and Ditches Cooling Water OU

Status Request For Regulator Approval of the RI Report – Received approval.

7. 200-CS-1 Chemical Sewer OU

Status of 216-A-29 Sampling Activity (Support to CHG) – Bechtel Hanford, Inc., is waiting to receive a work order from CH2M Hill Hanford Group, Inc. (CHG) to perform sampling. Ecology stated that it is their intention to support a Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (CERCLA) removal action if contamination is found during sampling. That would be the quickest option and would support ORP's construction schedule for the Waste Transfer Pipeline.

8. 200-TW-1 Scavenged and 200-TW-2 Tank Waste OUs

- Approval of Revised Waste Control Plans to Support Borehole Geophysical Logging


 The Waste Control Plan was submitted to Ecology. The revisions were to add
 geophysical logging wells. EPA approved the TW-1 Waste Control Plan. The TW-2
 Waste Control Plan was provided to Ecology for review and final approval.
- Review of Upcoming Drilling Activities Plan to be in the field with mock-up the
 week of June 11, 2001. Drilling is scheduled to begin on June 18, 2001. The driller
 was looking at the Personal Protective Equipment (PPE) requirements. The driller
 proposes back-shift drilling operations from 11:30 p.m. to 10:00 a.m. DOE is
 reviewing the health and safety concerns associated with night work.
- Status Ecology Approval of Work Plan -

9. 200-PW-2 Uranium-Rich Process Waste OU

 Status of the Workplan and TPA Change Packages – The transmittal letter to DOE's regulatory compliance organization was sent. "Suggested Changes to 200-PW-2 Work Plan to Incorporate 200-PW-4 RCRA TSD Units" was distributed at the meeting.

Attachment 5

21-Z/81-Z/A1-Z



Comparison of Maximum Carbon Tetrachloride Rebound Concentrations Monitored at 200-PW-1 (200-ZP-2) Soil Vapor Extraction Sites FY 1997 - FY 2001

095596

200-PW-1			November 199)6 -	October 1997	7 -	July 1998 -		July 1999 -	
(200-ZP-2)			July 1997		September 19	98	September 19		June 2001	
Location	Site	Zone	Maximum Rebound	months'	Maximum Rebound	months'	Maximum Rebound	months'		months"
(Well or Probe)			Carbon Tetrachloride	of	Carbon Tetrachlorid	of	Carbon Tetrachloride		Carbon Tetrachloride	of
/feet bgs			(ppmv)	rebound	(ppmv)	rebound	(ppmv)	rebound	(ppmv)	rebound
79-03/ 5 ft	Z-18	1	0	8	0	3	0	12		
79-06/ 5 ft	Z-1A	1	not measured		not measured		1.4	12		
79-11/ 5 ft	Z-1A	1	0	8	0	6	2.9	12		
86-05/ 5 ft	Z-9	1	not measured		not measured		0	3		
86-05-01/ 5 ft	Z-9	1	not measured		not measured		0	3		
86-06/ 5 ft	Ž-9	1	1.3	8	0		1.9	6		
87-05/ 5 ft	Z-1A	1	not measured		0		1.0	12		
87-09/ 5 ft	Z-1A	1	not measured	<u>-</u> -	1.5	3	2.6 1.4	3		
94-02/ 5 ft	Z-9	1		8	not measured 2.1	9	2.5	6		
95-11/5 ft 95-12/5 ft	Z-9 Z-9	1	1.1	8	1,5		1.3	6		
95-14/ 5 ft	Z-9	1	not measured	<u> </u>	not measured	-	0	3		
CPT-13A/ 9 ft	Z-1A	2	not measured		0	6	1.0	12		
CPT-16/ 10 ft	Z-9	2	not measured		Ō		1.5	6		
CPT-17/ 10 ft	Z-9	2	not measured		4.2	9	5.1	6	6.6	22
CPT-18/ 15 ft	Z-9	2	not measured		6.5	9	5.0	6	5.2	22
CPT-31/25 ft	Z-1A	2	not measured		0		0	12		
CPT-16/ 25 ft	Z-9	2	not measured		not measured		not measured		1.8	22
CPT-32/ 25 ft	Z-1A	2	not measured		9.1	6	10	12	16.5	18
CPT-4A/ 25 ft	Z-1A	2	not measured		not measured		not measured		3.5	0
CPT-30/ 28 ft	Z-18	2	not measured		not measured	ļ	3.2	12	1.4	18
CPT-13A/ 30 ft	Z-1A	2	2.2	8	not measured	<u> </u>	not measured		3.6	18
CPT-7A/ 32 ft	Z-1A	2	not measured	<u></u> _	2.3	6	5.4	12	6.2	18
CPT-27/ 33 ft	Z-9	2	1.2	8	not measured		not measured	40	2.6	22 18
CPT-1A/ 35 ft	Z-18	2	2.0	8	1.4		3.0	12	5.1	
CPT-33/ 40 ft	Z-1A	2	not measured	8	2.0 not measured	3	2.6 1.7	12	1.9	0
CPT-34/ 40 ft	Z-18	2	2.3 65.6	8	52.7	9	57	3	127	22
CPT-21A/ 45 ft W15-220ST/ 52 ft	Z-9 Z-9	2	2	l å	not measured		1.6	3	2.5	22
CPT-28/ 60 ft	Z-9	2	not measured		1.5	0	3.7	3	2:0	
CPT-9AV 60 ft	Z-9	2	45.5		41.1	0	44	3	68	22
CPT-30/ 68 ft	Z-18	2	1.7	8	not measured		3.0	12		
CPT-13A/ 70 ft	Z-1A	2	5.2	8	not measured		5.6	12		
CPT-24/70 ft	Z-9	2	not measured		3.2	9	3.6	3		
W15-219SST/ 70 ft	Z-9	2	14.6	8	not measured		7.6	3	7.7	22
CPT-18/75 ft	Z-9	2	not measured		not measured		not measured		16	22
CPT-31/76 ft	Z-1A	2	4.0	- 8	not measured		4.2	12		
CPT-33/ 80 ft	Z-1A	2	5.8		not measured		9.2	12		
W15-82/ 82 ft	Z-9	2	28.9	8	5.5		46	6_	55	22
W15-95/ 82 ft	Z-9	2_	not measured	<u> </u>	15.3	9	39	6	43	21
CPT-21A/ 86 ft	Z-9	2	221	8	206	9	148	6	195	22
CPT-34/ 86 ft	Z-18	2	36.3	-	5.9	3	0	12		
W15-218SST/ 86 ft		2	not measured 280	-	not measured 230	9	203	6	224	22
CPT-28/ 87 ft	Z-18	2	3.9		not measured	-	4.2	12		
CPT-1A/ 91 ft CPT-4A/ 91 ft	Z-18		not measured		7.7	3	14	12		
CPT-9A/ 91 ft	Z-9	2	103		34.5		72	3		
W15-85/ 92 ft	Z-9	2	not measured	-	not measured		not measured		51	22
W18-252SST/ 100			38.2		17.8		24	12		
W18-152/ 113 ft	Z-12	_	46.8	1	11.1		33	12	25	18
W15-217/ 115 ft	Z-9	3	797		630		561	6	442	22
CPT-24/ 118 ft	Z-9	3	44.8		37.7	9	37	6	35	22
W15-220SST/ 118		4	21.9		not measured		36	3	34	22
W18-158L/ 123 ft	Z-1A	3	not measured		143	3	492	12	284	18
W18-167/ 123 ft	Z-1A		323		79.7	3	228	12	248	18
W15-219SST/ 130	Z-9	4	298		not measured		47	3	54	22
W18-249/ 134 ft	Z-18		206		20.4		215	12	176	18
W18-248/ 136 ft	Z-1A		288	•	86.3		177	12	214	18
W15-219SST/ 155		5	59.6		not measured		24	3	44	22
W15-220SST/ 185		5	14.5		not measured		13	3	15	22
W15-6L/ 189 ft	Z-9	6	22.6		17.8		1.3	6		احييها
W15-9L/ 189 ft	Z-9	6	18.3		15.0		15	6	20	21
W18-7/ 200 ft	Z-1A		28.5		17.3		29	12		
W18-6L/ 208 ft	Z-1A	-	36		31.3		15	12		
W18-12/ 210 ft	Z-18	6	not measured	1	3.8	3	19	12		

^{* -} based on location (Z-1A/18/12 or Z-9) of monitoring point; specific points may be beyond SVE zone of influence during particular operating configurations

⁻ Z-18 and Z-12 wells off-line Oct 96 - Apr 98

⁻ CPT-1A, CPT-9A, and possibly CPT-7A appeared to be beyond SVE zone of influence in Oct 96 based on differential pressure (BHI-01105, p. 6-1)

[.] CPT-9A, CPT-21A, CPT-28 beyond SVE zone of influence in May 96 based on CCH concentrations and airflow modeling based on measured vacuums (BHI-01105, p. 6-1)

Carbon Tetrachloride Rebound Concentrations Monitored at 200-PW-1 (200-ZP-2) Soil Vapor Extraction Sites July 1999 - April 2001

	200-PW-1				$\boldsymbol{\dashv}$				н														
CCA	1		07/30/96 09		+		2000	222000	_	30,700	W2/2000 04	_	07/24/2000	06/28/2000	00/25/2000	10/31/2000	11/1/2000	11/20/2000	12/29/2000	1002/21/20	02/28/2001 C	2202001	1,30,200
COM COCK C	┪		-1	┩		┥		4	4	-						3	9						
Character Coperany	Vell or Probe)			Ц	ğ	H	Н	Н	Ц	Н	Н	2	Ď	8	ğ	8	충	3	700	ğ	ş	700	충
2.0			_	Н		I	Н	-	Н	H	-	(ppmv)	(bbmv)	(huudd)	(hundd)	(bbane)	(Alludd)	(vingg)	(DDCLLAN)	(Amidd)	(vinda)	(Auudd)	(pomv)
2.0 0.0 0.0 1.0 1.0 1.0 1.0 1.0 1.0 1.0 1		L,	_	느	=	Ŀ	-	-	_	L	-	**	42			4.3		3.7				5.3	
10	H	L	1.5	3.5	ō	49,	9.	7	2.8	2.6	52	8.0	2.0			-		2				15	~
Section Sect		L	-	-		0	٥	0	0	٥	0	1.8	1.4			9		٦					
22.1 2.2 2.3 2.4 2.5 3.4 2.5 3.4 2.5 2.4 2.5 2.5 2.5 2.5 2.5 2.5 2.5 2.5 2.5 2.5		L.	\mid	1		ö	ō	1.5	3.8	7.0	86	72	-			4		7.8				1	1
2.0 0.0 0.0 1.0 0.0 <td>Γ</td> <td>L</td> <td> </td> <td>-</td> <td></td> <td></td> <td>l</td> <td></td> <td>f</td> <td>-</td> <td>-</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>2</td> <td></td> <td></td> <td></td> <td>1</td> <td>1</td>	Γ	L		-			l		f	-	-							2				1	1
28.8 2.6.5 2.7 2.7 2.7 4.3 4.0 2.7 2.7 2.7 2.7 2.7 2.7 2.7 2.7 2.7 2.7	Γ	L	-	r	T	٩	ů.	-	6	c	-		ſ	[•			1		ľ		ļ	3
4.4 4.7 3.4 2.5 3.4 2.3 2.9 2.4 2.5 5.5 5.6 2.0 2.4 4.7 3.9 4.3 3.9 2.4 2.3 2.5 5.5 5.5 5.5 5.5 5.5 5.6 5.0 3.0 4.3 4.0 3.0 4.1 2.2 5.2 5.2 5.5 5.5 5.5 5.5 5.5 5.2 <td>١.</td> <td>L</td> <td></td> <td>-</td> <td>l</td> <td></td> <td>t</td> <td> </td> <td>•</td> <td>,</td> <td>1</td> <td>1</td> <td>1</td> <td></td> <td>3</td> <td></td> <td></td> <td>2</td> <td></td> <td></td> <td></td> <td>Б</td> <td></td>	١.	L		-	l		t		•	,	1	1	1		3			2				Б	
1.4	Ţ	1	+	1	1	5	5	8		22	52	*	52					2.3				5.4	5.1
13.3		┙	1	1	1	22	2	2.8	23	*	4.7	62	3.9					3.8				5.1	2
5.3 4.2 3.7 4.3 4.0 3.7 5.1 4.9 5.0 4.6 4.2 54.0 99.4 88.7 91.4 172 96.4 90.8 84.4 92.9 81.8 66.8 66.8 33.2 43.9 67.6 40.3 41.6 42.2 38.1 1.2 6.1 1.9 62.9 36.1 31.5 34.2 23.2 43.9 67.6 40.3 41.6 42.2 38.1 1.9 61.0 19.9 47.1 24.2 23.2 23.5 23.5 23.5 23.7 23.7 23.7 1.2 6.1 1.9 61.0 19.9 47.1 24.2 113.2 12.7 23.6 13.6 13.6 13.6 13.6 13.6 13.7 14.7 14.7 17.7 14.8 14.7 14.7 14.7 14.7 14.7 14.8 14.7 14.8 14.7 14.8 14.7 14.8 14.7		4		1	1	1.1	0	1.2	1.2	1.3	1.6	1.3	1.2					12				20	1
54.0 94 68.7 91.4 122 96.4 80.8 92.8 81.0 96.8 96.8 96.8 33.2 43.9 67.6 40.3 41.6 42.2 38.1 38.2 42.9 36.1 31.5 34.3 32.2 43.9 67.6 40.3 41.6 42.2 38.1 13.2 42.1 2.4 113.2 21.2 21.7 22.7 27.4 27.4 27.4 28.1 17.2 17.1 17.1 30.2 30.1 17.2 17.1 22.1 17.2 42.1 17.2 42.1 17.1 17.1 17.1 17.1 17.1 17.1 17.1 17.1 17.1 17.1 17.1 17.1 17.1 17.1 17.1 17.2 22.1 17.2 17.1 17.1 17.1 17.1 17.1 17.1 17.1 17.1 17.1 17.1 17.1 17.1 17.1 17.1 17.1 17.1 17.1 17.1		4	1	+		2.5	3.1	2.8	4.1	3.3	4.2	3.7	3.7	6.4				5.1				12	
54.0 \$44. \$45. \$44. \$45. \$44. \$45. <th< td=""><td>7</td><td>4</td><td>-</td><td>1</td><td>1</td><td>_</td><td></td><td></td><td></td><td>_</td><td>_</td><td>-</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td>-</td></th<>	7	4	-	1	1	_				_	_	-											-
20.2 43.9 67.6 40.3 41.6 42.2 38.1 38.2 42.9 30.1 31.5 34.3 34.3 13.2 22.3 22.3 22.3 22.3 22.3 22.3 22	_	Ц	51.7	90.6	62	50.3	2	70.4	81.6	54.0	Z	788	21.6	122	788	200		84.4		l		0 33	
29.2 43.6 67.6 40.3 41.6 42.2 38.1 1.9 42.6 38.1 31.5 34.3 29.8 25.6 23.5 28.5 28.6 1.1 30.2 1.1 30.2 1.1 30.2 1.1 30.1 13.9 47.1 2.4 113.2 2.1.2 2.1.2 2.1.3 1.2 6.1 1.2 6.1 1.2 6.1 1.2 1.1 30.1 1.2 4.1 30.2 1.2 1.1 1.2 6.1 1.2 6.1 1.2 6.1 1.2 6.1 1.2 6.1 1.2 6.1 1.2	_	Щ				-	 	-														000	2
28.8 26.5 22.5 26.5 28.5 28.5 28.5 28.5 28.5 28.5 28.5 28	_	L	(8)	43.9	44.0	8.02	9	43.5	5	33.0	9 67	7.00	46.2	Ĺ		8	Ī						1
28.8 25.5 23.5 23.5 23.5 23.5 23.5 23.5 23.5	2	Ļ		T	T				+	1	2	0.10				8		382				8	<u></u>
28.8 25.5 23.5 22.5 28.5 28.7 11.2 6.1 1.9 51.0 19.8 47.1 2.4 13.2 21.2 21.7 22.7 27.4 28.5 1.1 30.2 30.6 38.1 32.1 35.5 42.6 89.7 20.6 18.6 11.8 13.7 27.4 28.5 1.1 30.2 30.6 38.1 32.1 35.5 42.6 89.7 22.5 3.1 1.8 13.7 22.7 21.6 15.7 17.1 17.0 10.6 20.6 20.0 19.0 2.3 82.0 442 35.0 11.8 13.7 28.1 13.7 17.1 17.1 17.0 10.6 10.0 20.0 10.0 20.0 10.0 20.0 10.0 20.0 10.0 20.0 10.0 1	1	↓	+	+	\dagger		\dagger	1	$\frac{1}{1}$	\dagger	$\frac{1}{1}$	1											7.
13.2 27.2 22.5 22.5 22.5 22.5 1.1 30.2 30.6 39.1 32.1 22.4 32.5 3	T	ļ	10	120	•	,	1	1000	1	†	1	+										-	18.
13.2 27.2 27.7 23.5 1.1 30.2 30.6 39.1 35.1 25.5 42.9 113.2 27.2 27.4 20.5 17.5	t	ļ		1		1		7.5	0.0	7.7	ġ	SE	25.5	28.5	28.7	12	6.1	1.9				2.4	55.(
113 146	t	4				3	71.	120	34.5	132	21.2	21.7	23.7	27.4	28.5	1.1	30.2	30.6		32.1	35.5	42.8	
82.0 442 358 166 452 269 130 105 52 50 180 127 140 180 127 140 180 127 140 180 127 140 180 127 140 180 127 140 180 127 140 180 127 140 180 180 180 180 180 180 180 180 180 18	1	4	90.0	12.6	Ž	8	1 3	ភ	141	113	195	196	20	28	175	20		148				121	ğ
82.0 442 354 15 13.7 52 2.9 5.2 5.8 3.8 6.0 2.3 82.0 442 359 166 462 269 160 160 23 3.9 66.5 3.9 66.7 3.9 66.7 3.9 66.7 3.9 6.7 1.4 1.6 1.7 1.6 1.6 1.6 1.6 <t< td=""><td>1</td><td>4</td><td>46.3</td><td>151</td><td>105</td><td>ğ</td><td>8</td><td>98</td><td>191</td><td>69.7</td><td>205</td><td>185</td><td>1,74</td><td>214</td><td>Se</td><td>127</td><td></td><td>135</td><td></td><td></td><td>L</td><td></td><td>2 8</td></t<>	1	4	46.3	151	105	ğ	8	98	191	69.7	205	185	1,74	214	Se	127		135			L		2 8
9.7 22.9 3.1 1.8 13.7 5.2 2.9 1.0 5.3 6.5 5.2 3.9 6.5 92.0 442 359 166 150 130 165 200 239 66.5 152 134 156 166 151 141 177 156 166 135 97.2 104 246 227 216 167 174 177 156 166 155 97.2 100 178 137 78.3 154 66.2 51.0 169 175 214 164 176 130 163 170 164 177 169 175 214 164 176 150 163 170 164 10.1 5.9 5.5 8.8 8.9 5.2 1.4 164 175 11.2 11.1 20.4 10.1 5.9 5.5 8.9 8.3 5.6 5.2 <td>1</td> <td>4</td> <td>-</td> <td></td> <td></td> <td>_</td> <td>_</td> <td></td>	1	4	-			_	_																
82.0 442 359 166 520 150 155 200 150 520 150 520 150 520 150 520 520 150 520 520 520 520 520 520 520 520 520 5	┪	_		_	۲	1.8	12	24.7	17.7	3.7	22.9	14	1.8	ĺ	4.2			6.3				1	ä
142 134 136 186 187 171 170 184 187 239 86.5 152 134 186 187 171 171 170 184 187 239 200 284 153 134 137 173 174 177 189 189 173 239 200 284 150 173 189 189 189 170 189 86.2 177 189 175 214 184 178 150 123 11.9 11.0 20.4 10.1 5.9 5.5 8.8 8.3 5.8 5.5 1.4 150 123 11.9 11.0 20.4 10.1 5.9 5.5 8.8 8.3 5.8 5.5 1.4 150 123 11.9 11.0 20.4 10.1 5.9 5.5 8.8 8.3 5.8 6.3 5.8 1.4 150 123 11.9 11.0 20.4 10.1 5.9 5.5 8.8 8.3 5.8 6.3 5.8 1.4 150 123 11.9 11.0 20.4 10.1 5.9 5.5 8.8 8.3 6.3 5.8 6.5 1.4 150 123 11.9 11.0 20.4 10.1 5.9 5.5 8.8 8.3 6.3 5.8 6.5 1.4 150 123 11.9 11.0 20.4 10.1 5.9 5.5 8.8 8.3 6.3 5.8 6.5 1.4 150 123 11.9 11.0 20.4 10.1 5.9 5.5 8.8 8.3 6.3 5.8 6.5 1.4 150 123 11.9 11.0 20.4 10.1 5.9 5.5 8.8 8.3 6.3 5.8 6.5 1.4		L	98.6	287	26.3	Š	317	25	904	9	1	2	3		1		30,	3 5				6.3	
152 134 196 186 151 141 176 164 197 239 200 284 100 200 137 783 154 167 174 177 196 197 239 200 284 100 200 178 137 783 154 52 510 199 175 214 164 178 130 130 130 130 130 130 130 130 130 130	_	L	-	H		-		-			-	t	1			ŀ	3	8				6.5	8
104 246 227 216 157 174 177 159 164 197 239 200 284 109 246 227 216 157 174 177 159 169 169 155 972 178 150 178 150 178 178 178 150 178 178 178 178 178 178 178 178 178 178		Ļ.	-	-	l			-	-		+	†											35.
104 2.46 2.27 2.19 157 141 171 194 197 239 200 284 197 239 200 284 197 239 230 234 239 230 234 235 235 2		L		+	T	78.6	100	75.	2	169	755	100	947	1		1	7						*
9.0 173 119 11.0 20.4 10.1 5.9 5.5 8.8 8.9 8.2 1.4 178 178 178 178 178 178 178 178 178 178		L		H		-	118	77.	18	12	5	2	B	0	1	9		š				284	
90.0 176 137 78.3 154 86.2 51.0 49.2 123 52.1 125 46.7 130 130 130 130 130 130 130 130 130 130	15	L			l	+			3	5	2	ğ	219	18/	7.4	2		8				97.2	
100 100		ļ.		t	\dagger	•			9,	-				ĺ								_	54.
9.0 12.3 11.9 11.0 20.4 10.1 5.9 5.5 8.8 8.3 5.2 11.4 16.4 178 MWIS-9L are autrected according to sample results to be undergoing maintenance. WIS-95 appears to have refutivad to normal.	T	⊥.	+	t	\dagger		2 2		2 5	200	2/2	13/	76.3		86.2	51.0		49.2				46.7	
9.0 12.3 11.9 11.0 20.4 10.1 5.9 5.5 8.8 8.3 5.8 5.2 1.4 Nd Y15-81, are auspected scoopeding to sample results to be undergoing maintenance. 11.4 11.9 10.1 5.9 5.5 8.8 8.3 5.8 5.2 1.4 Nd Y15-81, are authorized scoopeding to sample results to PTT. 11.4		L	\dagger	+	+	3	2.0	200	2	3	20	8	2	100	8	177		169				178	
9.0 12.3 11.9 11.0 20.4 10.1 5.9 5.5 8.8 8.3 5.8 5.2 1.4 and W15-84, wise suspected scoording to sample results to be undergoing maintenance. W15-85, W15-84, W15-85 to support well despending for PTT. W15-85 appears to have refurned to normal.		1		-	\dagger	t		+	+	1	1	†											43.
No. 12.3 11.9 11.0 20.4 10.1 5.9 5.5 8.8 8.3 5.2		Į.	13	\$	 		465	1	1														7
emple pump faithing amples comment. The well cage were off on wells W15-65 and W15-62. In addition, wells W15-62 and W15-62, and w15-62 and w15	✝	+		2	†	83	2	1		0.6	12.3	2	11.0	8	10.1	6.5	5.5	8.8				1.4	
sempler comment. The well cape were off on wells W15-62 and W15-62. In addition, well W15-91, and W15-92, and W15-92, and W15-92 and W15-92, and W15-92 an	ample pump failure	I	-	1	T		T	+	\dagger	\dagger	+	1										1	
e velte will be related on 11(01,00.) Total: Before that well cape were off as a result of downhole video survey conducted on 10/31/00 in W15-62, W15-84, W15-85 to support well despend on 11/01/00. Amy the comment: W15-21, W15-81, and W15-82 and a result of downhole video survey conducted on 10/31/00 in W15-82, W15-84, W15-85 to support well despend to PTT. Amy the comment: W15-21, W15-81, and W15-82 and a result of downhole video survey conducted on 11/2/00 in W15-82, W15-84, W15-85. Total: citil (braughtines) lest orthogon on 11/7/00 in W15-82, W15-84, W15-85.	emoler comment.	The Will	And when of	- CO	WILES	THE WATER	P. meleline	A marke 14/42		20 20]								
note: Before that will cape using of as a meal of downhole video survey conducted on 10/31/00 in Wis-8c, Wis-8c to support was dependent for PITT. Applies comment: Wis-8ct, and Wis-8ct are bover than especial. Well Wis-8c appears to have returned to normal. Applies beact or well-6ct the service of the s	to well will be release	9	A01/00	-							- Preparation	OCCUPATION OF		00 De 1110	Mem dulom	enence.							
Ample comment with the season of the season	Acte. Refer of their																					-	
Sent were back or 17, 175-21, and V15-25 show returns that selected. Well W15-55 spoems to have returned to normal. Toda: clift (straightness) sent conducted or 11/200 in W15-82, W15-84, W15-85. India: clift (straightness) sent conducted on 11/700 in W15-82, W15-84, W15-85.	The property of	1			DOM:	NO STILL	Sononci	10/31	SLM WIGH	¥.	4, ¥15-98 R	support we	decening	for PITT.									
Copies conf. of man on 110700 damp sempling. Copies conf. (if (included on 110700 damp sempling.) Copies (included on 110700 damp sempling.) Copies (included on 110700 damp sempling.)		74	1		A STONE TO		Toward ou	No expecter	Med W	5-95 appe	In to herve ru	Humad to no	ormel										
TOWN: CREATING THE CONDUCTOR ON 11/2/DO In WIS-82, WIS-84, WIS-85, WIS-84, WIS-85, WIS-84, WIS-85, WIS	CORTO MAN CONTRACTO	00	17/07/00 00	Supplement Supplement	ď	1	-	_	1	-	_												
notice: eldow-up downthole vidoo aurway conductied on 11/7/20 in W15-62, W15-64, W15-65.	NOW: CHI STREOM	200	conducted	8	on Wis-	Z, W15-84	W15-96		_													+	
	NOTE: TORON-UP DO	A POLICE	DBO BLITVEY !	ponducien	1 on 11/7/	20 In W15-B	2 W15-84	, W15-95.								T	ľ					†	

Suggested Changes to 200-PW-2 Work Plan to Incorporate 200-PW-4 RCRA TSD Units

 Change the title of the document to the following:
 200-PW-2 Uranium-Rich Process Waste Group Operable Unit RI/FS Work Plan and Process Waste RCRA TSD Unit Sampling Plan

Note that this affects the footer on all pages. (For simplicity this footer will read "200-PW-2 OU RI/FS Work Plan and RCRA TSD Unit Sampling Plan".)

2. Modify the Executive Summary by adding the following sentence to the end of the first paragraph:

As a result of recent discussions with the regulators regarding streamlining the 200 Area assessment process the assessment of two additional RCRA TSD units (the 216-A-37-1 Crib and the 207-A South Retention Basin) has been integrated into the RI/FS process as part of the 200-PW-2 OU. By adding the assessment of these 2 TSD units from the 200-PW-4 General Process Waste Group OU to the scope of the 200-PW-2 OU it will be possible to accelerate the investigation of all process waste-type related RCRA TSD units.

3. Rewrite Section 1.0 by adding the paragraph highlighted as the last paragraph:

1.0 INTRODUCTION

The Hanford Federal Facility Agreement and Consent Order (Tri-Party Agreement) (Ecology et al. 1998) identifies approximately 700-800+ soil waste sites (and associated structures) resulting from the discharge of liquids and solids from 200 Area processing facilities to the ground. These 700-800+ sites have been arranged into 23 separate waste groups that contain Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (CERCLA) past-practice sites; Resource Conservation and Recovery Act of 1976 (RCRA) past-practice (RPP) sites; and RCRA treatment, storage, and disposal (TSD) units.

This work plan supports CERCLA remedial investigation/feasibility study (RI/FS) activities for the 200-PW-2 Uranium-Rich Process Waste Group Operable Unit (OU) and the assessment of the 216-A-37-1 Crib and 207-A South Retention Basin RCRA TSD units from the 200-PW-4 General Process Waste Group OU. This work plan also-integrates both RCRA facility investigation/corrective measures study (RFI/CMS) and CERCLA requirements for the OU. The process outlined in the work plan follows the CERCLA format with modifications to concurrently satisfy RCRA requirements as described in the 200 Areas Remedial Investigation/Feasibility Study Implementation Plan - Environmental Restoration Program (DOE-RL 1999) (hereinafter referred to as the Implementation Plan). The Implementation Plan is summarized in Section 1.1 of this work plan.

The 200 Areas is one of three areas on the Hanford Site that remain on the U.S. Environmental Protection Agency's (EPA) National Priorities List under CERCLA. The 200-PW-2 OU is located near the center of the Hanford Site in south-central Washington State. The 200-PW-2

OU consists of 26 waste sites and 8 associated unplanned release (UPR) sites as defined in the Implementation Plan (DOE-RL 1999). This was subsequently updated using information in the Waste Information Data System (WIDS), bringing the current total to 34 sites. In the spring of 2000, an effort was initiated to evaluate the waste sites identified in the 200-PW-2 OU following the waste site reclassification process, as described in *Tri-Party Agreement Handbook Management Procedures*, Guideline Number TPA-MP-14, "Maintenance of the Waste Information Data System (WIDS)" (DOE-RL 1998). As a result of that process, waste site 200-W-23 has been rejected as a duplicate of 200-W-22, and site UPR-200-E-40 has been rejected through consolidation into a larger site, 200-E-103, which will be addressed under the 200-UR-1 OU. Thus, site numbers 200-W-23 and UPR-200-E-40 will no longer be considered in the 200-PW-2 planning. The total number of sites remaining in the 200-PW-2 OU, therefore, is 32.

Of the 23 source OUs in the 200 Areas, the 200-PW-2 OU was assigned a higher priority because waste sites within the OU have relatively high inventories of a mobile contaminant (i.e., uranium), and some waste sites are known contributors to uranium contamination in groundwater. In addition, the OU includes RCRA TSD unit waste sites that have Tri-Party Agreement-required closure plans in the year 2003.

The 200-PW-2 waste sites received uranium-rich process condensate/process waste, primarily from waste streams generated at the 221/224-U Plant Uranium Recovery Project (URP), the Reduction-Oxidation (REDOX) process facility, and the 224-U/UO₃ Program for the Plutonium/Uranium Extraction (PUREX) Plant, as well as at the 221-B (B Plant) and Semi-Works facilities in the 200 East and 200 West Areas. Most of the process waste sites (cribs and trenches) received uranium-rich solutions from both the cold runs (nonirradiated uranium) and startup phases prior to the operation of the three main plants. The process condensates were vapors collected from thermally hot process steps that were condensed and subsequently discharged to the ground.

This work plan contains the requirements for characterization of the four waste sites from this the 200-PW-2 OU that are considered to be representative of the remaining sites. Three of the four sites (i.e., the 216-A-19 Trench, the 216-B-12 Crib, and the 216-U-8 Crib) are RPP sites, whereas the fourth (i.e., the 216-U-12 Crib) is also a RCRA TSD unit. Two additional RCRA TSD units (the 216-A-10 Crib and 216-A-36B Crib) will also be characterized as part of RCRA closure activities for this the 200-PW-2 OU. The three TSD units are identified as interim status units under Washington Administrative Code (WAC) 173-303. The current Part A Permit applications for these units are contained in Appendix A. The logic for selecting sites from this OU to be characterized is contained in Section 2.2. All six sites are identified in the Implementation Plan (DOE-RL 1999).

Based on recent discussions with Ecology and EPA on ways to further streamline 200 Area assessment planning, two additional RCRA TSD units have been added into the RI/FS process as part of the 200-PW-2 OU. This more focused approach was also discussed during the annual review of 200 Area work scope priorities conducted during the spring of 2001. As a result of these meetings, Ecology agreed that the assessment of the 216-A-37-1 Crib and 207-A South Retention Basin RCRA TSD units (from the 200-PW-4 General Process Waste Group) may be addressed as part of the 200-PW-2 OU work plan to accelerate the investigation of all process

waste-type RCRA TSD units. A separate Sampling and Analysis Plan will be prepared for these two RCRA TSD units; the implementation of which will be integrated with the 200-PW-2 RI. Furthermore, the TSD units will also be incorporated into subsequent RI/FS documents under the 200-PW-2 OU. The current Part A Permit applications for these two units are contained in Appendix A.

The characterization and remediation of waste sites at the Hanford Site are addressed in the Tri-Party Agreement (Ecology et al. 1998). The schedule of work at the Hanford Site is governed by these Tri-Party Agreement milestones. The Washington State Department of Ecology (Ecology) is the lead regulatory agency for this OU. The milestone controlling the schedule for the 200-PW-2 OU in-was M-13-25, "Submit Uranium-Rich Process Waste Group Work Plan," which was met with submittal of the work plan by December 31, 2000. Associated project milestones are discussed in Section 6.0. An Other associated milestones is-include Milestone M-20-33, which requires submittal of the 216-A-10 Crib and 216-A-36B Crib closure/post-closure plans to Ecology by October 31, 2003, and M-20-52 and M-20-53 that address submittal of closure/post-closure plans for the 216-A-37-1 Crib and 216-A South Retention Basin by December 31, 2003. (These dates are currently under review for possible consolidation with the proposed submittal date for the feasibility study/closure plan.) The schedule shown in Figure 6-1 proposes new completion dates for these RCRA TSD milestones in order to align them with completion of the feasibility study/closure plan.

- 4. Modify Figure 1-1 to show the addition of the 216-A-37-1 Crib and 207-A South Retention Basin RCRA TSD Unit Sampling and Analysis Plan task. Add information such as that included in Column 1 to describe the contents of the SAP, including the DQO report.
- 5. Modify Section 5.1 as shown in the highlighted section.

5.1 INTEGRATED REGULATORY PROCESS

The RCRA closure and corrective action authorities have clear jurisdiction over waste with chemical constituents (in particular, dangerous waste and dangerous waste constituents) and the chemical constituents in mixed wastes (i.e., mixtures of dangerous waste and radiological contaminants), but not jurisdiction over waste with radiological contaminants only. By applying CERCLA authority concurrently with RCRA closure and corrective action requirements through integration, cleanup will be addressing all regulatory and environmental obligations at this OU, including compliance with MTCA, as effectively and efficiently as possible. Also, by applying CERCLA authority jointly with that of RCRA, additional options for disposal of closure, corrective action, and remedial action wastes at the Environmental Restoration Disposal Facility are possible. By allowing flexibility in final disposal options, DOE, Ecology, and EPA intend to minimize disposal costs as much as possible while remaining fully protective of human health and the environment.

The integrated process for characterization of the 200-PW-2 OU uses this RI/FS work plan in combination with the Implementation Plan (DOE-RL 1999) to satisfy the requirements for both an RI/FS work plan and an RFI/CMS work plan. General facility background information, potential ARARs, preliminary RAOs, and preliminary remedial technologies developed in the

Implementation Plan are incorporated by reference into this work plan. This work plan also provides RCRA TSD unit closure plan information on facility description, location, and process information (Sections 2.1 and 2.2), waste characteristics (Section 3.1), and groundwater monitoring (Section 3.2). Following the completion of the work plan, an RI will be performed that will satisfy the requirements for an RFI and will provide the data needed to support the selection of a closure strategy for RCRA TSD units. The RI will be limited to the concurrent investigation of representative waste sites and RCRA TSD units undergoing closure. A report summarizing the results of the RI will then be prepared that will satisfy the requirements for an RFI report. The report will also contain the characterization information required in a RCRA TSD unit closure plan.

Based on recent discussions with Ecology and EPA on ways to further streamline 200 Area assessment planning, two additional RCRA TSD units have been added into the RI/FS process as part of the 200-PW-2 OU. This more focused approach was also discussed during the annual review of 200 Area work scope priorities conducted during the spring of 2001. As a result of these meetings, Ecology agreed that the assessment of the 216-A-37-1 Crib and 207-A South Retention Basin RCRA TSD units (from the 200-PW-4 General Process Waste Group) may be addressed as part of the 200-PW-2 OU work plan to accelerate the investigation of all process waste-type RCRA TSD units. A separate Sampling and Analysis Plan will be prepared for these two RCRA TSD units; the implementation of which will be integrated with the 200-PW-2 RI. Furthermore, the TSD units will also be incorporated into subsequent RI/FS documents under the 200-PW-2 OU.

After the RI is complete, remedial alternatives/closure strategies will be developed and evaluated against performance standards and evaluation criteria. The integration process for the evaluation of remedial alternatives includes the preparation of an FS/closure plan that will satisfy the requirements for a CMS report. Both documents are required to include identification and development of corrective measure/remedial alternatives and an evaluation of those alternatives. The CMS generally also includes a recommended alternative, which is typically the purpose of the proposed plan under CERCLA. The FS will include a section that provides corrective action recommendations for RPPs and closure plans will address the RCRA TSD units in the OU. The FS will also include further evaluation and refinement of ARARs that were identified in the Implementation Plan.

The RCRA TSD closure options (i.e., landfill, modified, and clean closure as defined in Condition II.K. of the Hanford Facility RCRA Permit) will be determined based on the alternative selected and the amount of cleanup that can be attained by the alternative. Landfill closure under RCRA could include the construction of an engineered barrier over the unit and equates to what is typically termed as a "containment alternative" under CERCLA. A modified closure option includes alternatives that leave contaminants in place above MTCA Method B cleanup standards in soil, debris, or groundwater, but below MTCA Method C. A clean closure option requires that all contaminated material and media be removed and decontaminated to levels below MTCA Method B.

Recent revisions prompted by the EPA and codified in the June 2000 amendments to WAC 173-303-610(1)(d) for closure/postclosure plans and WAC 173-303-645(1)(e) for

corrective actions allow for alternative requirements for closure, post-closure, groundwater monitoring, or corrective action at TSD units. WAC 173-303-645(1)(e) states:

"The director may, in an enforceable document, replace all or part of the requirements of this section with alternative requirements for ground water monitoring and corrective action when he or she determines: (i)A dangerous waste unit is situated among other solid waste management units or areas of concern, a release has occurred, and both the dangerous waste unit and one or more of the solid waste management units or areas of concern are likely to have contributed to the release; and (ii) It is not necessary to apply the requirements of this section because the alternative requirements will protect human health and the environment."

These revisions allow certain TSD units to be addressed through the corrective action program rather than through the TSD closure requirements. This flexibility is intended to reduce the potential for confusion and inefficiency created by the application of two different regulatory requirements at the same unit or between units within close proximity of one another. Under these new provisions, closure and postclosure plans may be eliminated as stand-alone documents in favor of generating a more holistic document that includes the closure/postclosure elements within the details of the corrective action requirements at TSD, RPP, and CERCLA past-practice units. The application of these revised regulations to OUs within the 200 Areas of the Hanford Site will require further discussion between Ecology and DOE and may result in changes to the integrated RCRA/CERCLA process presented in the Implementation Plan (DOE-RL 1999), Figure 1-1 of this work plan, and this section.

The decision-making process for the 200-PW-2 OU will be based on the use of a proposed plan, ROD, and Hanford Facility RCRA Permit modification. Based on the FS/closure plan, a proposed plan will be prepared that identifies the preferred remedial alternative for waste sites within the OU. The proposed plan will include a draft permit modification with unit-specific permit conditions for RPP waste sites and the RCRA TSD units within the OU for incorporation into the Hanford Facility RCRA Permit. The CERCLA ROD will document the RCRA TSD unit closure and RCRA corrective action decisions for these units. The lead regulatory agency (Ecology) will prepare the CERCLA ROD following completion of the public involvement process for the proposed plan, which, after signature by the Tri-Parties, will authorize the selected remedial action. The remedy selected under CERCLA will be incorporated into the Hanford Facility RCRA Permit as the RCRA closure/corrective action after issuance of the public notice and the comment process.

The technical and procedural elements of RCRA and CERCLA are each addressed in full in this process. The CERCLA public involvement, including public notice and opportunity to comment, will be enhanced, as necessary, to concurrently satisfy the public involvement requirements for the RCRA closure and RPP processes. The public will be given an opportunity to review and comment on the FS/closure plan and the proposed permit conditions that will be contained in the proposed plan. The proposed plan with a draft permit modification will be issued for a minimum 45-day public review and comment period. Supporting documents, including the FS/closure plan, will also be made available to the public for review at this time.

A combined public meeting/public hearing may be held during the comment period to provide information on the proposed action and permit modification and to solicit public comment.

6. Modify Section 5.2.1 to include the following highlighted paragraph:

5.2 REMEDIAL INVESTIGATION ACTIVITIES

This section summarizes the planned tasks that will be performed during the RI phase for the 200-PW-2 OU, including the following:

- Planning
- Field investigation
- Management of investigation-derived waste (IDW)
- Laboratory analysis and data validation
- Preparing an RI report.

These tasks and subtasks reflect the work breakdown structure that will be used to manage the work and to develop the project schedule discussed in Section 6.0.

5.2.1 Planning

The planning subtask includes activities and documentation that need to be completed before field activities can begin. These include the preparation of a job hazard analysis and site-specific health and safety plan (HASP), radiation work permits, excavation permits and supporting surveys (e.g., cultural, radiological, wildlife, and utilities), work instructions, personnel training, and the procurement of materials and services (e.g., drilling and geophysical logging services). In addition, borehole locations identified in Figures 4-1 through 4-3 will be located using a global positioning satellite system.

With the addition of the 216-A-37-1 Crib and 207-A South Retention Basin RCRA TSD units from the 200-PW-4 OU to the scope of work for this work plan, it will be necessary to prepare a separate Sampling and Analysis Plan for these two RCRA TSD units. All required approvals and necessary planning activities identified above will be completed prior to initiating field activities. Field activities for these two TSD units will be initiated in sequence with the remainder of the assessment activities identified in this work plan.

Appendix B of the Implementation Plan (DOE-RL 1999) provides a general HASP that outlines health and safety requirements for RI activities. Site-specific HASPs will be prepared for test pit excavation and drilling following the requirements of the general HASP. Initial surface radiological surveys will be performed to document any radiological surface contamination and the background levels in and around the sampling locations. This information will be used to document initial site conditions and prepare HASPs and radiation work permits.

7. Modify Section 6 as shown below:

6.0 PROJECT SCHEDULE

The project schedule for activities discussed in this work plan is shown in Figure 6-1. This schedule will serve as the baseline for the work planning process and will be used to measure the progress of the implementation of this process. The schedule for field activities and the preparation, review, and issuance of the RI report, the FS/closure plan, and the proposed plan/ proposed permit modification are also shown in Figure 6-1. The schedule concludes with the preparation of a ROD. Modification of the Hanford Facility RCRA Permit will occur after issuance of the ROD, during Ecology's annual modification process.

The portion of the schedule most germane to this work plan and the SAP (Appendix B) are FY 2001 through 2003. One Tri-Party Agreement milestone that has been completed involved submittal of Draft A of the work plan to the regulators by December 31, 2000 (Milestone M-13-25). Existing outyear RCRA TSD unit milestones include M-20-33, which requires submittal of the 216-A-10 Crib and 216-A-36B Crib closure/post-closure plans to Ecology by October 31, 2003, and M-20-52 and M-20-53 which require submittal of the 216-A-37-1 Crib and 207-A South Retention Basin closure/post-closure plans, to Ecology by December 31, 2003. The schedule shown in Figure 6-1 proposes new completion dates for these RCRA TSD milestones in order to align them with completion of the feasibility study/closure plan. Modifications to major milestone M-20-00 will be proposed at a later date as part of a comprehensive package to address all other remaining M-20 interim milestones.

The following are proposed project milestone completion dates for key activities:

- Complete field activities (M-15-43A) September 30, 2003*
- Submit Draft A RI report for regulatory review (M-15-43B) June 30, 2004*
- Submit Draft A FS/closure plans and Draft A proposed plan/permit modification for regulator review (M-15-43C) – December 31, 2005*.

Interim milestones to be designated under the Tri-Party Agreement will be established through negotiations between the Tri-Parties. A Class II change form will be submitted to Ecology and EPA to request the addition of any interim milestones. Any updates to the project schedule or associated milestones will be reflected in the annual work planning process. Currently field activities are scheduled to begin in FY 2003.

*Target project milestone

- 8. Revise the project schedule in Figure 6-1 to add a line for preparation of the SAP for the 2 TSD's, move all project milestones out 1 year to be consistent with the new targets, eliminate reference to the M-20-33 milestone on the figure (in lieu of having it mentioned in the text), and do not add the other 2 PW-4 milestones to the figure.
- 9. Add copies of the Part A, Form 3 Permit Applications for both the 216-A-37-1 Crib and 207-A South Retention Basin to Appendix A.

10. To be consistent with the approach taken in recent work plans remove Appendix C, the Waste Control Plan, from the document. This document will be issued as a separate document that will get regulator concurrence. A global search of the document will be conducted to remove reference to the Waste Control Plan.

Remedial Investigation
Data Quality Objectives
Summary Report for the
200-PW-1 Operable Unit
Phase I Representative
Waste Sites

Prepared for the U.S. Department of Energy, Richland Operations Office
Office of Environmental Restoration

TRADEMARK DISCLAIMER

Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors.

This report has been reproduced from the best available copy. Available in paper copy and microfiche.

Available for a processing fee to U.S. Department of Energy and its contractors from:
U.S. Department of Energy
Office of Scientific and Technical Information
P.O. Box 62
Oak Ridge, TN 37831-0062
(865) 576-8401
fax: (865) 576-5728
email: reports@adonis.osti.gov
online ordering: http://www.doe.gov/bridge

Available for sale to the public, in paper, from:
U.S. Department of Commerce
National Technical Information Service
5285 Port Royal Road
Springfield, VA 22161
(800) 553-6847
fax: (703) 605.6900
email: orders@ntis.fedworld.gov
online ordering: http://www.ntis.gov/ordering.htm

Printed in the United States of America

DISCLM-5.CHP (11/99)

BHI-01477

Rev. 0

OU: 200-PW-1, 200-ZP-2 TSD: N/A GW/vzi00

ERA: N/A

APPROVAL PAGE

Title:

Remedial Investigation Data Quality Objectives Summary Report for

the 200-PW-1 Operable Unit Phase I Representative Waste Sites

Approval:

L. R. Curry, Groundwater/Vadose Zone Integration Project Engineer

Signature

B. H. Ford, Groundwater/Vadose Zone Integration Project, 200 Area Assessment Task Lead

Date

M. N. Jarayssi, Groundwater/Vadose Zone Integration Project

Environmental Lead

HHI-DIS JUR 5/9/01

The approval signatures on this page indicate that this document has been authorized for information release to the public through appropriate channels. No other forms or signatures are required to document this information release.

Remedial Investigation Data Quality Objectives Summary Report for the 200-PW-1 Operable Unit Phase I Representative Waste Sites

Authors

R. G. Bauer
M. L. Yates
CH2M HILL Hanford, Inc.

Date Published

April 2001

EXECUTIVE SUMMARY

This Phase I data quality objective (DQO) summary report supports the remedial investigation/feasibility study (RI/FS) and remedial action decision-making processes for the 200-PW-1 Organic Rich/Plutonium Rich Waste Group Operable Unit (OU). A RI of the 200-PW-1 OU will be conducted under the Comprehensive Environmental Response, Compensation, and Liability Act of 1980. The 200-PW-1 OU consists of eight waste sites including cribs, trenches, and two unplanned release sites. Two waste sites in the 200-PW-1 OU have tentatively been identified as representative sites in the Waste Site Grouping for 200 Area Soil Investigations report (DOE-RL 1997b) and the 200 Areas Remedial Investigation/Feasibility Study Implementation Plan – Environmental Restoration Program (hereinafter referred to as the Implementation Plan) (DOE-RL 1999).

Another RI/FS DQO (Phase II) will be performed for the 200-PW-1 OU waste sites that addresses the dispersed carbon tetrachloride plume underlying a portion of the Hanford 200 West Area. The sampling requirements identified in the two DQO summary reports will be combined in the sampling and analysis plan within the 200-PW-1 OU work plan.

The waste sites in the 200-PW-1 OU received effluents from the Z Plant Complex, including the Plutonium Finishing Plant processes, which contained significant concentrations of chemicals and radionuclides. Data collected during the RI will be used to determine if the waste sites are contaminated above levels that will require remedial action, to support evaluation of remedial alternatives and/or closure strategies, and to verify or refine the preliminary conceptual contaminant distribution models. The data will be generated mainly through soil sampling and analysis.

This DQO effort follows the concepts developed in the Implementation Plan (DOE-RL 1999) for using analogous site contaminant data to reduce the amount of characterization required to support RI/FS decisions. These concepts involve grouping sites with similar process histories, structures, and contaminants and then choosing one or more representative sites for comprehensive field investigation, including sampling during RI activities. Findings from the RI

at representative sites are then used to make remedial action decisions for all of the waste sites in the OU. Nonrepresentative sites for which field data have not been (or will not be) collected are assumed to have contaminant characteristics similar to the representative sites that are characterized. A Record of Decision for the OU will be issued through the RI/FS process using the data collected during the RI. The analogous sites (i.e., those not sampled during the RI) will be addressed during the confirmatory sampling phase to ensure that the remedial action specified in the Record of Decision is appropriate and to provide design data as needed. Following remedial actions, verification samples will be collected to support site closeout.

The Washington State Department of Ecology's document, Guidance on Sampling and Data Analysis (Ecology 1995), was used in developing the sampling design for the RI. Because the data will not be used to demonstrate compliance with a cleanup level, focused (biased) soil sampling of areas selected with the highest contamination potential was selected over an area-wide (unbiased) sample design. The concentrations of all contaminants in each soil sample will be compared directly with the cleanup levels. A statistical analysis of the sampling data is not appropriate for focused sampling schemes and, therefore, is not used in this report. The locations of samples exceeding the cleanup level will be used to delineate the areas of soil contamination that require a decision to be made on the need for remediation.

The proposed sampling locations were selected with the goal of intersecting the areas of highest contamination and determining the vertical extent of contamination. The nature (e.g., contaminant type and concentration) and the vertical extent of the contamination are the major RI data needs. For sites that have not been adequately characterized, boreholes will be drilled to the groundwater table and soil samples will be collected at specified locations within the borehole. Geophysical logging of planned boreholes will also be performed.

The contaminants of potential concern were identified through process history information and previous data collection efforts. Analytical performance criteria were based on *Model Toxics*Control Act chemical compliance criteria (Washington Administrative Code 173-340) and other applicable or relevant and appropriate requirements. In the absence of applicable or relevant and appropriate requirements, other preliminary action levels were identified to determine analytical

performance criteria. These levels provide the basis for identifying the laboratory or field screening detection limits required to support remedial action decisions. A modified version of the U.S. Environmental Protection Agency's DQO guidance (EPA 1994a) was used to identify project data quality needs, to evaluate sampling and analysis options, and to document project data quality decisions.

TABLE OF CONTENTS

1.0	STEP	1 – STATE THE PROBLEM1-	1
	1.1	INTRODUCTION1-	-1
	1.2	PROJECT SCOPE1-	4
	1.3	PROJECT OBJECTIVES1-	4
	1.4	PROJECT ASSUMPTIONS1-	-5
	1.5	PROJECT ISSUES1-	.8
		1.5.1 Global Issues	
	1.6	WASTE SITES AND OPERATING HISTORY 1-1	.0
		1.6.1 Plant History	
2.0	STE	P 2 – IDENTIFY THE DECISION2-	-1
3.0	STE	P 3 – IDENTIFY THE INPUTS TO THE DECISION	-1
	3.1	BASIS FOR SETTING THE PRELIMINARY ACTION LEVEL	-1
	3.2	INFORMATION REQUIRED TO RESOLVE DECISION STATEMENTS 3-	-1
		3.2.1 Data Gap Analysis	-7
	3.3	COMPUTATIONAL AND SURVEY/ANALYTICAL METHODS 3-	-7
	3.4	ANALYTICAL PERFORMANCE REQUIREMENTS3-1	0
4.0	STE	P 4 – DEFINE THE BOUNDARIES OF THE STUDY4-	-1
	4.1	OBJECTIVE4	-1
	4.2	WORKSHEETS FOR STEP 4 – DEFINE THE BOUNDARIES OF THE STUDY4-	-1
	4.3	SCALE OF DECISION MAKING4	4
	4.4	PRACTICAL CONSTRAINTS4	-4

5.0	STEI	P 5 – DEVELOP A DECISION RULE	5-1
	5.1	INPUTS NEEDED TO DEVELOP DECISION RULES	5-1
	5.2	DECISION RULES	5-2
6.0	STE	6 - SPECIFY TOLERABLE LIMITS ON DECISION ERRORS	6- 1
	6.1	STATISTICAL VERSUS NON-STATISTICAL SAMPLING DESIGN	6- 1
	6.2	NON-STATISTICAL DESIGNS	6-2
7.0	STEI	7 - OPTIMIZE THE DESIGN	7-1
	7.1	PURPOSE	7-1
	7.2	WORKSHEETS FOR STEP 7 – OPTIMIZE THE DESIGN	7- 1
	7.3	SAMPLING OBJECTIVES	7 -4
	7.4	SAMPLING DESIGN	7-4
		7.4.1 Preferred Sampling Design	7-12
	7.5	POTENTIAL SAMPLE DESIGN LIMITATIONS	7-22
8.0	REFI	ERENCES	8-1
FIGU	JRES		
1-1.	Locat	ion of the Hanford Site and 200-PW-1 Operable Unit Waste Sites	1-2
1-2.		W-1 Operable Unit Waste Sites Relative to Source Facilities.	
1-3.		eptual Exposure Model for the 200-PW-1 Operable Unit.	1-31
1-4.		ninary Conceptual Contaminant Distribution Model	
1 5	ior the	e 216-Z-1A Tile Field	1-32
1-5. 7-1.		ninary Conceptual Contaminant Distribution Model for the 216-Z-9 Trench View of the 216-Z-1A Tile Field	
7-1. 7-2.		eptual Diagram of Borehole in the 216-Z-1A Tile Field	
7-2. 7-3.		View of the 216-Z-9 Trench	
7-3. 7-4.		on View of the 216-Z-9 Trench.	
7-5.		eptual Diagram of the Angle Drilling Boreholes.	
7 -4/1	-01100	-prem - regium of the range briming botonois	/-1/

TABLES

l-1.	DQO Scoping Team Members	1-12
l -2 .	DQO Workshop Team Members	1-13
1-3.	DQO Integration Team Members	1-13
l-4.	DOO Key Decision Makers.	1-14
1-5.	Existing Documents and Data Sources for 200-PW-1 Operable Unit	1-14
1-6.	Sources of Contamination, COPCs, and Affected Media for the 200-PW-1	
	Operable Unit	1-17
1-7.	200-PW-1 Operable Unit COPC Exclusions and Justifications	1-18
1-8.	200-PW-1 Operable Unit Final COC List.	1-22
1-9.	List of Preliminary ARARs and PRGs.	1-26
1-10.	General Exposure Scenarios.	1-27
1-11.	Regulatory Milestones.	1-28
1-12.	Project Milestones.	1-28
1-13.	Preliminary Conceptual Contaminant Distribution Model Discussion	
	and Concise Statement of the Problem.	1-28
2-1.	Summary of DOO Step 2 Information	2-1
3-1.	Basis for Setting Preliminary Action Level.	3-1
3-2.	Required Information and Reference Sources.	3-2
3-3.	Information Required to Resolve the Decision Statements.	3-7
3-4.	Details on Identified Computational Methods.	3-8
3-5.	Potentially Appropriate Survey and/or Analytical Methods	3-9
3-6.	Analytical Performance Requirements - Shallow and Deep Zone Soils	3-11
3-6.	Analytical Performance Requirements - Shallow and Deep Zone Soils	3-12
4-1.	Characteristics that Define the Population of Interest	4-1
4-2.	Geographic Boundaries of the Investigation	4-1
4-3.	Strata with Homogeneous Characteristics.	4-2
4-4.	Temporal Boundaries of the Investigation	4-3
4-5.	Scale of Decision Making.	4-4
4-6.	Practical Constraints on Data Collection.	4-4
5-1.	Decision Statements	5-1
5-2.	Inputs Needed to Develop Decision Rules	5-1
5-3.	Alternative Actions.	5-2
5-4.	Decision Rules	5-2
6-1.	Statistical Versus Non-Statistical Sampling Design.	6-1
7-1.	Determine Data Collection Design.	7-1
7-2.	Determine Non-Statistical Sampling Design.	7-2
7-3.	Methods for Collection of Data at Depth	7-2
7-4.	Characterization Goals and Drivers	7-4
7-5.	Sampling Design Alternatives	7-5
7-6.	Proposed Sampling Designs	7-19

ACRONYMS

AA alternative action
AEA alpha energy analysis

ALARA as low as reasonably achievable

ARAR applicable or relevant and appropriate requirement

BGO bismuth-germinate
bgs below ground surface
BHI Bechtel Hanford, Inc.
CAS Chemical Abstract Service

CERCLA Comprehensive Environmental Response, Compensation, and Liability Act

of 1980

CFR Code of Federal Regulations
CHI CH2M Hill Hanford, Inc.
COC contaminant of concern

COPC contaminant of potential concern

CPP Comprehensive Environmental Response, Compensation, and Liability Act

of 1980 past-practice

CVAA cold vapor atomic absorption
DBBP dibutyl butyl phosphonate
DNAPL dense non-aqueous phase liquid
DOE U.S. Department of Energy
DQO data quality objective

DR decision rule
DS decision statement

EPA U.S. Environmental Protection Agency
ERC Environmental Restoration Contractor

FH Fluor Hanford, Inc.
FS feasibility study
GC gas chromatography

GCMS gas chromatography/mass spectrometry

GEA gamma energy analysis
GPC gas proportional counter
GW/VZ Groundwater/Vadose Zone

HEIS Hanford Environmental Information System

HPGe high-purity germanium
IC ion chromatography
ICP inductively coupled plasma

inductively coupled plasma

ICPMS inductively coupled plasma mass spectrometer

MCL maximum contaminant level MTCA Model Toxics Control Act

NaI sodium iodide

O&M operating and maintenance

OU operable unit

PCB polychlorinated biphenyl

PFP Plutonium Finishing Plan

PHMC Project Hanford Management Contractor
PNNL Pacific Northwest National Laboratory

PQL practical quantitation limit
PRF Plutonium Reclamation Facility
PRG preliminary remediation goal
PSO principal study question

PUREX Plutonium-Uranium Extraction (Facility)

RDR/RAWP remedial design report/remedial action work plan

REDOX Reduction-Oxidation (Facility)
RESRAD RESidual RADioactivity dose model

RG rubber glove

RI remedial investigation

RL U.S. Department of Energy, Richland Operations Office

RMA remote mechanical operations "A" line RMC remote mechanical operations "C" line

ROD Record of Decision

SAP sampling and analysis plan SGL spectral gamma logging

STOMP Subsurface Transport Over Multiple Phases

SVOC semi-volatile organic compound

TBP tributyl phosphate

TIC tentatively identified compound

TOC total organic carbon

Tri-Party Hanford Federal Facility Agreement and Consent Order

Agreement

TRU waste materials contaminated with 100 nCi/g of transuranic materials

having half-lives longer than 20 years

UCL upper confidence level
UPR unplanned release
VOA volatile organic analyte
VOC volatile organic compound
WAC Washington Administrative Code

WDOH Washington State Department of Health

WIDS Waste Information Data System

METRIC CONVERSION CHART

Iı	nto Metric Unit	s	Ou	t of Metric Units	:
If You Know	Multiply By	To Get	If You Know	Multiply By	To Get
Length			Length		
inches	25.4	millimeters	millimeters	0.039	inches
inches	2.54	centimeters	centimeters	0.394	inches
feet	0.305	meters	meters	3.281	feet
yards	0.914	meters	meters	1.094	yards
miles	1.609	kilometers	kilometers	0.621	miles
Area			Area		
sq. inches	6.452	sq. centimeters	sq. centimeters	0.155	sq. inches
sq. feet	0.093	sq. meters	sq. meters	10.76	sq. feet
sq. yards	0.0836	sq. meters	sq. meters	1.196	sq. yards
sq. miles	2.6	sq. kilometers	sq. kilometers	0.4	sq. miles
acres	0.405	hectares	hectares	2.47	acres
Mass (weight)			Mass (weight)		
ounces	28.35	grams	grams	0.035	ounces
pounds	0.454	kilograms	kilograms	2.205	pounds
ton	0.907	metric ton	metric ton	1.102	ton
Volume			Volume		
teaspoons	5	milliliters	milliliters	0.033	fluid ounces
tablespoons	15	milliliters	liters	2.1	pints
fluid ounces	30	milliliters	liters	1.057	quarts
cups	0.24	liters	liters	0.264	gallons
pints	0.47	liters	cubic meters	35.315	cubic feet
quarts	0.95	liters	cubic meters	1.308	cubic yards
gallons	3.8	liters			
cubic feet	0.028	cubic meters	·		
cubic yards	0.765	cubic meters			
Temperature			Temperature		
Fahrenheit	subtract 32, then multiply by 5/9	Celsius	Celsius	multiply by 9/5, then add 32	Fahrenheit
Radioactivity			Radioactivity		
picocuries	37	millibecquerel	millibecquerel	0.027	picocuries

1.0 STEP 1 – STATE THE PROBLEM

The purpose of data quality objective (DQO) Step 1 is to state the problem clearly and concisely and to ensure that the focus of the study is unambiguous.

1.1 INTRODUCTION

This Phase I summary report has been developed to support the remedial investigation/feasibility study (RI/FS) and remedial action decision-making processes for the 200-PW-1 Organic Rich/Plutonium Rich Waste Group Operable Unit (OU). A RI of the 200-PW-1 OU will be conducted under the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (CERCLA). The 200-PW-1 OU consists of eight waste sites that include cribs, trenches, and two unplanned release (UPR) sites. Two waste sites in the 200-PW-1 OU have tentatively been identified as representative sites in the Waste Site Grouping for 200 Areas Soil Investigations report (DOE-RL 1997b) and the 200 Areas Remedial Investigation/Feasibility Study Implementation Plan - Environmental Restoration Program (hereinafter referred to as the Implementation Plan) (DOE-RL 1999).


Another RI/FS DQO (Phase II) will be performed for the 200-PW-1 OU waste sites that addresses the dispersed carbon tetrachloride plume underlying a portion of the Hanford 200 West Area. The sampling requirements identified in the two DQO summary reports will be combined in the sampling and analysis plan (SAP) within the 200-PW-1 OU work plan.

The waste sites in the 200-PW-1 OU received effluents from the Z Plant Complex, including the Plutonium Finishing Plant (PFP) processes, which contained significant concentrations of chemicals and radionuclides. A map of the Hanford Site is provided in Figure 1-1 and depicts the 200 Areas and vicinity (i.e., the location of the 200-PW-1 OU). Figure 1-2 identifies the locations of the 200-PW-1 OU waste sites and the associated source facilities.

This DQO summary report focuses on the development of sampling designs for the representative (typical and worst-case) sites identified in the waste site grouping report (DOE-RL 1997b) and the Implementation Plan (DOE-RL 1999). This DQO summary report includes confirmation of the appropriate representative waste sites for implementation of the analogous site concept for this OU.

The 216-Z-1A Tile Field is a typical waste site for the 200-PW-1 OU. Waste sites in this OU received similar types of contaminants, but the estimated waste inventories vary significantly. The 216-Z-9 Trench site is the worst-case site for this OU.

Figure 1-1. Location of the Hanford Site and 200-PW-1 Operable Unit Waste Sites.



216-T-19 216-Z-1&2 216-Z-3 200-PW-1 Waste Sites 241-U Tank Farm 100 200 300 400 500 BHI:mea 11/20/00 /home/meaye/amh/pw1_sites.aml Plotted 30-NOV-2000 Rev 1

Figure 1-2. 200-PW-1 Operable Unit Waste Sites Relative to Source Facilities.

1.2 PROJECT SCOPE

This DQO summary report focuses on the representative waste sites associated with the 200-PW-1 Organic Rich/Plutonium Rich Waste Group OU. The scope of this project includes the DQO process and development of a SAP for the two representative waste sites that will be incorporated into an RI/FS work plan. The DQO summary report and SAP will provide the basis for RI of the 200-PW-1 OU using the analogous site concept.

The Implementation Plan (DOE-RL 1999) presents a consistent approach to data collection activities associated with 200 Area assessment and remediation activities. The activities include all phases of sampling required to support the completion of the CERCLA process, which is outlined in Section 2.3 and depicted in Figure 2-2 of the Implementation Plan (DOE-RL 1999). Specific activities include the following:

- Data collection at representative sites defined for the waste group-specific OU work plan, with an emphasis on verifying the conceptual contaminant distribution model(s). This will support preparation of a risk evaluation, focused feasibility study, and remedial action decision making.
- Data collection after issuance of the Record of Decision (ROD) to confirm that the analogous sites in the specific waste group OU are represented by the conceptual contaminant distribution model(s). In addition, data collection activities will be included as part of the remedy selected for the waste group to provide site-specific information for preparation of the remedial design report/remedial action work plan (RDR/RAWP).
- Verification sampling will be performed to determine that remedial objectives have been
 met. For the remove, treat, and dispose alternative, a RDR/RAWP will identify data
 collection requirements to verify that remedial action objectives have been met. For sites
 where wastes have been contained in place, an operating and maintenance (O&M) plan will
 be prepared to demonstrate adequacy of the remedial action. For example, an O&M plan
 would specify barrier performance monitoring activities.

This DQO process supports the data collection that will enable the evaluation of remedial alternatives and selection of a preferred alternative through the RI/FS process. Additional DQO processes will be conducted to define the sampling requirements for the other phases of data collection. The critical data needs of other Groundwater/Vadose Zone (GW/VZ) core projects will be integrated in the 200-PW-1 RI/FS work plan/SAP and are not discussed in this DQO report.

1.3 PROJECT OBJECTIVES

The objective of the DQO process for the 200-PW-1 Organic Rich/Plutonium Rich Waste Group OU is to determine the environmental measurements necessary to support the RI/FS process and remedial decision making, including refinement of the preliminary conceptual contaminant

distribution model. Additionally, the DQO process supports development of a SAP for the RI, which will be included as an appendix to the RI/FS work plan.

Possible alternatives identified in the Implementation Plan (DOE-RL 1999) include the following:

- No action alternative (no institutional controls)
- Engineered multimedia barrier
- Excavation and disposal of waste
- Excavation, ex situ treatment, and geologic disposal of TRU-contaminated soil
- In situ vitrification of soil
- In situ grouting or stabilization
- Monitored natural attenuation (with institutional controls).

1.4 PROJECT ASSUMPTIONS

Project assumptions for the RI include the following:

- The DQO process will be performed in accordance with BHI-EE-01, Environmental Investigations Procedures, Procedure 1.2, "Data Quality Objectives," and Section 6.1 of the Implementation Plan (DOE-RL 1999).
- The 200-PW-1 is a source OU and the investigations will focus on vadose zone soil contamination.
- The Final Hanford Comprehensive Land Use Plan Environmental Impact Statement (DOE 1999) identifies land use in the near future (50 years) within the 200 Area land-use boundary as industrial (exclusive) and centers mainly on waste management activities.
- The Implementation Plan (DOE-RL 1999) outlines the assessment and remediation approach to be followed for the OU:
 - Defines the regulatory framework
 - Generally identifies the characterization approach
 - Provides background information on 200 Area site conditions, operational history, and secondary plans (e.g., quality assurance, health and safety, information management, and waste management)
 - Provides governing assumptions, including preliminary applicable or relevant and appropriate requirements (ARARs), land-use considerations, remedial action objectives, and alternatives.

- Rev. 0
- The analogous site approach will be used. Characterization will be limited to representative waste sites and the characterization will be used to reach remedial decisions for all waste sites within the OU. The DQO effort will focus on representative waste sites within the OU. Preliminary representative waste sites have been selected in the waste site grouping report (DOE-RL 1997b) and the Implementation Plan (DOE-RL 1999) that were considered to be representative of typical and worst-case conditions for the OU. Representative waste sites for the 200-PW-1 OU are as follows:
 - 216-Z-9 Trench (worst-case site)
 - 216-Z-1A Tile Field (typical site).
- Eight specific waste sites and two UPRs within the OU are listed in Appendix G of the Implementation Plan (DOE-RL 1999). Sites identified in the 200-PW-1 OU are listed below:
 - 216-T-19 Crib
 - 216-Z-1&2 Cribs
 - 216-Z-1A Tile Field
 - 216-Z-3 Crib
 - 216-Z-9 Trench
 - 216-Z-12 Crib
 - 216-Z-18 Crib
 - 241-Z-361 settling tank
 - UPR-200-W-103
 - UPR-200-W-110.

Sampling to characterize the non-representative waste sites is not included in the scope of the 200-PW-1 work plan.

- A review of the representative sites is a key component of the DQO process. The representative sites identified in the waste site grouping report (DOE-RL 1997b) and the Implementation Plan (DOE-RL 1999) have been revisited with the DQO scoping team members and key decision makers to ensure that the appropriate sites are chosen. The final selection of representative waste sites is considered flexible (i.e., different waste sites may be selected as representative sites, or additional representative sites may be added).
- The representative waste sites in this OU are known to contain transuranic radionuclides at concentrations greater than 100 nCi/g, indicating that some of the soils would be classified as TRU-contaminated soils under U.S. Department of Energy (DOE) Guide 435.1-1 IIIA.
- Existing characterization data from 200-PW-1 waste sites and analogous data (i.e., borehole logging results from boreholes in the vicinity of the waste sites) will be used to support the DQO process and to prepare the RI/FS work plan. Based on historical site uses and current contaminant of potential concern (COPC) information, it is recognized that certain waste site contaminants of concern (COCs) will exceed action levels and that remediation will be required.

- A preliminary conceptual contaminant distribution model for the 200-PW-1 waste group in general has been developed in Waste Site Grouping for 200 Area Soil Investigations
 (DOE-RL 1997b). This preliminary conceptual contaminant distribution model provides an initial prediction of the nature and extent of the primary COCs. Models for the representative sites will be developed as part of the DQO effort and work plan preparation.
- Remedial actions will likely be required to achieve ARARs, including the industrial soil cleanup standards of the Model Toxics Control Act (MTCA) (Washington Administrative Code [WAC] 173-340) for chemical contaminants. The industrial standards are designated Method C in MTCA. The radiological dose limits will be determined in the future. For purposes of this DQO process, a dose limit range from 15 to 500 mrem/yr above natural background is applied for radionuclides in soil (refer to Global Issue #2 in Section 1.5.1). Because the waste sites in this OU are contained within the exclusive land-use boundary for the 200 Areas, an industrial land-use scenario is assumed.
- Potential data uses that need to be considered when developing DQOs include refinement of the preliminary conceptual contaminant distribution model; evaluation of remedial action alternatives, remedial action decisions, and risk assessment; and worker health and safety.
- The environmental data collected will be used to support waste disposal. A subsequent DQO
 process will be conducted for designation of the wastes generated during RI/FS
 characterization sampling.
- Wastes with mobile contaminants were disposed at these sites and may have impacted groundwater in the past. However, evaluation of groundwater contamination and remediation is not included in the scope of the work plan.
- The RI (i.e., initial OU characterization) will validate, or provide the basis to refine, the conceptual contaminant distribution models for all of the waste sites in the OU through characterization of the representative waste sites. The conceptual contaminant distribution models and the conceptual exposure model will be used to develop and evaluate remedial action alternatives applicable to the OU in a FS/closure plan. The RI/FS will form the basis for selecting a preferred remedial action in a proposed plan for the 200-PW-1 OU.
- Supplemental sampling requirements that result from integration efforts with other projects
 are not addressed in this DQO summary report but will be incorporated in the SAP, which
 will be issued following the issuance of this DQO report.
- Ecological DQOs, if established/needed, will be addressed under a 200 Area-wide investigation. Ecologically sensitive COPCs will be evaluated through that process.

1.5 PROJECT ISSUES

Project issues include the global issues that transcend the specific DQO project and the technical issues that are unique to the project. Both global and project technical issues have the potential to impact the sampling design or the DQOs for the project.

1.5.1 Global Issues

Two global issues were identified during a meeting between the U.S. Environmental Protection Agency (EPA) and the U.S. Department of Energy, Richland Operations Office (RL) on December 5, 2000.

- Global Issue #1 The 200-PW-1 OU waste sites have contributed to the carbon tetrachloride plume (vadose zone vapor and groundwater) that underlies a significant portion of the 200 West Area. Because remediation of the plume exceeds the scope of the 200-PW-1 OU waste site remedial decisions (currently under the Groundwater Management Project), it is a global issue for this project. To address this need, DOE and the Environmental Restoration Contractor (ERC) are developing a 200 Area-wide carbon tetrachloride remediation strategy under the Groundwater Management Project. The scope of this DQO process is, therefore, limited to the contiguous boundaries of the 200-PW-1 OU waste sites. Consequently, characterization of the larger groundwater and vadose zone carbon tetrachloride plume and dense non-aqueous phase liquids (DNAPLs) is not considered to be an objective of this DQO process. The critical data needs of other GW/VZ core projects will be integrated in the 200-PW-1 RI/FS work plan/SAP.
- Global Issue #2 The radiological dose limit for industrial land use is a global issue for this project, as the dose limit has not been established by decision makers. The EPA is evaluating radiological limits that range from 15 to 500 mrem/yr above background, with an industrial scenario yet to be defined. This issue will be further defined in the FS process and documented in the ROD for the OU.
- Global Issue #3 During the external DQO briefing on February 28, 2001, EPA noted that RL may not have a consistent policy for handling TRU-contaminated materials on the Hanford Site. The EPA's concern is that several of the potential remedial alternatives for the 200-PW-1 OU waste sites would leave TRU-contaminated soil in place (with or without treatment). These alternatives appear to be inconsistent with the remedial practices for other Hanford TRU waste types that will be shipped to the Waste Isolation Pilot Plant.

This DQO summary report evaluates the ability of laboratory analytical methods for radionuclide COCs to meet the DQOs (i.e., detection limits) to support the evaluation of either the upper (500 mrem/yr) and lower (15 mrem/yr) limits.

1.5.2 Project Technical Issues

The project's technical issues include the following:

- Characterization of the 200-PW-1 OU waste sites must consider radiological control requirements for possible TRU-contaminated soils at levels above the DOE definition for TRU of 100 nCi/g.
- If contaminated soils are present above the TRU level in the 200-PW-1 OU waste sites, stringent health and safety restrictions will be imposed on workers and work practices. Analyses of TRU-contaminated soils may require the use of an onsite laboratory, which could unfavorably impact analytical costs, detection limit, and analyte lists. The RI-related waste disposal options may also be affected.
- The 200-ZP-2 Project will extend two wells (299-W15-84 and 299-W15-95) approximately 30.5 m (100 ft) through the caliche formation near the 216-Z-9 Trench. Split-spoon sampling will be performed for volatile organic analytes (VOAs), metals, gross alpha and beta, plutonium (and several other radionuclides), and oil and grease, primarily for waste designation. It is possible that some of the data accumulated through this effort will meet the data quality needs for the 200-PW-1 RI/FS DQO process. The use of these data will be addressed in the SAP.
- The enclosure structure located on top of the 216-Z-9 Trench is not designed to support loads greater than those imposed by several occupational workers. The structure cannot be used to support heavy sampling equipment (e.g., drilling equipment). Because of the high contamination levels within this trench, operations that could breach the enclosure roof were deemed unacceptable. This was considered in the development of sampling design alternatives in Section 7.0.
- Several of the waste constituents within the 200-PW-1 OU waste sites have degraded to complexing agents. This may have affected the mobility of other constituents and analytical methods may not exist. These are noted in Table 1-7, where applicable.
- Although the 241-Z-361 settling tank is an analogous site within the 200-PW-1 OU, a unique remediation path may be implemented because of perceived risks associated with this site. The Hanford Federal Facility Agreement and Consent Order (Tri-Party Agreement) (Ecology et al. 1998) Milestone M-15-37B established the need to characterize the tank contents and structural integrity. Fluor Hanford, Inc. (FH) fulfilled this milestone, which is documented in a letter from FH to RL entitled, Submittal of Documentation in Fulfillment of Milestone M-15-37B, dated June 15, 2000 (FH 2000). In this letter, FH proposed a regulatory path forward that included three options: (1) a non-time critical removal action, (2) interim remedial action, and (3) deferral to the 200-PW-1 OU. The analytes reported in this characterization effort are consistent with the COCs in this DQO summary report including americium-241, neptunium-237, plutonium-238, plutonium-239/240, strontium-90, technetium-99, uranium-235, silver, cadmium, chromium, mercury, nickel, lead, tributyl

phosphate (TBP), ammonia, chloride, fluoride, nitrate, polychlorinated biphenyls (PCBs), phosphate, and sulfate.

1.6 WASTE SITES AND OPERATING HISTORY

The 200-PW-1 OU in the Hanford Site's 200 West Area includes eight CERCLA past-practice (CPP) sites and two UPR sites that received mostly acidic aqueous wastes, organic process wastes, and laboratory wastes containing relatively large amounts of americium and plutonium, with a moderate amount of uranium and small amounts of fission products. Figures 1-1 and 1-2 depict the location of the study areas relative to the 200 West Area. Waste discharged to the soil column in this OU was generated at the Z Plant Complex (which includes the PFP) from 1949 through 1980.

1.6.1 Plant History

The 231-Z Building was constructed in 1944 and served to further decontaminate the plutonium products from both T and B Plants before shipment offsite. In 1948, the 234-5 Z Building and ancillary facilities were constructed to replace the processes of the 231-Z Building. The rubber glove (RG) line was implemented in 1949. The remote mechanical operations (RMA-RMC) began in 1935 and continued until 1989. Throughout its lifetime, the Z Plant Complex received various types of processed (uranium and fission products removed) plutonium solutions from each of the 200 Area separations facilities. The major processes conducted in the Z Plant Complex included plutonium isolation and purification from the various solutions, production of metallic plutonium, and recovery of plutonium and americium from plutonium scrap solutions. Currently Z Plant's mission is the stabilization of plutonium-containing solids, solutions, and incinerator ashes and the deactivation of the facility. Several buildings were associated with the 200-PW-1 OU waste streams from Z Plant including the PFP and the RECUPLEX plutonium recovery process housed in 234-5Z, the Plutonium Reclamation Facility (PRF) in 236-Z, the americium recovery facility in 242-Z, and the Analytical and Development Laboratory.

Liquid waste generated at Z Plant was routed to an underground storage tank (e.g., 241-Z-361 settling tank) through an underground transfer system. The storage tank was used to settle the heavier constituents from the liquid effluents, forming sludge. The liquid supernatants in the tanks were ultimately discharged to the soil column via cribs, trenches, and tile fields.

The "worst-case" representative site is the 216-Z-9 Trench. This trench operated from 1955 to 1962. It received solvent and aqueous wastes from the RECUPLEX process. (The trench was the only waste site to receive solvent wastes during the RECUPLEX operation.) In 1976 and 1977, the trench floor was mined for plutonium using remotely operated equipment. Mining efforts recovered 58.1 kg (128 lb) of plutonium. Data collected during mining operations suggest that approximately 38 to 48 kg (84 to 106 lb) of plutonium remain in the soil below the trench. An enclosure structure was built to cover the trench before liquid discharges were initiated. The enclosure is reportedly not capable of supporting loads greater than the weight of two workers. A formal structural analysis has not been performed for the enclosure to date. Currently the FH Nuclear Materials Stabilization Project is responsible for the trench.

The "typical case" representative site is the 216-Z-1A Tile Field. The tile field operated from 1949 to 1969 and received effluent waste from the 234-5Z, 236-Z, and 242-Z facility operations. The tile field was originally constructed to receive liquid waste overflow from the 216-Z-1 and 216-Z-2 Cribs; however, the cribs were bypassed and the waste was routed directly to the tile field.

1.6.2 Process Information

At the Z Plant Complex, the recovered purified plutonium was refined to one of several forms depending upon the era and available process. At the start of Hanford operations, plutonium was refined in the 231-Z Building where it was converted to a nitrate paste prior to shipment offsite. Shortly thereafter, however, a more elaborate plant, the 234-5Z (i.e., PFP), was constructed with the capability to convert plutonium into metal, nitrate, or oxide forms. A number of process lines in the 234-5Z Building were used between 1949 and 1989. Initially batch inorganic chemical steps were used to refine and convert plutonium to the desired form, and elaborate mechanical extraction processes were developed later. The PFP was used to fabricate plutonium into weapons shapes and to reprocess scrap plutonium using solvent extraction techniques based on TBP mixed with carbon tetrachloride (RECUPLEX). Processes at the Z Plant Complex that generated the primary waste streams into the 200-PW-1 OU waste sites included the following (it should be noted that 200-PW-1 waste sites did not receive any waste from the 231-Z Building and its operations):

- Rubber glove (RG) line: Operation was then transferred to the newly constructed 234-5 Building in 1949 and operated until 1953, when it was abandoned for remote mechanical operations. Waste generated by this process included hydrofluoric, sulfuric, and nitric acids, as well as peroxide, plutonium, and other transuranic metals.
- Remote mechanical "A" (RMA) line: The RMA line was constructed in 1949 and began operations in 1953. The RMA line operated until it was upgraded to remote mechanical C (RMC) operations. The process was the same as the RG line chemically; however, the plutonium was handled by remote mechanical means. Thus, the RMA produced the same waste as the RG line.
- Remote mechanical "C" (RMC) line: The RMC line was constructed in 1957 and began operations in 1960. The RMC operated until 1973 and again from 1985 to 1989. The process was the same as the RG and RMA lines chemically; however, the plutonium was handled remotely by mechanical means, with additional mechanical upgrades to increase the safety of the operators. Thus, the RMC produced the same waste as the RG and RMA lines.
- <u>Plutonium Metal Fabrication</u>: Weapons-grade plutonium metal was cut and milled into weapons shapes for quick assembly into nuclear weapons in the late 1950s. Waste generated by this process included mixed lard oil and carbon tetrachloride, as well as other volatile organics used as cutting fluids.
- <u>RECUPLEX</u>: This plutonium recovery process operated in the 234-5Z Building from 1955 to 1962, at which time the process was terminated after a criticality event (i.e., an

uncontrolled nuclear reaction) within the PFP. Waste generated by this process included hydroiodic, hydrofluoric, sulfuric, and nitric acids, as well as silver, carbon tetrachloride, TBP, plutonium, and other transuranic metals.

- Americium recovery: An americium recovery process operated in the 242-Z Building between 1964 and 1976. The process was shut down in 1976 after an explosion occurred in one of the recovery units. Waste generated by this process included hydrochloric, hydrofluoric, phosphoric, and nitric acids, as well as dibutyl butyl phosphonate (DBBP), carbon tetrachloride, TBP, plutonium, and other transuranic metals.
- Plutonium Reclamation Facility (PRF): In 1964, a replacement plutonium scrap solution recovery facility, the PRF, was brought on line in the 236-Z Building. The PRF operated from 1964 to 1979 and from 1984 to 1987. Waste generated by this process included hydrofluoric, phosphoric, and nitric acids, as well as silver, hydroxyl amines, DBBP, carbon tetrachloride, TBP, uranium, plutonium, and other transuranic metals.

Tables 1-1, 1-2, 1-3, and 1-4 identify the DQO scoping team members, DQO workshop team members, DQO integration team members, and key decision makers, respectively. The scoping team developed the DQO checklist and binder prior to the internal seven-step process. The DQO workshop team members participated in the seven-step DQO process. The key decision makers provided external review of the results of the seven-step process.

Table 1-1. DQO Scoping Team Members. (2 Pages)

Name	Organization	Area of Expertise (Role)	
Janet Badden CHI Regulatory Support/ Environmental Science		Regulatory	
Roy Bauer	CHI Environmental Engineering	DQO Workbook/Facilitator	
Steve DeMers	BHI Radiological Control Engineering	Radiological Control Engineering	
Bruce Ford	BHI Site Assessments	200 Area Remedial Action Task Manager	
Lyle Ivey	CHI Regulatory Support/Environmental Science	Statistician	
John Ludowise	CHI Environmental Engineering 200-PW-1 Task Lead, Proce Knowledge		
Jim Sharpe	CHI Regulatory Support/ Environmental Science Cultural/Biological Issues		
Kevin Singleton	CH2M Hill, Inc. Geosciences Technical Staff, Au		
Dave St. John	CHI Sample/Data Management Sampling Data Management/S Sampling History		
Wendy Thompson	BHI Environmental Technologies Sampling/Field Analysis		
Rich Weiss	CHI Sample/Data Management	Radiochemical and Analytical, Data Management	

Table 1-1. DQO Scoping Team Members. (2 Pages)

Name	Organization	Area of Expertise (Role)
Curt Wittreich	CHI Environmental Engineering	200 Area Remedial Action Lead
Michelle Yates	CHI Environmental Engineering	Process Chemistry, Technical Staff, Author

BHI = Bechtel Hanford, Inc. CHI = CH2M Hill Hanford, Inc.

Table 1-2. DQO Workshop Team Members.

Name	Organization	Area of Expertise (Role)	
Kim Anselm	CHI Office Services	Project Assistant/Document Control	
Janet Badden	CHI Regulatory Support	Regulatory Compliance	
Roy Bauer	CHI Environmental Engineering	DQO Facilitator/Workbook	
Bruce Ford	BHI Environmental Leads	200 Area Remedial Action Task Manager	
John Ludowise	CHI Environmental Engineering	CHI Project Lead	
Virginia Rohay	CHI Geosciences/Modeling	Technical Staff	
Jim Sharpe	CHI Environmental Engineering	Scoping - Cultural Resources	
Kevin Singleton	CH2M Hill, Inc.	Geology	
Rob Sitzler	BHI Radiological Control Engineering	neering Environmental Radiological Engineering	
Wendy Thompson	BHI Environmental Technologies	Sampling and Analysis Collection	
Rich Weiss	CHI Sample/Data Management	/Data Management Analytical Laboratory	
Curt Wittreich	CHI Environmental Engineering	CHI 200 Area Project Lead	
Michelle Yates	e Yates CHI Environmental Engineering Scoping – 200 Area Proces Chemistry		

Table 1-3. DQO Integration Team Members.

Name	Organization	Area of Expertise (Role)	
Keith Hampton	FH	241-Z-361 Settling Tank	
Virginia Rohay 200-ZP-1 and 200-ZP-2		Technical Staff/Coordination	
Craig Swanson 200-ZP-1 and 200-ZP-2 Technical Sta		Technical Staff	

Table 1-4. DQO Key Decision Makers.

Name	Name Organization Area of Expertise (Re	
Dennis Faulk	ЕРА	EPA OU Manager
Bryan Foley	DOE	DOE Project Manager

Table 1-5 lists the key sources of existing documents and data collected from previous investigations that were reviewed by the DQO team.

Table 1-5. Existing Documents and Data Sources for 200-PW-1 Operable Unit. (3 Pages)

Reference	Summary
200 Areas Remedial Investigation/Feasibility Study Implementation Plan – Environmental Restoration Program, DOE/RL-98-28, Rev. 0 (DOE-RL 1999)	Background geography, process, waste site, and COC knowledge, and strategy for the 200 Areas.
200 Areas Waste Sites Handbook, 3 vols., RHO-CD-673 (Maxfield 1979)	Waste site descriptions, releases, waste discharge information, and management reports.
1994 Conceptual Model of the Carbon Tetrachloride Contamination in the 200 West Area at the Hanford Site, WHC-SD-EN-TI-248, Rev. 0 (Rohay 1994)	Provides data summaries and analytical results from limited field investigations conducted at 216-Z-1A and 216-Z-9. Geological information and COPC, COC, and carbon tetrachloride information.
Distribution of Plutonium and Americium Beneath the 216-Z-1A Crib: A Status Report, RHO-ST-17 (Price et al. 1979)	Provides data summaries and analytical results from limited field investigations at 216-Z-1A. Contains geological, COPC, and COC information.
Report on Plutonium Mining Activities at 216-Z-9 Enclosed Trench, RHO-ST-21 (Ludowise 1978)	Provides data summaries and analytical results of plutonium inventories before and after removal at 216-Z-9. Provides logistical data of mining activities and current condition of the trench.
Nuclear Reactivity Evaluations of 216-Z-9 Enclosed Trench, ARH-2915 (Smith 1973)	Provides data summaries and analytical results of plutonium inventories at 216-Z-9 before removal.
Hanford Site Atlas, BHI-01119, Rev. 1 (BHI 1998)	Site maps.
WIDS reports for 200-PW-1: 216-T-19 Crib, 216-Z-1&2 Cribs, 216-Z-1A Tile Field, 216-Z-3 Crib, 216-Z-9 Trench, 216-Z-12 Crib, 216-Z-18 Crib, 241-Z-361 settling tank, UPR-200-W-103, UPR-200-W-110	Summarizes site names, locations, types, status, site and process descriptions, associated structures, cleanup activities, environmental monitoring description, access requirements, references, regulatory information, and waste information (e.g., type, category, physical state, description, and stabilizing activities).
Performance Evaluation Report for Soil Vapor Extraction Operations at the Carbon Tetrachloride Site, February 1992-September 1999, BHI-00720, Rev. 4 (Rohay 2000)	Provides data summaries and updated results of limited field investigations for the 200 West Area with respect to carbon tetrachloride and selected VOAs.

Table 1-5. Existing Documents and Data Sources for 200-PW-1 Operable Unit. (3 Pages)

Reference	Summary
Description of work documents for the 216-Z-9 Trench, which are currently being developed by the ERC Groundwater/Vadose Zone Integration Project (to be published)	Information on COCs. Will also provide geological and vadose zone information.
Submittal of Documentation in Fulfillment of Milestone M-15-37B, letter FH-000279, to RL, dated June 15, 2000 (FH 2000)	Information on COCs.
Hydrogeologic Conceptual Model for the Carbon Tetrachloride and Uranium/Technetium Plumes in the 200 West Area: 1994 to 1999 Update, BHI-01311, Rev. 0 (BHI 1999)	Geological and groundwater information.
DNAPL Investigation Report, BHI-00431, Rev. 0 (BHI 1995)	Geological information.
241-Z-361 Sludge Characterization Data Quality Objectives, HNF-4225, Rev. 0 (LMHC 1999)	Historical waste site and COC disposal information for 241-Z-361 tank.
216-Z-12 Transuranic Crib Characterization: Operational History and Distribution of Plutonium and Americium, RHO-ST-44 (Kasper 1982)	Historical waste site, operational, geological, and COC disposal information.
Evaluation of Scintillation Probe Profiles from 200 Area Crib Monitoring Wells, ARH-ST-156 (Fecht et al. 1977)	Geophysical logs and contaminant distribution data.
Hanford Site Groundwater Monitoring for Fiscal Year 1998, PNNL-12086 (PNNL 1999a)	Groundwater annual report information.
PNLATLAS/LG-ARCHV/200 East and West	Database for geophysical logging.
Z Plant Liquid Waste Disposal Through the 241-Z Vault, ARH-CD-323 (ARH 1976)	Historical waste site, operational, geological, and COC disposal information.
Hanford Sitewide Groundwater Remediation Strategy, DOE/RL-94-95, Rev. 1 (DOE-RL 1997a)	Groundwater and geological information.
History and Stabilization of the Plutonium Finishing Plant (PFP) Complex, Hanford Site, HNF-EP-0924 (Gerber 1997)	Historical account of process operations information for Z Plant and ancillary facilities, and feed process modifications at REDOX, PUREX, and T and B Plants. Provides information on trouble encountered, solutions implemented, chemical used, an overview of each processes' daily activities, building construction, functions, maintenance, and sampling, laboratory, and disposal activities.
200 Areas Disposal Sites for Radioactive Liquid Wastes, ARH-947 (Curren 1972)	Waste site and COC information.
Radionuclide Inventories of Liquid Waste Disposal Sites on the Hanford Site, HNF-1744 (FH 1999)	Waste site and COC information.

Table 1-5. Existing Documents and Data Sources for 200-PW-1 Operable Unit. (3 Pages)

Reference	Summary
Waste Site Grouping for 200 Areas Soil Investigations, DOE/RL-96-81, Rev. 0 (DOE-RL 1997b)	Summarizes site name, location, type status, site and process descriptions, known and suspected contamination, preliminary contaminant distribution conceptual model, site conditions that may affect COC fate and transport, COC mobility in Hanford Site soils, COC distribution and transport to groundwater, and hazards associated with COCs. Soil porosity information for each waste site.
Results of 1998 Spectral Gamma-Ray Monitoring of Boreholes at the 216-Z-1A Tile Field, 216-Z-9 Trench, and 216-Z-12 Crib, PNNL-11978 (PNNL 1999b)	Spectral gamma logging data in the 216-Z-1A Tile Field and around the 216-Z-9 Trench.
Proof-of-Principle Demonstration of a Passive Neutron Tool for Detection of TRU-Contaminated Soil at the 216-Z-1A Tile Field, BHI-01436, Rev. 0 (Bauer et al. 2000)	Gross gamma logs and passive neutron results in two boreholes in the 216-Z-1A Tile Field, confirming TRU-contaminated soils in the tile field.
Z Plant Source Aggregate Area Management Study Report, DOE/RL-91-58, Rev. 0 (DOE-RL 1992)	Soil and geological information, COPC information, process history, and geophysical logging.
HEIS database	Well information and sampling data.
Discussions with Mr. Thurman D. Cooper, PFP Chemist	Historical process and operation information and COPC listings.
Discussions with Mr. David A. Dodd, PFP Chemist	Historical process and operation information and COPC listings.
Site visit notes	Information on general site conditions.
Drawings	Construction "as-built" drawings of individual waste sites.

HEIS = Hanford Environmental Information System

PUREX = Plutonium-Uranium Extraction (Facility)

REDOX = Reduction-Oxidation (Facility)
WIDS = Waste Information Data System

Table 1-6 represents the complete, unconstrained set of COPCs that were, or could have been, discharged to the 200-PW-1 OU waste sites. The master COPC list was then evaluated against a set of exclusion rationale to determine the final list of project COCs. The COPCs that were excluded and the rationale for their exclusion are listed in Table 1-7.

Table 1-6. Sources of Contamination, COPCs, and Affected Media for the 200-PW-1 Operable Unit. (2 Pages)

Known or Suspected Contamination (1			Contamination from Each (General Contamination)	Affected Media
The 200-PW-1 OU waste sites received plutonium-rich and organic-rich wastes from the RECLUPLEX and PRF processes, PFP operations including RMA, RMC, and americium recovery operations, and laboratory wastes, all from the Z Plant Complex.		anions and amounts of levels of p americium	stes contained inorganic d cations, acidic, and large of organic waste with high blutonium and n-241, moderate amounts m, and lower amounts of oducts.	Shallow soils (0 to 4.6 m [15 ft] bgs) and deep soils (>4.6 m [>15 ft] bgs) associated with the waste sites and groundwater beneath the waste sites.
Radioactive COPCs				
Americium-241 Americium-242 Americium-243 Antimony-123 Antimony-125 Cerium-141 Cerium-144 Cesium-134 Cesium-135 Cesium-137 Cobalt-60	Curium-242 Curium-243 Curium-244 Curium-245 Lanthanum-140 Lead-212 Lead-214 Neptunium-237 Neptunium-239 Plutonium-238 Plutonium-239		Plutonium-240 Plutonium-241 Plutonium-242 Protactinium-233 Radium-224 Radium-226 Radium-228 Ruthenium-103 Ruthenium-106 Strontium-89	Strontium-90 Technetium-99 Thorium-232 Tritium Uranium-232 Uranium-233 Uranium-234 Uranium-235 Uranium-236 Uranium-238
Inorganic COPCs				<u></u>
Aluminum Aluminum fluoride Aluminum nitrate Aluminum nitrate (mono basic) Aluminum sulfate Ammonia Ammonium hydroxide Ammonium lanthanum nitrate	Ammonium oxa Ammonium fluc Ammonium sulf Arsenic nitrate Bismuth Cadmium nitrate Calcium Calcium carbona Calcium iodide Calcium fluoride	orosilicate rate	Calcium nitrate Chloride Fluoride Gallium oxide Hydrochloric acid Hydrofluoric acid Hydrofodic acid Hydrogen Hydrogen peroxide	Hydroxide Lanthanum Lanthanum fluoride Lanthanum hydroxide Lanthanum nitrate Lithium chloride Magnesium Magnesium oxide Mercury
Inorganic Chemical COP	Cs			
Nickel Nitrate Nitric acid Peroxide Phosphate Phosphoric acid Plutonium Plutonium fluoride	Plutonium dioxi Plutonium nitrat Plutonium perox Potassium perm Selenium Silver Sodium Sodium alumina	e tide anganate	Sodium bicarbonate Sodium carbonate Sodium chloride Sodium fluoride Sodium hydroxide Sodium nitrate Sodium oxalate	Sodium sulfate Sulfate Sulfuric acid Uranium Uranium dioxide Uranium trioxide Uranyl nitrate

Table 1-6. Sources of Contamination, COPCs, and Affected Media for the 200-PW-1 Operable Unit. (2 Pages)

Known or Suspected Source of Contamination (Process)		ype of Contamination from Each Jource (General Contamination)	Affected Media
Organic Chemical COPC	3		
1,1-dichloroethane (DCA) 1,2-dichloroethane (DCA) 1,1,1-trichloroethane (TCA) Benzene Carbon tetrachloride Cis-1,2-dichloroethylene Chlorobenzene	Chloroform DBBP Dibutyl phosphate Ethylbenzene Hydraulic fluids (gre Hydrogen dibutyl phosphate Hydroxylamine Hydroxylamine Hydroxhloride	Methyl ethyl ketone (MEK) Methyl iso butyl ketone (MIBK) Methylene chloride Miscellaneous cutting oils (lard and other oils) Monobutyl phosphate n-butyl benzene Normal paraffins	Oxalic acid Phenol PCBs Toluene Tetrachloroethylene (PCE) Trans-1,2-dichloroethylene TBP Trichloroethylene (TCE) Xylene

Table 1-7. 200-PW-1 Operable Unit COPC Exclusions and Justifications. (3 Pages)

COPCs	Rationale for Exclusion
Radionuclides	
Americium-242	Constituent with atomic mass number greater than or equal to 242 that represents << 1% of the activity (based on ORIGIN2 modeling of Hanford reactor production).
Americium-243	Constituent with atomic mass number greater than or equal to 242 that represents << 1% of the activity (based on ORIGIN2 modeling of Hanford reactor production).
Antimony-123	Stable.
Antimony-125	Short-lived radionuclide (half-life <3 years).
Cerium-141	Short-lived radionuclide (half-life <3 years).
Cerium-144	Short-lived radionuclide (half-life <3 years).
Cesium-134	Short-lived radionuclide (half-life <3 years).
Cesium-135	Constituent generated at less than 5E-5 times the Cs-137 activity.
Curium-242	Constituent with atomic mass number greater than or equal to 242 that represents << 1% of the activity (based on ORIGIN2 modeling of Hanford reactor production).
Curium-243	Constituent with atomic mass number greater than or equal to 242 that represents << 1% of the actinide activity (based on ORIGIN2 modeling of Hanford reactor production).
Curium-244	Constituent with atomic mass number greater than or equal to 242 that represents less than 1% of the activite. May be reported via americium isotopic analysis.
Curium-245	Constituent with atomic mass number greater than or equal to 242 that represents << 1% of the activity (based on ORIGIN2 modeling of Hanford reactor production).
Lanthanum-140	Short-lived radionuclide (half-life <3 years).
Neptunium-239	Short-lived radionuclide (half-life <3 years).
Plutonium-241	Not detected by normal plutonium analysis, can infer from americium/plutonium results.

Table 1-7. 200-PW-1 Operable Unit COPC Exclusions and Justifications. (3 Pages)

COPCs	Rationale for Exclusion
Plutonium-242	Constituent with atomic mass number greater than or equal to 242 that represents << 1% of the activity (based on ORIGIN2 modeling of Hanford reactor production).
Protactinium-233	Even though Pa-233 was detected during spectral gamma logging performed at boreholes in the representative sites referenced by Price et al. (1979), it is a daughter product and can be calculated from Np-237.
Radium-224	Value can be calculated from Th-232 if present.
Radium-226	GEA will report if detectable quantities are present.
Radium-228	GEA will report if detectable quantities are present.
Ruthenium-103	Short-lived radionuclide (half-life <3 years).
Ruthenium-106	Short-lived radionuclide (half-life <3 years).
Strontium-89	Short-lived radionuclide (half-life <3 years).
Uranium-232	<2E-3 times the U-238 activity.
Uranium-233	Measurement cannot resolve U-233 + U-234 isotopes, reported as U-234 or U-233/234.
Uranium-236	Measurement cannot resolve U-235 + U-236 isotopes, reported as U-235.
Inorganics	
Aluminum	This inorganic substance is unlikely to be present in toxic concentrations. Routine analyte reported by ICP analysis.
Bismuth	This inorganic substance is unlikely to be present in toxic concentrations.
Calcium	This inorganic substance is unlikely to be present in toxic concentrations. Routine analyte reported by ICP analysis.
Carbonate(axb)	This inorganic substance is unlikely to be present in toxic concentrations.
Gallium	This inorganic substance is unlikely to be present in toxic concentrations.
Hydrogen	Gas.
Hydroxide	Assessed via pH determination.
Iodine	This inorganic substance is unlikely to be present in toxic concentrations.
Iron	This inorganic substance is unlikely to be present in toxic concentrations. Routine analyte reported by ICP analysis.
Lanthanum	This inorganic substance is unlikely to be present in toxic concentrations.
Lithium	This inorganic substance is unlikely to be present in toxic concentrations. Routine analyte reported by ICP analysis.
Magnesium	This inorganic substance is unlikely to be present in toxic concentrations. Routine analyte reported by ICP analysis.
Manganese	This inorganic substance is unlikely to be present in toxic concentrations. Routine analyte reported by ICP analysis.
Peroxide	Has degraded.

Table 1-7. 200-PW-1 Operable Unit COPC Exclusions and Justifications. (3 Pages)

COPCs	Rationale for Exclusion		
Potassium	This inorganic substance is unlikely to be present in toxic concentrations. Routine analyte reported by ICP analysis.		
Silicon	This inorganic substance is unlikely to be present in toxic or high concentrations due minimal use in Hanford 200 Area processes.		
Sodium	This inorganic substance is unlikely to be present in toxic concentrations. Routine analyte reported by ICP analysis.		
Organics			
Dibutyl butyl phosphonate	DBBP was widely used as a solvent during the PRF americium recovery operations. No direct standard analytical procedure available. Will degrade to phosphate and detected in those analytical measurements.		
Dibutyl phosphate	No direct standard analytical technique available. This compound is a degradation product of TBP and is unlikely to be present in toxic or high concentrations. This compound will be detected as TBP (TIC).		
Hydroxylamine	No direct standard analytical technique available. Hydroxylamine was used during the PRF processes.		
Hydroxylamine hydrochloride	No direct standard analytical technique available. Hydroxylamine hydrochloride was used during the PRF processes.		
Miscellaneous cutting oils (lard and other oils)	No direct standard analytical technique available. These compounds are not likely to be present in toxic or high concentrations. They may, however, be detected by the analyses performed for the hydraulic fluids or the normal paraffins.		
Monobutyl phosphate	No direct standard analytical technique available. This compound is a degradation product of TBP and is unlikely to be present in toxic or high concentrations. This compound will be detected as TBP (TIC).		
Oxalate	Oxalate and oxalic acids were used during the plutonium isolation (RG, RMA, and RMC) operations. No direct standard analytical technique available. Oxalate has dissolved to a complexing agent that could have affected the mobility of certain COCs. Unexpected mobility of COCs will indicate the presence of complexants.		

GEA = gamma energy analysis ICP = inductively coupled plasma TIC = tentatively identified compound

Based on a review of process, operations, and waste discharge information from various sources (Table 1-5), the chemical behavior of the constituents was evaluated. Process knowledge indicates that the 200-PW-1 OU waste streams were predominantly liquid effluent discharges from the plutonium purification by solvent extraction processes performed at Z Plant. In general, the waste generated can be described as plutonium and organic-rich, discharged mainly from the RECLUPLEX and PRF processes. Additional waste streams from PFP operations included the RG line, remote mechanical (RMA and RMC) operations, the americium recovery process, and laboratory waste. This waste contained inorganic anions and cations, acids, and large amounts of organic waste with high levels of plutonium and americium-241, moderate amounts of uranium, and lower amounts of fission products.

The first step in the evaluation process involved extracting known toxic materials from the master COPC list for placement on the final COC list. Inorganic salts and acids represent a large group of constituents in the waste sites being evaluated. Because laboratory analyses are generally not acid- or compound-specific, the acids and inorganic salts were excluded from further consideration. Instead, the readily detected cations and anions (e.g., metals, fluorides, and nitrates) associated with the acids and inorganic salts serve as the target constituents for those compounds. This logic recognizes the small volumes of hazardous and radiological constituents released into large-volume aqueous discharges.

The analytical approach employed for this project generally targets the significant risk drivers that are representative of the waste constituents present. The general suite-type analytical techniques yield results on many metals and organic compounds, providing a cost-effective approach for the known toxic materials that could be present.

The COPCs in the following categories were excluded from further consideration:

- Short-lived radionuclides with half-lives less than 3 years
- Radionuclides that constitute less than 1% of the fission product inventory and for which historical sampling indicates nondetection
- Naturally occurring isotopes that were not created as a result of Hanford Site operations
- Constituents with atomic mass numbers greater than 242 that represent less than 1% of the activities
- Progeny radionuclides that build insignificant activities within 50 years and/or for which parent/progeny relationships exist that permit progeny estimation
- Constituents that would be neutralized and/or decomposed by facility processes
- Chemicals in a gaseous state that cannot accumulate in soil media
- Chemicals used in minor quantities relative to the bulk production chemicals consumed in the normal processes; these chemicals are not likely to be present in toxic or high concentrations
- Chemicals that are not persistent in the environment due to biological degradation or other natural mitigating features.

Table 1-8 includes the final list of COCs for the 200-PW-1 OU waste sites, with the rationale for inclusion for each of the COCs.

Table 1-8. 200-PW-1 Operable Unit Final COC List. (4 Pages)

Final COCs	Rationale for Inclusion	
Radiological Constituents		
Americium-241	Known production from fission reaction and listed via tank farm integration (Agnew et al. 1997, Borsheim and Simpson 1991). Analytical results from sediment samples collected within the 241-Z-361 tank (FH 2000).	
Cesium-137	Known fission product (GE 1944 [Sections A, B, and C], GE 1951b).	
Cobalt-60	Known fission product (GE 1944 [Sections A, B, and C], GE 1951b, WHC 1991).	
Hydrogen-3 (tritium)	Known fission product and listed via tank farm integration (Agnew et al. 1997, Borsheim and Simpson 1991).	
Neptunium-237	Known production from fission reaction and listed via tank farm integration (Agnew et al. 1997, Borsheim and Simpson 1991). Analytical results from sediment samples collected within the 241-Z-361 tank (FH 2000).	
Plutonium-238	Known production from fission reaction (GE 1944, Sections A, B, and C). Analytical results from sediment samples collected within the 241-Z-361 tank (FH 2000).	
Plutonium-239	Known production from fission reaction (GE 1944, Sections A, B, and C). Analytical results from sediment samples collected within the 241-Z-361 tank (FH 2000).	
Plutonium-240	Known production from fission reaction (GE 1944, Sections A, B, and C). Analytical results from sediment samples collected within the 241-Z-361 tank (FH 2000).	
Strontium-90	Known fission product (GE 1944 [Sections A, B, and C], GE 1951b). Analyzed as total radioactive strontium. Analytical results from sediment samples collected within the 241-Z-361 tank (FH 2000).	
Technetium-99	Known fission product (GE 1944 [Sections A, B, and C], WHC 1991). Analytical results from sediment samples collected within the 241-Z-361 tank (FH 2000).	
Thorium-232	Known production from fission reaction (GE 1944 [Sections A, B, and C], FH 1999).	
Uranium-234	Known feed from fission reaction (GE 1944, Sections A, B, and C).	
Uranium-235	Known feed from fission reaction (GE 1944, Sections A, B, and C). Analytical results from sediment samples collected within the 241-Z-361 tank (FH 2000).	
Uranium-238	Known feed from fission reaction (GE 1944, Sections A, B, and C).	
Nonradiological Constituen	ts – Metals	
Arsenic	Analytical results from sediment samples collected within the 241-Z-361 tank (FH 2000).	
Analytical results from sediment samples collected at wells near 200-PW-1 sites (Rohay 1994). Analytical results from sediment samp collected within the 241-Z-361 tank (FH 2000).		

Table 1-8. 200-PW-1 Operable Unit Final COC List. (4 Pages)

Final COCs	Rationale for Inclusion	
Chromium	Analytical results from sediment samples collected at wells near 200-PW-1 sites (Rohay 1994). Analytical results from sediment samples collected within the 241-Z-361 tank (FH 2000).	
Chromium (VI)	Analytical results from sediment samples collected at wells near 200-PW-1 sites (Rohay 1994).	
Copper	Analytical results from sediment samples collected at wells near 200-PW-1 sites (Rohay 1994).	
Lead	Analytical results from sediment samples collected at wells near 200-PW-1 sites (Rohay 1994). Analytical results from sediment samples collected within the 241-Z-361 tank (FH 2000).	
Mercury	Analytical results from sediment samples collected within the 241-Z-361 tank (FH 2000).	
Nickel	Analytical results from sediment samples collected at wells near 200-PW-1 sites (Rohay 1994). Analytical results from sediment samples collected within the 241-Z-361 tank (FH 2000).	
Selenium	Analytical results from sediment samples collected within the 241-Z-361 tank (FH 2000).	
Silver	Analytical results from sediment samples collected at wells near 200-PW-1 sites (Rohay 1994). Analytical results from sediment samples collected within the 241-Z-361 tank (FH 2000).	
Nonradiological Constituent	s – General Inorganics	
Ammonia/ammonium	Several compounds contained ammonium. The most widely used included ammonium silica fluoride, which was used as a cleaning and decontamination compound based on the ability to dissolve metals and fission products (GE 1944 [Section C], GE 1951b, HEW 1945). Also used in PRF processes (discussions/publications by Thurman D. Cooper, PFP Chemist). Analytical results from sediment samples collected within the 241-Z-361 tank (FH 2000).	
Several compounds contained chloride. The most widely used inclu Lithium chloride, which was used as a salting agent, and hydrochlor which was used as a carrier during the americium recovery operation (discussions/publications by Thurman D. Cooper, PFP Chemist). A residual waste from the bismuth-phosphate process (GE 1944 [Secti GE 1951b, HEW 1945). Analytical results from sediment samples of within the 241-Z-361 tank (FH 2000).		
Several compounds contained fluoride the most widely used include hydrofluoric acid, a stripping solvent used in the RG, RMA, RECLU PRF, and americium recovery operations (discussion/publications by Thurman D. Cooper, PFP Chemist). Lanthanum fluoride (which was during the concentration operations of the bismuth-phosphate process also a large carry-over waste product (GE 1944 [Section C], GE 1951 (HEW 1945). Analytical results from sediment samples collected with 241-Z-361 tank (FH 2000).		

Table 1-8. 200-PW-1 Operable Unit Final COC List. (4 Pages)

Final COCs	Rationale for Inclusion	
Nitrate/nitrite	Several compounds contained nitrates/nitrites the most widely used included nitric acid, a stripping solvent used in the RG, RMA, RECLUPLEX, PRF, and americium recovery operations (discussion/publications by Thurman D. Cooper, PFP Chemist). Nitric acid and various salts were also used throughout the bismuth-phosphate, Uranium Recovery Project, REDOX, and PUREX processes to isolate plutonium from various fission products (GE 1944 [Section C], GE 1951a, GE 1951b, GE 1955). Analytical results from sediment samples collected within the 241-Z-361 tank (FH 2000).	
Phosphate	Several compounds contained phosphate. The most widely used included TBP and its derivatives and DBBP, which was used RECLUPLEX, PRF, and americium recovery operations (discussion/publications by Thurman D. Cooper, PFP Chemist). Analytical results from sediment samples collected within the 241-Z-361 tank (FH 2000).	
Sulfate	Several compounds contained sulfate. The most widely used included sulfuric acid, which was used as a persulfate-leaching step in the RECLUPLEX, PRF, and americium recovery operations (discussion/publications by Thurman D. Cooper, PFP Chemist). Analytical results from sediment samples collected within the 241-Z-361 tank (FH 2000).	
Volatile Organics		
1,1-dichloroethane (DCA)	Analytical results and measurements have illustrated that this contaminant is found throughout the vadose zone (Rohay 1994).	
1,2-dichloroethane (DCA)	Analytical results and measurements have illustrated that this contaminant is found throughout the vadose zone (Rohay 1994).	
1,1,1-trichloroethane (TCA)	Analytical results and measurements have illustrated that this contaminant is found throughout the vadose zone (Rohay 1994).	
Acetone	Analytical results and measurements have illustrated that this contaminant is found throughout the vadose zone (Rohay 1994).	
Benzene	Analytical results and measurements have illustrated that this contaminant is found throughout the vadose zone (Rohay 1994).	
Carbon tetrachloride	Carbon tetrachloride was widely used as a dilutant for TBP and DBBP in the RECUPLEX, PRF, and americium-241 recovery processes. Analytical results and measurements have illustrated that this contaminant is prevalent throughout the vadose zone and has impacted groundwater (Rohay 1994).	
Cis-1,2-dichloroethylene	Analytical results and measurements have illustrated that this contaminant is found throughout the vadose zone (Rohay 1994).	
Chlorobenzene	Analytical results and measurements have illustrated that this contaminant is found throughout the vadose zone (Rohay 1994).	
Chloroform	Chloroform is a degradation product of carbon tetrachloride. Analytical results and measurements have illustrated that this contaminant is prevalent throughout the vadose (Rohay 1994).	
Ethylbenzene	Analytical results and measurements have illustrated that this contaminant is found throughout the vadose zone (Rohay 1994).	

Table 1-8. 200-PW-1 Operable Unit Final COC List. (4 Pages)

Final COCs	Rationale for Inclusion	
Hydraulic fluids (greases)	Several types of hydraulic fluids were used during the milling and cutting of plutonium buttons and/or rods.	
Methyl ethyl ketone (MEK)	Analytical results and measurements have illustrated that this contaminant is prevalent throughout the vadose zone (Rohay 1994).	
Methyl iso butyl ketone (MIBK)	Analytical results and measurements have illustrated that this contaminant is prevalent throughout the vadose zone (Rohay 1994).	
Methylene chloride	Analytical results and measurements have illustrated that this contaminant is prevalent throughout the vadose zone (Rohay 1994).	
n-butyl benzene	Analytical results and measurements have illustrated that this contaminant is found throughout the vadose zone (Rohay 1994).	
Toluene	Analytical results and measurements have illustrated that this contaminant is found throughout the vadose zone (Rohay 1994).	
Tetrachloroethylene (PCE)	Analytical results and measurements have illustrated that this contaminant is found throughout the vadose zone (Rohay 1994).	
Trans-1,2-dichloroethylene	Analytical results and measurements have illustrated that this contaminant is found throughout the vadose zone (Rohay 1994).	
Trichloroethylene (TCE)	TCE is a degradation product of carbon tetrachloride. Analytical results and measurements have illustrated that this contaminant is prevalent throughout the vadose zone and has impacted groundwater (Rohay 1994).	
Xylene	Analytical results and measurements have illustrated that this contaminant is found throughout the vadose zone (Rohay 1994).	
Semi-Volatile Organics		
Normal paraffins (greases and oils)	Various types of normal paraffins were used as milling, cutting, and washing solutions during the production of plutonium buttons/rods.	
PCBs	Various types of normal paraffins were used as milling, cutting, and washing solutions during the production of plutonium buttons/rods. These solutions almost always contained PCBs (discussions/publications with David A. Dodd, PFP Chemist). Analytical results from sediment samples collected within the 241-Z-361 tank (FH 2000).	
Phenol	Analytical results and measurements have illustrated that this contaminant is found throughout the vadose zone (Rohay 1994).	
TBP and derivatives (mono, bi) Extensive use in solvent extraction operation of RECLUPLE americium recovery operations (discussions/publications wi Dodd, PFP Chemist). Analytical results from sediment sam within the 241-Z-361 tank (FH 2000).		

The final COC list for this DQO process was developed for the representative waste sites. Process knowledge indicates that this list is also appropriate for the analogous sites within the 200-PW-1 OU. It should be noted, however, that the 216-T-19 Crib received unique T Plant second-cycle bismuth/phosphate wastes in addition to the Z Plant wastes. Screening the master list of COPCs for the 216-T-19 Crib would result in the addition of the following unique

contaminants to Table 1-8: carbon-14, europium-152, europium-154, europium-155, and nickel-63. Because these constituents are not associated with the representative sites, the samples collected during remedial characterization will not include these analytes. This unique condition will be addressed during the confirmatory sampling performed in the remedial design phase for the 216-T-19 Crib.

Table 1-9 defines the ARARs and preliminary remediation goals (PRGs) for each COC.

Table 1-9. List of Preliminary ARARs and PRGs. (2 Pages)

COCs	Preliminary ARARs	PRGs	
Radionuclides Inside the 200 Area Industrial Land-Use Boundary a			
Shallow zone (0 to 4.6 m [0 to 15 ft] bgs)	15 to 500 mrem/yr above background ^b via industrial land-use scenario while under DOE control; 15 mrem/yr above background at the end of the exclusive-use period if DOE control is relinquished; 4 mrem/yr above background to groundwater; or no additional groundwater degradation.	Contaminant-specific; RESRAD modeling ^c	
Deep zone (>4.6 m [>15 ft] bgs)	4 mrem/yr above background to groundwater, or no additional groundwater degradation.	MCLs, state and Federal ambient water quality control criteria; alternatively, site-specific modeling	
Nonradiological Constituents Inside	e the 200 Area Industrial Land-Use Bo	undary	
Shallow zone (0 to 4.6 m [0 to 15 ft] bgs)	MTCA Method C, and 100 times groundwater	Chemical-specific	
Deep zone (>4.6 m [>15 ft] bgs)	100 times groundwater (in accordance with MTCA)	Alternatively, site-specific modeling	
TRU Waste Definition			
Any depth zone	Radioactive waste containing more than 100 nCi of alpha-emitting transuranic isotopes per gram of waste, with half-lives greater than 20 years except for (1) high-level radioactive waste; (2) waste that the Secretary of Energy has determined, with the concurrence of the Administrator of the EPA, does not need the degree of isolation required by the 40 CFR 191 disposal regulations; or (3) waste that the U.S. Nuclear Regulatory Commission has approved on a case-by-case basis in accordance with 10 CFR 61.	Contaminant-specific	

Table 1-9. List of Preliminary ARARs and PRGs. (2 Pages)

COCs	Preliminary ARARs	PRGs		
Greater Than Class C Waste				
Any depth zone	10 CFR 61.55	Contaminant-specific		

Based on Final Hanford Comprehensive Land Use Plan Environmental Impact Statement (DOE 1999) (see Figure 1-1).

bgs = below ground surface
CFR = Code of Federal Regulations
MCL = maximum contamination level
RESRAD = RESidual RADioactivity dose model

Table 1-10 lists the general exposure scenarios.

Table 1-10. General Exposure Scenarios.

Scenario No.	General Exposure Scenario Description
	Industrial land-use scenario (inside the 200 Area land-use boundary)*:
	The source of contamination in the 200-PW-1 OU is the liquid effluent disposed to the waste sites. The near-term release mechanism is direct radiation exposure to occupational workers in the vicinity of the waste sites (although shielded by stabilizing cover). Ingestion and inhalation of surface or subsurface soils in an occupational scenario does not represent a substantial exposure due to waste site surface stabilization and the limited soil ingestion and inhalation anticipated during excavation activities in an industrial setting (e.g., use of dust control measures limits exposures). Downward migration of mobile constituents into the groundwater would not affect occupational workers, as their drinking water source would not be the underlying aquifers. However, the protection of groundwater is a requirement and must be addressed by evaluating potential future impacts.
1	The exposure time is divided into time spent inside and outside an industrial facility:
:	• Building occupancy: 8 hours/day x 0.6 (building occupancy factor), 5 days/week, 50 weeks/yr, for 20 years (of a 75-year lifetime).
	Outdoor exposure: 8 hours/day x 0.4 (outdoor exposure factor), 5 days/week, 50 weeks/yr, for 20 years (of a 75-year lifetime).
:	In addition, the building occupancy exposure includes a factor of 0.4 to reduce the ingested dust component due to building ventilation system filtration.
i	Biota that may be exposed to contaminants is this OU will be addressed under a separate 200 Area-wide evaluation. Remedial actions to address human health concerns will also serve to protect biota.

The Final Hanford Comprehensive Land Use Plan Environmental Impact Statement (DOE 1999) (see Figure 1-1) identifies the actual and near future (50-yr) land use within the 200 Area land-use boundary as industrial (exclusive) and would center mainly on waste management activities.

b The 200 Area radionuclide cleanup standard for the industrial land-use scenario has not been established. This will be agreed upon in the ROD. The EPA is currently evaluating cleanup standards that range from 15 to 500 mrem/yr above background.

RESRAD has been used for similar waste sites and will be used as a minimum for direct exposure. If more appropriate models are developed, the models will be evaluated for use.

^d Working definition of TRU waste as stated in DOE Guide 435.1.

Table 1-11 provides the regulatory milestones and regulatory drivers associated with this project.

Table 1-11. Regulatory Milestones.

Milestone	Due Date	Regulatory Driver
M-13-26	June 29, 2001	Tri-Party Agreement milestone to submit 200-PW-1 Plutonium Rich/Organic Rich Waste Group work plan (Draft A) to EPA.

The project milestones and their drivers are listed in Table 1-12.

Table 1-12. Project Milestones.

Milestone	Due Date	Driver	
Internal DQO workshop	January 15, 2001	DQO schedule	
External DQO briefing	February 15, 2001		
Issue DQO summary report	February 28, 2001	DQO documentation	

As noted in the project assumptions, the DQO scoping team concurred on selection of representative waste sites for the 200-PW-1 OU.

Table 1-13 combines the relevant background information into a concise statement of the problem to be resolved for this DQO process.

Table 1-13. Preliminary Conceptual Contaminant Distribution Model Discussion and Concise Statement of the Problem. (3 Pages)

Preliminary Conceptual Contaminant Distribution Model*:

Plutonium-rich and organic-rich waste streams associated with the plutonium recovery processes at the Z Plant Complex were discharged to the 200-PW-1 OU waste sites. The Z Plant Complex was used to process plutonium nitrate solutions into plutonium oxide and plutonium metal. These process streams contained recoverable quantities of plutonium that were reclaimed during RECLUPLEX and PRF operations. This waste also contained inorganic anions and cations, acids, large amounts of organic waste, high amounts of plutonium and americium-241, moderate amounts of uranium, and lower amounts of fission products. Additional waste streams were generated from the americium recovery operations and the Z Plant laboratory. The RECLUPLEX and PRF are primary sources of carbon tetrachloride in the 200-West Area.

Waste streams discharged at the 200-PW-1 OU waste sites contained a variety of constituents, including carbon tetrachloride, americium, plutonium, and uranium. The organic solutions, which contained carbon tetrachloride as DNAPL, constituted 4% to 8% of the total volume of liquid waste discharged. The predominant discharge was an acidic, high-salt (sodium nitrate) solution composed primarily of nitric acid, fluoride, nitrate, and phosphate, containing plutonium and americium with an organic content of less than 1% dissolved carbon tetrachloride.

Table 1-13. Preliminary Conceptual Contaminant Distribution Model Discussion and Concise Statement of the Problem. (3 Pages)

Effluent and contaminants (carbon tetrachloride as DNAPL and in the dissolved aqueous form, plutonium-239/240, americium-241, and uranium) were discharged directly to the soil column at liquid waste receiving sites. The wetting front and contaminants infiltrated the soil column. Effluent and contaminant(s) migration is predominately vertically downward beneath the waste site. Lateral spreading is primarily associated with finer grained strata. Older, poorly sealed wells that perforate the Plio-pleistocene Unit and/or penetrate the water table may provide a localized vertical conduit for fluids along the outside well casing. Clastic dikes and discontinuous sand- and gravel-filled randomly oriented features also provide preferential pathways for solution movement through the finer strata. Carbon tetrachloride migrates through the vadose zone under its own hydraulic gradient. As DNAPL migrates downward, part of the liquid carbon tetrachloride will be held as residual liquid (i.e., DNAPL, dissolved, and absorbed phases) in the soil pores by capillary forces. In addition, some of the liquid carbon tetrachloride will be retained in the vadose zone through mechanisms such as sorption to soil (adsorbed phase) and entrapment of DNAPL/dissolved liquids in dead-end pore spaces. Residual contamination of both phases will be left along the contaminant migration path. Carbon tetrachloride also volatilizes from the DNAPL and aqueous phase to form a vapor phase in the soil pore space. Vapor phase migration is by molecular diffusion and advection. Sediment density, stratification, and variability also influence fluid and vapor migration patterns.

All carbon tetrachloride phases (except DNAPL) have been found throughout the vadose zone beneath the representative sites (Rohay 2000). The highest carbon tetrachloride concentration in sediment samples collected was 37.8 ppm and 6.6 ppm beneath 216-Z-9 Trench and 216-Z-1A Tile Field, respectively. At both locations, maximum concentrations are associated with the interbedded sands and silts of the Hanford formation lower fine unit, laminated silts of the Plio-pleistocene Unit, and/or the top of the caliche. Other volatile organic compounds detected include methylene chloride, chloride, trichloroethylene (TCE), tetrachloroethylene (PCE), trans-1,2-DCE, 1,1-DCA, 1,2-DCA, cis-1,2-DCE, 1,1,1 TCA, benzene, xylenes, and toluene (Rohay 2000).

Plutonium and americium are typically retained in the upper few meters of the soil column (WHC 1993) when released in a dissolved aqueous phase. Because of their large distribution coefficients (K_ds), they normally adsorb strongly to Hanford soils. At the 216-Z-1A Tile Field, these radionuclides were discharged as co-contaminants with the DNAPL-complexant mixture (TBP) and are found deep within the vadose zone. Contaminants such as tritium and nitrate with low K_ds are not readily adsorbed on soil particles and migrate with the wetting front. The maximum vertical extent of plutonium and americium contamination in 1979 was interpreted to be located approximately 30 m (98 ft) below the bottom of the crib and 30 m (98 ft) above the 1978 water table (Price et al. 1979). Year 2000 depth-to-water measurements indicated that the surface of the water has dropped 3.4 m (11 ft). Spectral gamma performed in the 1990s indicated that radiological contamination may extend to 37 m (121 ft). The estimated lateral extent of radiological contamination is located within a 10-m (32.8-ft)-wide zone encompassing the perimeter of the crib (Price et al. 1979). The distribution of contaminants deep within the vadose zone suggest that plutonium and americium mobility is highly enhanced in the presence of carbon tetrachloride, TBP and derivatives, acidic liquid waste effluents, and other complexants. The exact transport mechanism of the observed plutonium/americium is not known at this time. Further investigation is needed.

More than half of the waste sites in the 200-PW-1 OU received small quantities of effluent relative to estimated soil pore volumes. The effluent volume discharged to the 216-Z-1A Tile Field is 12% of the estimated soil pore volume. The 216-Z-9 Trench received 142% of its estimated soil pore volume. This information suggests that the wetting front has migrated through the vadose zone beneath the 216-Z-9 Trench and has reached the water table. The wetting front may not have reached groundwater at the 216-Z-1A Tile Field.

Table 1-13. Preliminary Conceptual Contaminant Distribution Model Discussion and Concise Statement of the Problem. (3 Pages)

Only the dissolved phase of carbon tetrachloride has been detected in groundwater. The plume of dissolved carbon tetrachloride extends over 11 km^2 (4.4 mi^2) in the unconfined aquifer underlying the 200 West Area. The area of highest concentrations ($4,000 \text{ to } 8,000 \mu g/L$) in the past included the 216-Z-9 Trench. Carbon tetrachloride discharged to the trench may be providing a continuous source of contamination to groundwater. The distribution of carbon tetrachloride vapor below the Plio-pleistocene layer suggests that these vapors may have volatilized from the dissolved groundwater plume throughout the 200-West Area (Rohay 2000). Major nonradiological groundwater plumes in the vicinity of representative sites in addition to carbon tetrachloride include chloroform, trichloroethylene, and nitrate. There are no major radiological plumes in the vicinity of representative sites (PNNL 2000).

The preliminary conceptual contaminant distribution models for 200-PW-1 OU, the 216-Z-1A Tile Field, and the 216-Z-9 Crib are shown in Figures 1-3, 1-4, and 1-5, respectively.

DQO Approach:

The DQO process for the 200-PW-1 OU is being performed to determine if representative sites have been contaminated to levels that require remedial action.

The outcome of the characterization being developed in this DQO process for the representative sites will be applied to the other analogous sites. A SAP will be developed after completion of the DQO process, which will specify the sampling and analyses to be performed for characterization of the five representative sites.

All of the waste sites associated with this OU are located within the 200 Area industrial land-use boundary line and will be evaluated on the basis of future industrial uses.

Problem Statement:

The problem is to determine contaminant concentrations and soil physical parameters in the representative sites to support evaluation of remedial alternatives in the FS and to verify or refine the conceptual contaminant distribution models.


The preliminary conceptual contaminant distribution model will become the conceptual contaminant distribution model after acceptance of this DQO summary report and will then be applied to the project work plan.

POTENTIAL RECEPTORS Unitively exposure pathway Likely exposure pathway LEGEND Dermal Contact Conceptual Exposure Pathway Model Surface Soils Subeurlace Solls Radioactive Decay Excavation Settling Tank Trenches **5** Weste from Z-Plant Operations

Figure 1-3. Conceptual Exposure Model for the 200-PW-1 Operable Unit.

Rev. 0

Figure 1-4. Preliminary Conceptual Contaminant Distribution Model for the 216-Z-1A Tile Field.



- 1 Plutonium/organic rich process wastes were discharged to the 216-Z-1A Tile Field between 1949 and 1969. The tile field received 6.2 x 10⁶ L of high-salt acidic liquid waste that contained 57 kg plutonium, 3.4 kg americum, and approximately 268,000 kg carbon tetrachloride.
- 2 Effluent and contaminants were released to the environment near the bottom of the tile field through a herringbone arrangement of pipes into the H₁ soils.
- The wetting front and contaminants move vertically beneath the tile field. There is little or no lateral spreading unless it is associated with the Plio-Pleistocene Unit or fine-grained lenses in the Hanford formation. However, a vapor phase of carbon tetrachloride is present throughout the vadose zone in the source area.
- Older boreholes, and possibly clastic dikes, may provide preferential pathways through the vadose zone.
- (5) Constituents with large distribution coefficients, such americium and plutonium, sorb to soils with higher concentrations near the discharge pipe at the bottom of the tile field. These constituents are typically not detected deep within the vadose zone. Beneath the tile field, radionuclides were detected to a depth of 30 to 37 m. The distribution of these contaminants deep within the vadose zone indicate that plutonium and americium mobility is highly enhanced in the presence of carbon tetrachloride, TBP and derivatives, acidic liquid waste, and other complexants discharged. Their concentrations generally decrease with depth.
- (6) Carbon tetrachloride is present throughout the vadose zone beneath the 216-Z-1A Tile Field. As determined from sample and empirical data, carbon tetrachloride exist as a vapor (6A), dissolved aqueous phase in the effluent discharged (6B), dissolved aqueous phase produced from soil vapor (6C), dissolved aqueous phase from DNAPL and the absorbed phase (6D), and DNAPL and the adsorbed phase (6E). The presence of DNAPL has not been confirmed in soil samples.
- (7) The highest concentration of carbon tetrachloride is detected associated with Plio-Pleistocene Unit.
- (8) The effluent volume discharged (12% of the soil pore volume) to the tile field suggest that groundwater may not have been directly impacted by the wetting front unless a preferential pathway is present. Carbon tetrachloride in the groundwater may be associated with soil vapor phase, preferential movement, and adjacent facilities.

E0102036.2




Figure 1-5. Preliminary Conceptual Contaminant Distribution Model for the 216-Z-9 Trench.

- 1 Plutonium/organic rich process wastes were discharged to the 216-Z-9 trench between 1955 and 1962. The trench received 4.09 x 10⁶ L of high-salt acidic waste water that contained approximately 47 kg plutonium, 8.5 kg americium, 0.05 kg uranium, and 1.32 to 4.77 x 10⁵ kg carbon tetrachloride.
- 2 Effluent and contaminants were released to the environment at the bottom of an acid-resistant, tile-lined trench. The bottom of the trench is in H₁.
- 3 The wetting front and contaminants move vertically beneath the crib. There is little or no lateral spreading unless it associated with the Plio-Pleistocene Unit or fine-grained lenses in the Hanford formation. However, a vapor phase of carbon tetrachloride is present throughout the vadose zone in the source
- (4) Older boreholes, and possibly clastic dikes, may provide preferential pathways through the vadose zone.
- 6 Constituents with large distribution coefficients, such americium and plutonium, sorb to soils with higher concentrations near the discharge pipe at the bottom of the trench. These constituents typically are not detected deep within the vadose zone. Beneath the trench, these contaminants were detected to a depth of 36.9 m. The distribution of these contaminants deep within the vadose zone indicate that plutonium and americium mobility is highly enhanced in the presence of carbon tetrachloride, TBP and derivatives, acidic liquid waste, and other complexents discharged. Their concentrations generally decrease with depth.
- © Carbon tetrachloride is present throughout the vadose zone beneath the 216-Z-9 Trench. As determined from sample and empirical data, carbon tetrachloride exists as a vapor (6A), dissolved aqueous phase in the effluent discharged (6B), dissolved aqueous phase produced from soil vapor (6C), dissolved aqueous phase from DNAPL and the absorbed phase (6D), and DNAPL and the adsorbed phase (6E). The presence of DNAPL has not been confirmed in soil samples.
- The highest concentration of carbon tetrachloride is detected associated with Plic-Pleistocene Unit.
- The effluent volume discharged (142% of the soil pore volume) and presence of carbon tetrachloride in groundwater indicates that waste disposal practices at the crib have impacted the aquifer. Plutonium and americium have occasionally been detected in the groundwater near the trench.

2.0 STEP 2 - IDENTIFY THE DECISION

The purpose of DQO Step 2 is to define all of the principal study questions (PSQs) that need to be resolved to address the problems identified in DQO Step 1 and the alternative actions (AAs) that would result from resolution of the PSQs. The PSQs and AAs are then combined into decision statements (DSs) that express a choice among AAs. Table 2-1 presents the task-specific PSQs, AAs, and resulting DSs. This table also provides a qualitative assessment of the severity of the consequences of taking an incorrect AA. This assessment takes into consideration human health and the environment (flora/fauna) and political, economic, and legal ramifications. The severity of the consequences is expressed as low, moderate, or severe.

Table 2-1. Summary of DQO Step 2 Information. (2 Pages)

PSQ- AA#	Alternative Action	Consequences of Erroneous Actions	Severity of Consequences		
PSQ #1	PSQ #1 - Are the contaminant concentrations TRU or greater than Class C?				
1-1	Evaluate special remedial alternatives in a FS.	Low			
1-2	Evaluate conventional remedial alternatives in a FS.				
special	remedial alternatives in a FS,	minant concentrations are TRU or greater than Class C or evaluate conventional remedial alternatives in a FS.	and evaluate		
PSQ #2	2 – Is the soil radiologically c	ontaminated?			
2-1	Evaluate remedial alternatives in a FS.	The site may be inappropriately remediated resulting in unnecessary expenditure of funds.	Low		
2-2	Evaluate the site for closure with no remedial action.	The site may inappropriately be closed without remedial action, increasing risks of potential exposure to workers and the environment.	Severe		
	- Determine whether the soil is te the site for closure with no re	s radiologically contaminated and evaluate remedial alte emedial action.	ernatives in a FS, or		
PSQ #	3 – Is the soil chemically cont	aminated?			
3-1	Evaluate remedial alternatives in a FS.	The site may be inappropriately remediated resulting in unnecessary expenditure of funds.	Low		

Table 2-1. Summary of DQO Step 2 Information. (2 Pages)

PSQ- AA#	Alternative Action	Consequences of Erroneous Actions	Severity of Consequences
3-2	Evaluate the site for closure with no remedial action.	The site may inappropriately be closed without remedial action, increasing risks of potential exposure to workers and the environment.	Severe

DS #3 – Determine whether the soil is chemically contaminated and evaluate remedial alternatives in a FS, or evaluate the site for closure with no remedial action.

3.0 STEP 3 – IDENTIFY THE INPUTS TO THE DECISION

The purpose of DQO Step 3 is to identify the types of data needed to resolve each of the DSs identified in DQO Step 2. The data may already exist or may be derived from computational or surveying/sampling and analysis methods. Analytical performance requirements (e.g., practical quantitation limit [PQL], precision, and accuracy) are also provided in this step for any new data that need to be collected.

3.1 BASIS FOR SETTING THE PRELIMINARY ACTION LEVEL

The preliminary action level is the threshold value that provides the criteria for choosing between AAs. Table 3-1 identifies the basis (i.e., regulatory threshold or risk-based) for establishing the preliminary action level for each of the COCs. The numerical value for the action level is defined in DQO Step 5.

DS #	COCs	Basis for Setting Preliminary Action Level	Preliminary Action Levels
	TRU-contaminated soils	DOE's definition for TRU waste (DOE Guide 435.1).	100 nCi/g
	Greater than Class C contaminated soils	10 CFR 61 definition of greater than Class C waste.	>100 nCi/g ^a
2	Radiological COCs	Radiological lookup values for shallow zone soils based on RESRAD analyses for the applicable scenarios. Deep zone lookup values TBD.	Refer to Table 3-6
3	Nonradiological COCs	MTCA Method C cleanup levels with contaminant-specific variations.	Refer to Table 3-6

Table 3-1. Basis for Setting Preliminary Action Level.

3.2 INFORMATION REQUIRED TO RESOLVE DECISION STATEMENTS

Table 3-2 specifies the information (data) required to resolve each of the DSs identified in Table 2-1 and identifies whether the data already exist. For the data that are identified as existing, the source references for the data have been provided with a qualitative assessment as to whether or not the data are of sufficient quality to resolve the corresponding DS.

This limit applies to alpha emitting radionuclides with half-lives over 5 years in accordance with 10 CFR 61.55.

N/A = not applicable

TBD = to be determined (using a vadose zone transport model co-selection process)

Step 3 - Identify the Inputs to the Decision

Table 3-2. Required Information and Reference Sources. (5 Pages)

DS#	Required Information Category	Do Data Exist? (Y/N)	Source Reference	Sufficient Quantity RI/FS	able Data of Quality and to Support Process?	Are Additional Data Required to Support RI/FS Process? (Y/N)		
	Soil TRU- contamination and greater than Class C status		·	Z-9	Z-1A	Z-9	Z-1A	
1	contamination and greater than	Y	Distribution of Plutonium and Americium Beneath the 216-Z-1A Crib: A Status Report, RHO-ST-17 (Price et al. 1979). Provides data summaries and results from limited field investigations at 216-Z-1A.	N/A	Y	. N/A	Y²	
		`	Report on Plutonium Mining Activities at 216-Z-9 Enclosed Trench, RHO-ST-21 (Ludowise 1978). Provides data summaries and results of plutonium inventories before and after mining efforts at 216-Z-9.	Y	N/A	Yª	N/A	
			Z Plant Source Aggregate Area Management Study Report, DOE/RL 91-58, Rev. 0 (DOE-RL 1992).	Y	Y	Y²	Yª	
			Results of 1998 Spectral Gamma-Ray Monitoring of Boreholes at the 216-Z-1A Tile Field, 216-Z-9 Trench, and 216-Z-12 Crib, PNNL-11978 (PNNL 1999b).	N/A	Y	N/A	Y*	
			Proof-of-Principle Demonstration of a Passive Neutron Tool for Detection of TRU-Contaminated Soil at the 216-Z-1A Tile Field, BHI-01436, Rev. 0 (Bauer et al. 2000).	N/A	Y	N/A	Y*	
			Waste Site Grouping for 200 Areas Soil Investigations, DOE/RL-96-81, Rev. 0 (DOE-RL 1997b). Provides existing information for the wastes sent to this OU.	Y	Y	Y ^a	Y¹	
			Nuclear Reactivity Evaluations of 216-Z-9 Enclosed Trench, ARH-2915 (Smith 1973). Provides data summaries and analytical results of plutonium inventories before removal at 216-Z-9.	Y	N/A	N	N/A	

Table 3-2. Required Information and Reference Sources. (5 Pages)

DS#	Required Information Category	Do Data Exist? (Y/N)	Source Reference	Sufficient (Quantity RI/FS)	able Data of Quality and to Support Process? (/N)	Are Additional Data Required to Support RI/FS Process? (Y/N)		
	# Information Category (Y/N) Soil		Z -9	Z-1A	Z-9	Z-1A		
2	2 radiological		f ==== = ==== = === = = = == = = = = =	Y	Y	Yarp	Åsrp	
			(Price et al. 1979). Provides data summaries and results	N/A	Y	N/A	Y ^{2,b}	
			Report on Plutonium Mining Activities at 216-Z-9 Enclosed Trench, RHO-ST-21 (Ludowise 1978). Provides data summaries and results of plutonium inventories before and after removal at 216-Z-9.	Y	N/A	Yac	N/A	
			Z Plant Source Aggregate Area Management Study Report, DOE/RL 91-58, Rev. 0 (DOE-RL 1992).	Y	Y	Yª,b,c	Ya,b,c	
			Results of 1998 Spectral Gamma-Ray Monitoring of Boreholes at the 216-Z-1A Tile Field, 216-Z-9 Trench, and 216-Z-12 Crib, PNNL-11978 (PNNL 1999b).	Y	Y	Yª	Yª	
			Proof-of-Principle Demonstration of a Passive Neutron Tool for Detection of TRU-Contaminated Soil at the 216-Z-1A Tile Field, BHI-01436, Rev. 0 (Bauer et al. 2000).	N/A	Y	N/A	Y*	

Step

w

Identify the Inputs to the Decision

Step 3 - Identify the Inputs to the Decision

Table 3-2. Required Information and Reference Sources. (5 Pages)

DS#	Required Information Category	Do Data Exist? (Y/N)	Source Reference	Sufficient Quantity RI/FS	able Data of Quality and to Support Process? (/N)	Are Additional Dat Required to Suppo RI/FS Process? (Y/N)		
				Z-9	Z-1A	Z -9	Z-1A	
N/A	Groundwater data	Hydrostratigraphy and Recharge Distribution Direct Measurements of Hydraulic Conducti UFA Method, PNL-9424 (PNL 1994). Prese physical property analyses (saturation, hydra conductivity, pore volume, water content, pa mineralogy, and density) from samples collen near 216-Z-9 and 216-Z1A in 1992 and 1993 Hydrogeologic Model for the 200-West Grou Aggregate Area, WHC-SD-EN-TI-014, Rev. (WHC 1992). Presents site-specific data for Area that can be used to calculate soil density conductivity, and porosity. Composite Analysis for Low-Level Waste Dis 200 Area Plateau of the Hanford Site, PNNL (PNNL 1998). Provides 200 Area distribution for various waste stream types and Hanford Low-Activity Tank Waste Performance Asses (ILAW PA), PNNL-13037, Rev. 1 (Kaplan an Serne 2000). Provides 200 Area distribution	Hydrostratigraphy and Recharge Distributions from Direct Measurements of Hydraulic Conductivity Using the UFA Method, PNL-9424 (PNL 1994). Presents results of physical property analyses (saturation, hydraulic conductivity, pore volume, water content, particle size, mineralogy, and density) from samples collected at wells near 216-Z-9 and 216-Z1A in 1992 and 1993.		data cannot be nary conceptual			
1, 2, and 3	Physical properties moisture content, particle size distribution, and lithology	Y	Hydrogeologic Model for the 200-West Groundwater Aggregate Area, WHC-SD-EN-TI-014, Rev. 0 (WHC 1992). Presents site-specific data for 200 West Area that can be used to calculate soil density, hydraulic conductivity, and porosity.	N	N	Y	Y	
	Disa di sai		Composite Analysis for Low-Level Waste Disposal in the 200 Area Plateau of the Hanford Site, PNNL-11800 (PNNL 1998). Provides 200 Area distribution coefficients for various waste stream types and Hanford soils.	N	N	Y	Y	
Distribution coefficients			Geochemical Data Package for the Hanford Immobilized Low-Activity Tank Waste Performance Assessment (ILAW PA), PNNL-13037, Rev. 1 (Kaplan and Serne 2000). Provides 200 Area distribution coefficients for various waste stream types and Hanford soils.	N	N	Y	Y	

Identify the Inputs to the Decision

Table 3-2. Required Information and Reference Sources. (5 Pages)

DS#	Required Information Category	Do Data Exist? (Y/N)	Source Reference	Sufficient Quantity RI/FS I	able Data of Quality and to Support Process? /N)	Are Additional Data Required to Support RI/FS Process? (Y/N)		
				Z -9	Z-1A	Z-9	Z-1A	
1 and 2	RESRAD input data	Y	Manual for Implementing Residual Radioactive Material Guidelines Using RESRAD, Version 5.0, ANL-EAD-LD-2 (ANL 1993). Input parameters are defined in this manual that can be determined based on existing information or RESRAD defaults.	N	N	Y	Y	
1, 2, and 3	Vadose transport (STOMP) code- based model input data	Y	Subsurface Transport Over Multiple Phases (STOMP), PNNL-12034 (PNNL 2000). Site configuration inputs needed to develop site-specific model.	N	N	Y	Y	

^{*} Historical data indicated that these sites contain TRU-contaminated and radiologically contaminated soils. However, data gaps do exist, particularly in the deeper vadose zone. Therefore, additional data are needed to complete the vertical contaminant profile.

N/A = not applicable

STOMP = Subsurface Transport Over Multiple Phases

Data were not collected in a primary sampling location. The data were collected during soil/vapor extraction, therefore organic analyses are not considered accurate because of the effectiveness of the extraction system in reducing organic vapors from the vadose zone. In addition, the quality of the data needs to be further investigated to validate sample results.

Data were collected in a primary sampling location; however, the data were only collected to a depth of 3.1 m (10 ft) below the trench surface, and only for Cd, Am-241, Cs-137, Pu-239/240, Sr-90, and soil gas vapor. Thus, additional data are needed.

3.2.1 Data Gap Analysis

The data in the reference source documents were evaluated for adequacy to support the RI/FS decision-making process (see Table 3-2). The data review indicated that there are no data gaps for TRU-contamination and radiological contamination in the upper regions of the vadose zone (0 to 17 m [58 ft] depth for the 216-1A Tile Field and 0 to 21 m [105 ft] for the 216-Z-9 Trench). However, TRU contamination and radiological contamination data gaps exist for both sites below those elevations.

These sites were historically a concern from a radiological standpoint; consequently, little chemical characterization data exists. The data that do exist cover few of the contaminants in Table 1-8 and over limited depth intervals.

Because the deeper portions of the vadose zone lack radionuclide data and because chemical constituent data are missing for the entire vadose zone, the RI/FS decision-making process was evaluated for sensitivity to these data gaps. The remove, treat, and dispose alternative is the most sensitive to the TRU contamination and radiological contamination concentrations in the shallow depth zones. The historical information satisfies the data needs; however, the engineered multimedia barrier alternative requires contaminant information in the deep vadose zone to assess waste site conditions against barrier performance. Therefore, it was concluded that these data gaps must be filled to support evaluation for all of the remedial alternatives being considered.

3.3 COMPUTATIONAL AND SURVEY/ANALYTICAL METHODS

Table 3-3 identifies the DSs where existing data either do not exist or are of insufficient quality to resolve the DSs. For these DSs, Table 3-3 presents computational and/or surveying/sampling methods that could be used to obtain the required data.

Table 3-3. Information Required to Resolve the Decision Statements.^a (2 Pages)

DS#	Remedial Investigation Variable	Required Data	Computational Methods	Survey/Analytical Methods
1 and 2	Concentrations of radiological COCs	Alpha, beta, and gamma COC concentrations in soils for evaluation against ARARs and PRGs. Location data (depth and lateral extent of COCs within waste site boundaries).	RESRAD analytical modeling method for human health dose assessment. STOMP numerical modeling package to develop models for contaminant transport through vadose zone to groundwater.	Field screening with radiological detection equipment. Geophysical borehole logging with downhole radiological detectors. Soil sampling and laboratory analysis.

Remedial Computational Survey/Analytical DS# Investigation Required Data Methods Methods Variable Nonradiological (e.g., inorganic metals and anions, and SVOCs) Risk assessment. COC concentrations in STOMP numerical soils for evaluation Concentrations of modeling package to Soil sampling and against ARARs and 3 nonradiological develop models for laboratory analysis. PRGs. **COCs** contaminant transport Location data (depth and through vadose zone to lateral extent of COCs groundwater. within waste site boundaries). Moisture content, bulk Direct comparison to 1, 2, Soil physical Soil sampling and density, particle size existing models to and 3 properties laboratory analysis. distribution determine conductivity.

Table 3-3. Information Required to Resolve the Decision Statements. (2 Pages)

Table 3-4 presents details on the computational methods identified in Table 3-3. These details include the source and/or author of the computational method and information on how the method could be applied to this study.

Satisfy Computational Source/ DS# **Application to Study** Input Method Author Req't? Argonne RESRAD will be used to estimate direct human and RESRAD National Yes radiation exposure to account for radioactive decay. Laboratory 2 STOMP is a numerical modeling package for Pacific development of models that can be used to estimate the 1, 2, Northwest and **STOMP** migration of radiological and nonradiological Yes National 3 contaminants to groundwater for indirect exposure Laboratory estimates.

Table 3-4. Details on Identified Computational Methods.

Table 3-5 identifies each of the survey and/or analytical methods that may be used to provide the required information needed to resolve each of the DSs. The possible limitations associated with each of these methods are also provided.

^a See Table 3-5 for additional information.

SVOC = semi-volatile organic compound

Table 3-5. Potentially Appropriate Survey and/or Analytical Methods. (2 Pages)

Media	Remediation Variable	Potentially Appropriate Survey/Analytical Method	Possible Limitations
Field Screen	ing		
Vadose zone soils	Gross and isotopic gamma emissions	Cone penetrometer; NaI or BGO detector logging	A closed-end rod is pushed into the soil to the desired depth. A small-diameter NaI or BGO detector (or other suitable detector) is used to log the gross gamma response with depth. The cone penetrometer may not be effective in cobbly or rocky soils or for deep penetration.
	Radiological and chemical field screening	Cone penetrometer and direct push sampling	A closed-end rod is pushed into the soil to the desired depth, where a removable tip is displaced and a small volume of soil is retrieved. Due to the small volume of soil retrieved, multiple samples would be required to meet sample volume requirements for a large analyte list. Cobbles, rocks, or other features in the soil column easily stop the cone penetrometer and other direct-push methods.
	Gross and isotopic gamma emissions	Direct push; NaI or BGO detector logging	A small-diameter casing is pushed into the soil to the desired depth. A small-diameter NaI or BGO detector (or other suitable detector) is used to log the gamma response with depth. Direct-push methods (e.g., GeoProbe TM) may be ineffective in cobbly or rocky soils or deeper than approximately 10 m (33 ft).
	Gamma emissions from fission products, Am-241, Pu-239, and Np-237	Borehole SGL with HPGe detector	Gamma-ray logging provides the concentration profiles of gamma-emitting radionuclides such as Am-241, Pu-239, and many fission products in a borehole environment. It is considered by some to be more accurate than sampling and laboratory assay because the assay is performed in situ with less disturbance of the sample, there is higher vertical spatial resolution, and the sample size is much larger. This method may also be more economical than traditional sampling and analysis. This method does not assess radionuclides or daughter products that do not emit gamma rays. The gamma energies from Am-241, Pu-239, and Np-237 are at the low end of the spectrum, which results in high numerical minimum detectable activities and possible matrix effects from other isotopes. This technique requires the use of a single casing (installed by drilling or driving) in contact with the soil formation.
	Neutron emissions from plutonium and from alpha- neutron soil interaction	Borehole passive neutron logging	Passive neutron logging provides indication of the presence of neutron-emitting isotopes in soils. The passive neutron detection limit is approximately 100 nCi/g in TRU-contaminated soil.

Potentially Remediation Appropriate Media Possible Limitations Variable Survey/Analytical Method This technique uses source materials or generators to release neutrons into the soil formation. Passive detectors measure the response to the neutron flux as Active neutron a means of detecting specific transuranic Borehole emissions from constituents. Although neutron activation methods passive/active TRUhave been developed, these methods are not neutron-logging contaminated expected to be useful for this initial characterization methods soil effort. At present, these techniques are too expensive and time consuming and logistical problems are associated with the handling of intense sources or generators. N-N moisture logs can be used to determine current moisture content profiles of the subsurface through new or existing boreholes. The moisture profiles are often directly correlated to contaminant Borehole neutronconcentrations, sediment grain size, composition, or Vertical neutron moisture subsurface structural features. For this project, the moisture profile moisture profile may be useful for helping determine logging the location of contamination and establish geologic conditions to support contaminant fate and transport modeling. It may also be correlated to reflections identified in ground-probing radar surveys. Laboratory Samples Highly contaminated samples require use of onsite laboratories, with associated impacts (e.g., high cost, reduced analyte lists, matrix effects, degraded All COCs and Vadose detection limits, and long turnaround times). Lower physical Laboratory analysis zone soils contamination levels allow use of offsite properties laboratories, avoiding these limitations. Physical property analysis will include bulk density, moisture

Table 3-5. Potentially Appropriate Survey and/or Analytical Methods. (2 Pages)

TM GeoProbe is a registered trademark of GeoProbe Systems, Salinas, Kansas.

BGO = bismuth-germinate

EMI = electromagnetic imaging

GPR = ground-penetrating radar

HPGe = high-purity germanium

NaI = sodium iodide

SGL = spectral gamma logging

3.4 ANALYTICAL PERFORMANCE REQUIREMENTS

Table 3-6 defines the analytical performance requirements for the data that need to be collected to resolve each of the DSs. These performance requirements include the PQL and the precision and accuracy requirements for each of the COCs.

content, and particle size distribution.

Step 3 - Identify the Inputs to the Decision

Table 3-6. Analytical Performance Requirements - Shallow and Deep Zone Soils. (5 Pages)

				v .11		Targe	Required ()uantitation	Limits				
COCs	CAS#	Prelin	ninary Actio		Name/Analytical Technology	Water ⁴ Low	Water ⁴ High	Soil-Other Low	Soil-Other High	Precision	Accuracy	Precision Soil	Accuracy Soil
COCS	CAS #	15 mrem/yr ^k (pCl/g)	500 mrem/yrb (pCVg)	GW Protection ^{h.c} (pCi/g)		Activity (pCi/L)	Activity (pCi/L)	Activity (pCi/g)	Activity (pCi/g)	Water	Water		
Americium-241	14596-10-2	335	112,000	TBD	Americium isotopic – AEA	1	400	1	4,000	±20%	80-120%	±35%	65-135%
Cesium-137	10045-97-3	23.4	780	TBD	GEA	15	200	0.1	2,000	±20%	80-120%	±35%	65-135%
Cobalt-60	10198-40-0	4.90	164	TBD	GEA	25	200	0.05	2,000	±20%	80-120%	±35%	65-135%
Neptunium-237	13994-20-2	59.2	1,980	TBD	Neptunium-237 - AEA	1	N/A	1	8,000	±20%	80-120%	±35%	65-135%
Plutonium-238	13981-16-3	47	15,700	TBD	Plutonium isotopic – AEA	1	130	1	1,300	±20%	80-120%	±35%	65-135%
Plutonium-239/240	Pu-239/240	425	14,200	TBD	Plutonium isotopic – AEA	1	130	1	1,300	±20%	80-120%	±35%	65-135%
Strontium-90	Rad-Sr	2,410	80,300	TBD	Total radioactive strontium – GPC	2	80	t	800	±20%	80-120%	±35%	65-135%
Technetium-99	14133-76-7	412,000	13,700,000	TBD	Technetium-99 – liquid scintillation	15	400	15	4,000	±20%	80-120%	±35%	65-135%
Thorium-232	TH-232	4.8	160	TBD	Thorium isotopic – AEA (pCi) ICPMS (mg)	1	0.002 mg/L	1	0.02 mg/kg	±20%	80-120%	±35%	65-135%
Tritium (H-3)	10028-17-8	66,900	2,230,000	TBD	Tritium – liquid scintillation	400	400	400	400	±20%	80-120%	±35%	65-135%
Uranium-234	13966-29-5	2,660	88,800	TBD	Uranium isotopic - AEA (pCi) ICPMS (mg)	ı	0.002 mg/L	. 1	0.02 mg/kg	±20%	80-120%	±35%	65-135%
Uranium-235	15117-96-1	101	3,370	TBD	Uranium isotopic – AEA (pCi) ICPMS (mg)	1	0.002 mg/L	. 1	0.02 mg/kg	±20%	80-120%	±35%	65-1359
Uranium-238	U-238	504	16,800	TBD	Uranium isotopic - AEA (pCi) ICPMS (mg)	3	0.002 mg/L	. 1	0.02 mg/kg	±20%	80-120%	±35%	65-135%

Step 3 – Identify the Inputs to the Decision

Table 3-6. Analytical Performance Requirements – Shallow and Deep Zone Soils. (5 Pages)

	<u> </u>	T						Quantitation					
606-	CAS#	Prelin	ninary Action	Level*	Name/Analytical	Water ⁴	Water	Soil-Other	Soil-Other				
COCs	CAS#	Method Be (mg/kg)	Method C ^f (mg/kg)	GW Protection ^t (mg/kg)	Technology	Low Activity (pCi/L)	High Activity (pCi/L)	Low Activity (pCi/g)	High Activity (pCi/g)	Water	Water	Soil	Soil
Metals													
					Metals - 6010 - ICP	0.1	0.2	10	20	h	h	h	h
Arsenic	7440-38-2	1.67	219	0.00583	Metals – 6010 ^k – ICP (trace)	0.01	N/A	1	N/A	h	ħ	h	b
					Metals - 6010 ICP	0.005	0.01	0.5	1	h	h	h	h
Cadmium	7440-43-9	80	3,500	0.5 ⁱ	Metals – 6010 ^j – ICP (trace)	0.005	N/A	0.5	N/A	ħ	h	h	h
					Metals – 6010 – ICP	0.01	0.01	1	2	h	h	h	b
Chromium (total)	7440-47-3	80,000 ^k	3.5E6 ^k	10 ⁱ	Metals - 6010 - ICP (trace)	0.01	N/A	1	N/A	h	h	h	h
Chromium VI	18540-29-9	400	17,500	8	Chromium (hex) - 7196 - colorimetric	0.01	4	0.5	200	h	h	h	h
Соррег	7440-50-8	2,960	130,000	59.2	Metals - 6010 - ICP	0.025	0.025	2.5	2.5	h	h	h	ь
					Metals – 6010 – ICP	0.1	0.2	10	20	h	b	h	b
Lead	7439-92-1	353 ¹	1,000 ^m	1.5ª	Metals - 6010 - ICP(trace)	0.01	N/A	1	N/A	h	b	h	h
Mercury	7439-97-6	24	1,050	0.2 ⁱ	Mercury - 7470 - CVAA	0.0005	0.005	N/A	N/A	ь	b	h	h
Mercury	1433-31-0		1,000	0.2	Mercury - 7471 – CVAA	N/A	N/A	0.2	0.2	h	h	h	h
Nickel	7440-02-0	1,600°	70,000°	32	Metals - 6010 - ICP	0.04	0.04	4	4	h	à	h	ь
Selenium	7782-49-2	400	17,500	5 P	Metals - 6010 - ICP	0.1	0.2	10	20	q	q	9	q
					Metals - 6010 - ICP	0.02	0.02	2	2	h	ь	h	h
Silver	7440-22-4	400	17,500	8	Metals – 6010 – ICP (trace)	0.005	N/A	0.5	N/A	h	h	h	h
Uranium (total)	7440-61-1	240°	10,500°	2 ^p	Uranium total - kinetic phosphorescence analysis	0.0001	0.02	1	0.2	±20%	80-120%	±35%	65-135%
Inorganics												· · · · · · · · · · · · · · · · · · ·	
Ammonia/ ammonium	7664-41-7	Unlimited	Unlimited	27,200	Ammonia – 350.N°	0.05	800	0.5	8,000	h	h	h	h

Table 3-6. Analytical Performance Requirements - Shallow and Deep Zone Soils. (5 Pages)

						Target		,					
		Prelin	ninary Action	Level*	Name/Analytical	Water	Water ⁴	Soil-Other	Soil-Other	Precision	Accuracy	Precision	Accuracy
COCs	CAS#	Method B ⁴ (mg/kg)	Method C ^f (mg/kg)	GW Protection ^s (mg/kg)	Technology	Low Activity (pCi/L)	High Activity (pCVL)	Low Activity (pCi/g)	High Activity (pCl/g)	Water	Water	Soil	Accuracy Soil
Chloride	16887-00-6	25,000 ^g	25,000 ^g	25,000	Anions - 9056 - IC	0.2	5	2	5	h		h	h
Fluoride	16984-48-8	4,800	210,000	96	Anions - 9056 - IC	0.5	5	5	5	h	h	h.	
Nitrate	14797-55-8	128,000	Unlimited	4,400	Anions - 9056 - IC	0.25	10	2.5	40	h	•	h	
Nitrite	14797-65-0	8,000	350,000	160	Anions – 9056 – IC	0.25	15	2.5	20	h	a	h	
Nitrate/nitrite	NO-NO-N	128,000	Unlimited	4,400	NO ₂ /NO ₂ – 350.N ⁴	0.075	5	0.75	10	h	1	b	
Phosphate	14265-44-2	N/A	N/A	None	Anions - 9056 - IC	0.5	15	5	40	•	•	h	
Sulfate	14808-79-8	25,000 [#]	25,000 ^s	25,000 ⁸	Anions – 9056 – IC	0.5	15	5	40	h	h	h.	
Organics													
l,l-dichloroethane	75-34-3	8,000	350,000	80	Volatile organics – 8260 – GCMS	0.01	0.01	0.01	0.01	h	h	.	h
1,2-dichloroethane	107-06-2	11	1,440	0.0481	Volatile organics – 8260 – GCMS	0.005	0.005	0.005	0.005	a.	h	æ	h
1,1,1-trichlorethane	71-55-6	72,000	2,150,000	720	Volatile organics – 8260 – GCMS	0.005	0.005	0.005	0.005	•	•	is .	b
2-propanone (acetone)	67-64-1	8,000	350,000	80	Volatile organics – 8260 – GCMS	0.02	0.02	0.02	0.02	h	h.	h	
Benzene	71-43-2	34.5	4,530	0.151	Volatile organics – 8260 – GCMS	0.005	0.005	0.005	0.005	4	b	ь	h
Carbon tetrachloride	56-23-5	7.69	1,010	0.0337	Volatile organics – 8260 – GCMS	0.005	0.005	0.005	0.005	h	•	h	h
Chlorobenzene	108-90-7	1,600	7,000	16	Volatile organics – 8260 – GCMS	0.005	0.005	0.005	0.005	h	h	h	k
Chloroform	67-66-3	164	21,500	0.717	Volatile organics - 8260 - GCMS	0.005	0.005	0.005	0.005	. •	•	•	
Ethyl benzene	100-41-4	8,000	350,000	80	Volatile organics – 8260 – GCMS	0.005	0.005	0.005	0.005	h	h	h	h
Hydraulic fluids (grease)	8008-20-6	200	200°	200=	Oil and grease (total recoverable) – 413,N	2	N/A	200	N/A	h	h.	h	•

Table 3-6. Analytical Performance Requirements – Shallow and Deep Zone Soils. (5 Pages)

	T	B. 0.		Y01		Target	Required (Quantitation	Limits				
COCs	CAS#	Method B ^c	Method C ^f (mg/kg)	GW Protection ^t (mg/kg)	Name/Analytical Technology	Water ^d Low Activity (pCi/L)	Water ⁴ High Activity (pCi/L)	Soil-Other Low Activity (pCi/g)	Soil-Other High Activity (pCi/g)	Precision Water	Accuracy Water	Precision Soil	Accuracy Soil
2-butanone (MEK)	78-93-3	48,000	2,100,000	480	Volatile organics – 8260 – GCMS	0.01	0.01	0.01	0.01	b	h	h	h
Methyl iso butyl ketone (MIBK)	108-10-1	6,400	280,000	64	Volatile organics – 8260 – GCMS	0.01	0.01	0.01	0.01	b	h	h	h
Dichloromethane (methylene chloride)	75-09-2	133	17,500	0.583	Volatile Organics – 8260 ~ GCMS	0.005	0.005	0.005	0.005	ħ	ħ	ħ	ls.
n-butyl benzene	104-51-8	VOA TIC	VOA TIC	N/A	Volatile Organics – 8260 – GCMS	0.005	N/A	0.005	N/A	N/A	N/A	N/A	N/A
Toluene	108-88-3	16,000	70,000	160	Volatile organics – 8260 – GCMS	0.005	0.005	0.005	0.005	h	h	h	h
Tetrachloroethylene	127-18-4	19.6	2,570	0.0858	Volatile organics - 8260 - GCMS	0.005	0.005	0.005	0.005	h	h	h	h
Cis/trans-1,2-dichloro ethylene	156-60-5	1,600	70,000	16	Volatile organics – 8260 – GCMS	0.005	0.005	0.005	0.005	h	h	h	h
Trichloroethylene	79-01-6	90.9	11,900	0.398	Volatile organics - 8260 - GCMS	0.005	0.005	0.005	0.005	h	h	h	h
Xylene (total)	1330-20-7	160,000	7,000,000	1,600	Volatile organics – 8260 – GCMS	0.005	0.005	0.005	0.005	bi bi	h	h	h
Normal paraffin hydrocarbons	8008-20-6	200 ^m	200 ^m	200 ^m	Non-halogenated VOA - 8015M - GC modified for hydrocarbons	0.5	0.5	5	5	ħ	h	h	b
Phenol	108-95-2	48,000	2,100,000	960	Semi-volatiles - 8270 - GCMS	0.01	0.1	0.33	3.3	h	h	h	h
PCBs	1336-36-3	0.13	5.19	0.00114"	PCBs - 8082 - GC	0.0005	0.005	0.0165	0.1	h		h	h
ТВР	126-73-8	None	None	None	Semi-volatiles – 8270 – GCMS	0.1	0.5	3.3	5	b	h	h	h
Total organic carbon	TOC	N/A	N/A	None	TOC – 9060- combustion	1	1	100	100	±20%	80-120%	±35%	65-135%
Field Screening Measure	ments												
РН	TBD	TBD	TBD	TBD	TBD	TE	3D	TE	3D	TBD	TBD	TBD	TBD

Ħ
6
=
Ξ.
Ŧ
medial Investig
25
₹.
8
₹.
2
=
×
'Ά
tion DQO Sum
દ
3
3
ä
Ź
nmary Re
Report
8
ž
ĩ
į.
Š
9
0
Ŧ
0
×
\sim
20
Ē
200-PW-1 OU Phase I
-
20
43
ž
g
3
₹
3
₹,
10
₹
6
aste
aste S
aste Siti
Report – 200-PW-1 OU Phase I Representative Waste Sites

						Targe	t Required	Quantitation	Limits		ļ			
			Prelin	ninary Action	Level	Name/Analytical	Water ⁴	Water ^d	Soil-Other	Soil-Other	Precision	Accuracy	Precision	Accuracy
COCs	CAS#	Method B ⁴ (mg/kg)	Method C' (mg/kg)	GW Protection ² (mg/kg)	Technology	Low Activity (pCi/L)	High Activity (pCi/L)	Low Activity (pCi/g)	High Activity (pCi/g)	Water	Water	Soil	Soil	
Soil Physical Properties										•				
Moisture content	N/A	N/A	N/A	N/A	D2216	N	i/A	W W	1%	N/A	N/A	N/A	N/A	
Particle size distribution	N/A	N/A	N/A	N/A	D422	N	₹/A	W	1%	N/A	N/A	N/A	N/A	
Lithology	N/A	N/A	N/A	N/A	BHI-EE-01, Procedure 7.0	N	l/A	Desc	riptive	N/A	N/A	N/A	N/A	

- * The preliminary action level is the regulatory or risk-based value used to determine appropriate analytical requirements (e.g., detection limits). Remedial action levels will be proposed in the FS, will be finalized in the ROD, and will drive remediation of the sites.
- 15 mrem/yr = rural residential, 500 mrem/yr = commercial industrial, GW = groundwater protection radionuclide values from the Washington State Department of Health's (WDOH's) Hanford Guidance for Radiological Cleanup (WDOH 1983). Radionuclide values are calculated using parameters from WDOH guidance.
- The "100 times groundwater" rule does not apply to residual radionuclide contaminants. For radionuclides, groundwater protection is demonstrated through technical evaluation using STOMP code modeling (PNNL 2000).
- Water values for sampling quality control (e.g., equipment blanks/rinses) or drainable liquid (if recovered).
- * MTCA Method B soil values for direct exposure.
- MTCA Method C industrial soil values for direct exposure.
- ⁵ MTCA Method B soil values for groundwater protection.
- Precision and accuracy requirements as identified and defined in the referenced EPA procedures.
- Based on the Federal primary drinking water standards (40 CFR 141).
- All four-digit numbers refer to Test Methods for Evaluating Solid Waste: Physical/Chemical Methods (EPA 1986).
- Value based upon chromium (III) MTCA soil concentrations.
- Based on EPA's Guidance Manual for the Integrated Exposure Uptake Biokenetic Model for Lead In Children (EPA 1994b).
- Based upon MTCA Method A values.
- Based on 100 times the National Primary Drinking Water Regulations action level (40 CFR 141).
- Value based upon nickel or uranium soluble salts value.
- Based on a proposed drinking water standard.
- 1 From Methods of Analysis of Water and Waste (EPA 1983).

AEA = alpha energy analysis

CAS = Chemical Abstract Service

CVAA = cold vapor atomic absorption

GC = gas chromatograph

GCMS = gas chromatograph/mass spectrometry

GPC = gas proportional counter

= ion chromatography

ICPMS = inductively coupled plasma mass spectrometer

N/A = not applicable

TBD = to be determined

OC = total organic carbon

4.0 STEP 4 – DEFINE THE BOUNDARIES OF THE STUDY

4.1 OBJECTIVE

representative waste sites

The primary objective of DQO Step 4 is for the DQO team to identify the spatial, temporal, and practical constraints on the sampling design and to consider the consequences. This objective (in terms of the spatial, temporal, and practical constraints) ensures that the sampling design results in the collection of data that accurately reflect the true condition of the site and/or populations being studied.

4.2 WORKSHEETS FOR STEP 4 – DEFINE THE BOUNDARIES OF THE STUDY

Table 4-1 defines the population of interest to clarify what the samples are intended to represent. The characteristics that define the population of interest are also identified.

DS # Population of Interest Characteristics

Cribs and Specific Retention Trenches

The set of all environmental samples within the vadose zone and 3 associated with the Concentrations and activities of transuranic radionuclides, other radionuclides, metals, anions, and limited VOA and semi-VOA organic constituents; physical properties including moisture

content, bulk density, lithology, and grain-size distribution.

Table 4-1. Characteristics that Define the Population of Interest.

Table 4-2 defines the spatial boundaries of the decision and the domain or geographic area (or volume) within which all decisions must apply (in some cases, this may be defined by the OU). The domain is a region distinctly marked by some physical features (i.e., volume, length, width, and boundary).

Table 4-2. Geographic Boundaries of the Investigation.

DS#	Geographic Boundaries of the Investigation
1, 2,	The geographic boundaries for the investigation are the boundaries of the individual representative
and 3	waste sites from the surface to groundwater.

When appropriate, the population is divided into strata that have relatively homogeneous characteristics. The DQO team must systematically evaluate process knowledge, historical data, and plant configurations to present evidence of logic that supports alignment of the population into strata with homogeneous characteristics. Table 4-3 identifies the strata with homogeneous characteristics.

Table 4-3. Strata with Homogeneous Characteristics. (2 Pages)

DS#	Population of Interest	Strata	Homogeneous Characteristic Logic		
216-Z-1A 7	ile Field				
1, 2, and 3		Overburden over the contaminated tile field (depth varies)	Soils that are not expected to be contaminated as a result of liquid discharges to the tile field. Note that this stratum is not significant from an RI/FS decision-making standpoint and will not be carried further in this study.		
1, 2, and 3	The set of all environmental samples within the vadose zone associated with the representative waste	Highest contaminant concentration layer (presumed to be 17 m [58 ft])	Particulates and high distribution coefficient contaminants were sorbed and/or filtered out of the liquid flow via the soils at the bottom of the excavated field. This zone is expected to contain the highest concentrations of contaminants and to have decreasing concentrations with depth. May also contain residual concentrations of mobile constituents.		
2 and 3	sites	Low contaminant concentration layer (presumed to extend from 17 m to 63 m [58 ft to 207 ft])	This zone is expected to contain low concentrations of mobile contaminants from the source to the groundwater table. Concentrations are expected to remain fairly constant through the impacted zone because the majority of the contaminants have been flushed through the system, leaving residual concentrations.		
216-Z-9 Tr	ench				
1, 2, and 3	The set of all environmental samples within the vadose zone associated with the representative waste sites	Highest contaminant concentration layer (presumed to be 32 m [105 ft])	Particulates and high distribution coefficient contaminants were sorbed and/or filtered out of the liquid flow via the soils at the bottom of the excavated trench. This zone is expected to contain the highest concentrations of contaminants and to have decreasing concentrations with depth. May also contain residual concentrations of mobile constituents.		
2 and 3		Moderate to low contaminant concentration layer ^a (presumed to extend from 32 m to 37 m [105 ft to 121 ft])	A moderate concentration layer was formed immediately beneath the expected high concentration layer. In this zone, finer particulates and moderate distribution coefficient contaminants from the liquid waste streams were filtered and sorbed. High volumes of disposed liquids may have carried some immobile constituents into this zone, and residual concentrations of mobile constituents may also be present.		

Population of Homogeneous Characteristic Logic Strata DS# Interest This zone is expected to have decreasing concentrations with depth as more immobile constituents filter and sorb out with the passing of the moisture front. However, concentration changes are not strictly depth-related. The Pu and CCl4 appear to be associated with the fine grained layers. Also, the vapor vacuum extraction system has removed more of the VOCs from the high permeability layers.* This zone is expected to contain low concentrations of mobile contaminants from Low contaminant the source to the groundwater table. concentration layer Concentrations are expected to remain fairly (presumed to extend from 2 and 3 constant through the impacted zone because 37 m to 67 m [121 ft to the majority of the contaminants have been 220 ft]) flushed through the system, leaving residual concentrations.

Table 4-3. Strata with Homogeneous Characteristics. (2 Pages)

VOC = volatile organic compound

The temporal boundaries of the decision are defined in Table 4-4.

When to Collect Data **Timeframe** DS# Field Screening If possible, avoid extreme hot/cold months and inclement weather that that could potentially affect sampling operations 1, 2, N/A and sample contaminant concentrations during collection and and 3 handling. Laboratory Samples If possible, avoid extreme hot/cold months and inclement weather that that could potentially affect sampling operations 1, 2, N/A and sample contaminant concentrations during collection and and 3 handling.

Table 4-4. Temporal Boundaries of the Investigation.

N/A = not applicable

The wetted front may have reached groundwater for trench site. It is not known if groundwater was impacted by the discharges in the tile field site.

4.3 SCALE OF DECISION MAKING

Table 4-5 defines the scale of decision making for each DS. The scale of decision making is defined as the smallest, most appropriate subsets of the population (sub-population) for which decisions will be made based on the spatial or temporal boundaries of the area under investigation.

DS#	Population of	Geographic	Ten	poral Boundary	S44-
ייי פע	Interest	Boundary	Timeframe	When to Collect Data	Strata
	The set of all	Boundaries of the		If possible, avoid extreme hot/cold months	Highest contaminant concentration layer
1, 2, and 3	samples within the vadose zone associated with the representative	individual representative waste sites from the surface to groundwater	N/A	and inclement weather that that could potentially affect sampling operations and sample contaminant	Moderate-to- low contaminant concentration layer*
	waste sites			concentrations during collection and handling.	Low contaminant concentration layer

Table 4-5. Scale of Decision Making.

4.4 PRACTICAL CONSTRAINTS

Table 4-6 identifies the practical constraints that may impact the data collection effort. These constraints include physical barriers, difficult sample matrices, high radiation areas, or any other condition that will need to be taken into consideration in the design and scheduling of the sampling program.

Table 4-6. Practical Constraints on Data Collection. (2 Pages)

Significant contamination concentrations are present in both representative waste sites. Contamination controls will limit and hinder drilling and sample collection operations.

The 216-Z-9 Trench is not accessible for conventional vertical drilling equipment. The limitations imposed by the enclosure structure are identified as a project technical issue in Section 1.5.2 and are described in Section 1.6.1. This is discussed in greater detail in Section 7.4.1.

^a This layer applies uniquely to the 216-Z-9 Trench, as shown in Table 4-3. N/A = not applicable

Rev. 0

Table 4-6. Practical Constraints on Data Collection. (2 Pages)

Borehole soil sampling equipment may not obtain sufficient volumes of sample media if the sampled zone is 0.6 m (2 ft) thick or less. Advancement of the borehole casing may drag contamination down the hole. Drilling operations may volatilize the VOAs (including carbon tetrachloride) that are present. Thus, an inaccurate measurement may be obtained.

The soils in the vadose zone may include cemented zones that could pose difficulties in sample collection.

Health and safety constraints may be imposed during characterization sampling to ensure that as low as reasonably achievable issues are properly addressed when sampling potentially TRU-contaminated, greater than Class C, and other radiologically contaminated soils.

Laboratory constraints are expected when analyzing soil samples with high contaminant concentrations. Soil samples in this category would be analyzed in an onsite laboratory. Impacts are expected in cost, degradation of detection limits, and possible reduction in the analyte lists. If analytical turnaround times are extended, the short hold times for certain organic constituents may be exceeded. In addition, soil physical property testing may not be possible in onsite laboratories.

Extreme weather conditions may limit or shut down field screening operations.

5.0 STEP 5 - DEVELOP A DECISION RULE

The purpose of DQO Step 5 is initially to define the statistical parameter of interest (i.e., maximum, mean, or 95% upper confidence level [UCL]) that will be used for comparison to the action level. The statistical parameter of interest specifies the characteristic or attribute that a decision maker would like to know about the population. The preliminary action level for each of the COCs is also identified in DQO Step 5. When this is established, a decision rule (DR) is developed for each DS in the form of an "IF...THEN..." statement that incorporates the parameter of interest, the scale of decision making, the preliminary action level, and the AAs that would result from resolution of the decision. Note that the scale of decision making and AAs were identified earlier in DQO Steps 4 and 2, respectively.

5.1 INPUTS NEEDED TO DEVELOP DECISION RULES

Tables 5-1, 5-2, and 5-3 present the information needed to formulate the DRs that are presented in Section 5.2. This information includes the DSs and AAs identified in DQO Step 2, the scale of decision making identified in DQO Step 4, and the statistical parameters of interest and preliminary action levels for each of the COCs.

Decision Statement

Determine whether the contaminant concentrations are TRU or greater than Class C and evaluate special remedial alternatives in a FS, or evaluate conventional remedial alternatives in a FS.

Determine whether the soil is radiologically contaminated and evaluate remedial alternatives in a FS or evaluate the site for closure with no remedial action.

Determine whether the soil is chemically contaminated and evaluate remedial alternatives in a FS or evaluate the site for closure with no remedial action.

Table 5-1. Decision Statements.

Table 5-2. Inputs Needed to Develop Decision Rules. (2 Pages)

DS #	COCs	Parameter of Interest	Scale of Decision Making	Preliminary Action Levels
	Transuranic radionuclides			100 nCi/g
1	Greater than Class C radionuclides	Soil sampling;	Vadose zone soils	>100 nCi/g*
2	Radionuclides	values	v adose Zone sons	RESRAD lookup values and TBD through other modeling; radionuclide concentrations equating to dose limits from 15 to 500 mrem/yr above background

Table 5-2.	Inputs Ne	eded to	Develop	Decision	Rules.	(2 Pages)
------------	-----------	---------	---------	----------	--------	-----------

DS #	COCs	Parameter of Interest	Scale of Decision Making	Preliminary Action Levels
3	Nonradiological constituents	Soil sampling;		MTCA and other regulatory levels (identified in Table 3-6)
2 and 3	Soil physical properties	maximum detected values	Vadose zone soils	N/A

^a This limit applies to alpha emitting radionuclides with half-lives over 5 years in accordance with 10 CFR 61.55.

The AAs identified in DQO Step 2 are summarized in Table 5-3.

Table 5-3. Alternative Actions.

PSQ #	AA#	Alternative Actions
	1	Evaluate special remedial alternatives in a FS.
1	2	Evaluate conventional remedial alternatives in a FS.
2	1	Evaluate remedial alternatives in a FS.
2	2	Evaluate the site for closure with no remedial action.
7	1	Evaluate remedial alternatives in a FS.
3	2	Evaluate the site for closure with no remedial action.

5.2 **DECISION RULES**

The output of DQO Step 5 and the previous DQO steps are combined into "IF...THEN" DRs that incorporate the parameter of interest, the scale of decision making, the action level, and the actions that would result from resolution of the decision. The DRs are listed in Table 5-4.

Table 5-4. Decision Rules. (2 Pages)

DR#	Decision Rule
1	If the true maximum (as estimated by the maximum detected sample values) activity of transuranic radionuclides within the soil samples in each of the applicable strata* is greater than or equal to 100 nCi/g or the greater than Class C definition, evaluate special remedial alternatives in a FS; otherwise, evaluate conventional remedial alternatives in a FS.

N/A = not applicable TBD = to be determined

Table 5-4. Decision Rules. (2 Pages)

DR#	Decision Rule
2	If the true maximum (as estimated by the maximum detected sample values) activity of radionuclides within the soil samples in each of the applicable strata results in a radiological dose greater than or equal to 15 to 500 mrem/yr above background, evaluate remedial alternatives in a FS; otherwise, evaluate the site for closure with no remedial action.
3	If the true maximum (as estimated by the maximum detected sample values) concentration of chemical constituents within the soil samples in each of the applicable strata is greater than or equal to the preliminary action levels in Table 3-6, evaluate remedial alternatives in a FS; otherwise, evaluate the site for closure with no remedial action.

^a The applicable strata include the highest contaminant concentration layer (216-Z-1A and 216-Z-9), the moderate-to-low contaminant concentration layer (216-Z-9 only), and the low contaminant concentration layer (216-Z-1A and 216-Z-9).

6.0 STEP 6 – SPECIFY TOLERABLE LIMITS ON DECISION ERRORS

Because analytical data can only estimate the true condition of the site under investigation, decisions that are made based on measurement data could potentially be in error (i.e., decision error). For this reason, the primary objective of DQO Step 6 is to determine which DSs (if any) require a statistically based sample design. For those DSs requiring a statistically based sample design, DQO Step 6 defines tolerable limits on the probability of making a decision error.

6.1 STATISTICAL VERSUS NON-STATISTICAL SAMPLING DESIGN

Table 6-1 provides a summary of the information used to support the selection between a statistical versus a non-statistical sampling design for each DS. The factors that were taken into consideration in making this selection included the timeframe over which each DS applies, the qualitative consequences of an inadequate sampling design, and the accessibility of the site if resampling is required.

DS#	Time- frame (Years)	Qualitative Consequences of Inadequate Sampling Design (Low/Moderate/Severe)	Resampling Access After Remedial Investigation (Accessible/Inaccessible)	Proposed Sampling Design (Statistical/ Non-Statistical)
1, 2, and 3 ^a	N/A	Low	Accessible	Non-statistical
1, 2, and 3 ^a	N/A	Severe	Accessible	Statistical

Table 6-1. Statistical Versus Non-Statistical Sampling Design.

N/A = not applicable

The second row of Table 6-1 indicates that a statistical sampling design would be proposed for this DQO process because of the severe consequences of an inadequate sampling design. This assessment is based on strict adherence to the DQO process without considering the status of the 200-PW-1 OU representative waste sites. The contamination status of these sites is well documented and they are known to contain TRU-contaminated, radiologically contaminated, and chemically contaminated soils. There is no risk that these sites will be erroneously categorized or considered for no action remediation alternatives. Therefore, AAs 1-1, 2-1, and 3-1 (Table 2-1) associated with the "severe" error consequence do not apply. The "low" severity consequence associated with AAs 1-1, 2-1, and 3-1 (Table 2-1) will be used to determine the sampling design requirements. The proposed sampling design is, therefore, judgmental (as indicated in the first row of Table 6-1).

As shown in Table 2-1, AAs 1-1, 2-1, and 3-1 have low consequences of error; AAs 1-2, 2-2, and 3-2 have severe consequences of error.

6.2 NON-STATISTICAL DESIGNS

A biased (or focused) sampling approach that targets the maximum potential contamination within a waste site is considered appropriate for the waste sites in the 200-PW-1 OU. Contaminant distributions are expected to follow relatively predictable patterns based on process knowledge and historical data.

For the DSs to be resolved using a non-statistical design, there is no need to define the "gray region" or the tolerable limits on decision error because these only apply to statistical designs. The nature of the waste sites to be investigated in the RI supports the use of focused sampling, as identified in Washington State Department of Ecology Toxics Cleanup Program Guidance on Sampling and Data Analysis Methods (Ecology 1995). This guidance document defines "focused sampling" as selective sampling of areas where potential or suspected soil contamination can reliably be expected to be found if a release of a hazardous substance has occurred. The trench and tile field structures to be investigated had released contaminants in a point-source or line-source manner. The contaminants that were released in such a manner have been shown to impact the soil immediately beneath the waste site with minimal lateral spread (Smith 1973 and PNNL 1998). Therefore, focusing the RI sampling throughout the site will ensure sample collection in the area of greatest impact associated with the discharge.

7.0 STEP 7 – OPTIMIZE THE DESIGN

7.1 PURPOSE

The purpose of DQO Step 7 is to identify the most resource-effective design for generating data to support decisions while maintaining the desired degree of precision and accuracy. When determining an optimal design, the following activities should be performed:

- Review the DOO outputs from the previous DOO steps and the existing environmental data.
- Develop general data collection design alternatives.
- Select the sampling design (e.g., techniques, locations, or numbers/volumes) that most cost effectively satisfies the project's goals.
- Document the operational details and theoretical assumptions of the selected design.

7.2 WORKSHEETS FOR STEP 7 – OPTIMIZE THE DESIGN

Table 7-1 identifies information in relation to determining the data collection design.

Statistical Non-Statistical Rationale DS# Judgmental data collection design is applicable to investigation as preliminary data suggest that the highest levels of contamination are located relative to release points or the bottom of waste sites. Relative size of waste sites presents a point-source-type disposal, Non-statistical focusing the area of investigation on the distribution of 1, 2, and 3 N/A sampling design contaminants with depth. Consequences of erroneous decisions are not severe. Characterization sampling results will be verified by confirmatory sampling of analogous sites during the confirmatory and remedial design phase.

Table 7-1. Determine Data Collection Design.

N/A = not applicable

Table 7-2 is used to develop general data collection design alternatives. If the data collection design for a given decision will be non-statistical, determine what type of non-statistical design is appropriate (i.e., haphazard or judgmental).

Table 7-2. Determine Non-Statistical Sampling Design.

[DR#	Haphazard	Judgmental
	1, 2, and 3	None	Professional judgmental sampling design is indicated.

The data collection design alternatives for this project are described in Table 7-3.

Table 7-3. Methods for Collection of Data at Depth. (2 Pages)

Method	Description		
Trenching or test pit sampling	Excavation with backhoe or excavator. This technique provides grab samples taken directly from the soil column (approximate 0.3-m [1-ft] intervals) or from the excavator bucket. Because this technique creates a trench, direct inspection of the exposed soil column is possible. This method is not well suited for soils contaminated with alpha-emitting radionuclides because of the potential for spread of contamination at levels that cannot be readily detected with hand held survey instruments.		
Cone penetrometer or direct-push sampling A closed-end rod is pushed into the soil to the desired depth where a removable displaced and a small volume of soil is retrieved. Due to the small volume of so retrieved, multiple samples would be required to meet sample volume requirem a large analyte list. Cobbles, rocks, or other features in the soil column easily so cone penetrometer and other direct-push methods. The resulting hole can be geophysically logged, providing information on gamma-emitting radionuclides moisture content. Grab samples may be collected from the auger fitting during drilling, or split to samples may be collected with the aid of hollow-stem auger "flights." To achie laboratory analysis sample volume needs for large analytical lists, a 0.6-m (2-ft sample from a 13-cm (5-in.)-diameter sampler is typically needed. Running a stube down the hollow center of the flight retrieves split tube samples. This met not well suited for drilling in soils contaminated with alpha-emitting radionucli because of contamination control limitations. The auger split-spoon samples are typically 6 cm (2.5 in.) in diameter. This slow drilling method is particularly useful in highly contaminated areas be potential contamination releases can be more easily controlled. This drilling method adequate laboratory analysis sample volumes for large analytical lists, a 0.6-m (2-ft)-long core sample from a 13-cm (5-in.)-diameter sampler is typically need DOE-owned, controlled cable tool rigs are available onsite for use in highly contaminated areas. In alpha-contaminated soils, significant contamination cor are required.			
		Diesel hammer drilling	The diesel hammer is a dual-string, reverse-air-circulation drilling method. The potential impacts of this drilling method include degraded sample quality and increased contaminant release potential. Because of the introduction of air to the sample media, affects on analytical results for volatile organics and increased potential for dust result from this technique.

Description Method Sonic drilling can quickly advance either well casings or sample tubes. Samples are retrieved similar to split-spoon sample collection during a cable tool operation. To achieve adequate laboratory analysis sample volumes, a 0.6-m (2-ft)-long core sample is typically needed from a 13-cm (5-in.)-diameter sampler. Sonic drilling is much Sonic drilling and faster than cable tool drilling but the technique generates a significant amount of heat, sampling which can alter samples (e.g., liberate volatile organics from the sampled soils) and the surrounding formation. In alpha-contaminated soils, significant contamination controls are required and may be difficult to implement because of the nature of the equipment and operations. Air rotary drilling is much faster than other drilling techniques. Grab samples and split-spoon samples may be taken using this method. In addition, most rotary drill rigs can be configured to collect core samples. To achieve adequate laboratory analysis Air rotary drilling and sample volumes, a 0.6-m (2-ft)-long core sample is typically needed from a 13-cm sampling (5-in.)-diameter sampler. This technique may introduce air into the soil, potentially altering the sample quality and formation moisture levels. A pile driver set upon drive casing can be used with or without a liner to collect soil Pile driver direct-push samples until refusal depth is reached. The use of crane and pile driver allows drive casing to be pushed into the soil formation at a stand-off distance from the drilling sampling location.

Table 7-3. Methods for Collection of Data at Depth. (2 Pages)

The design options are evaluated based on cost and ability to meet the DQO constraints. The results of the trade-off analyses should lead to one of two outcomes: (1) the selection of a design that most efficiently meets all of the DQO constraints, or (2) the modification of one or more outputs from DQO Steps 1 through 6 and the selection of a design that meets the new constraints.

The key features of the selected design are then documented, including (for example) the following:

- Descriptions of sample locations, strata, inaccessible areas, and maps (if beneficial)
- Directions for selecting sample locations (if the selection is not necessary or appropriate at this time)
- Order in which samples should be collected (if important)
- Stopping rules
- Special sample collection methods
- Special analytical methods.

7.3 SAMPLING OBJECTIVES

In Section 3.2.1, it was concluded that the identified radionuclide and the chemical constituent data gaps must be filled to support evaluation of the engineered multimedia barrier alternative. Table 7-4 summarizes the characterization goals and drivers for the 200-PW-1 OU sampling designs.

Characterization Goals	Waste Site	Sampling Area	Driver
Determine the types and concentrations of radiological and chemical constituents with depth at worst-case locations		Vadose zone under the waste site footprint	Support evaluation of all remedial alternatives in the RI/FS process
Geophysically log available boreholes	216-Z-9 Trench, 216-Z-1A Tile Field		Low-cost expansion of the radiological database
Analyze soils for physical properties			Support RI/FS modeling efforts

Table 7-4. Characterization Goals and Drivers.

7.4 SAMPLING DESIGN

7.4.1 Preferred Sampling Design

The most cost-effective sampling design for most RI/FS-type DQO projects is one that follows the "focused sampling" methodology (Ecology 1995). This methodology applies when contamination can be reliably expected to be found if a release of a hazardous substance has occurred. This approach is viable only if reliable information can be used to focus sampling efforts on the appropriate locations. This is clearly the case for the two 200-PW-1 OU representative waste sites. The locations of the sites are well known, and there is a significant historical database that can be used to guide sampling efforts to locations with the highest contaminant concentrations.

Three sampling alternatives were initially developed for the 216-Z-1A Tile Field. The first alternative was for drilling through the worst-case contamination location in the tile field, from the surface to the groundwater. The second alternative evaluated the possible extension of borehole 299-W18-174 from the 39.7-m (130-ft) elevation to groundwater as a lower-cost alternative. However, a review of the as-built drawing for the borehole revealed that the diameter of borehole 299-W18-174 is 10.2 cm (4 in.), which is too small for borehole extension. Therefore, two sampling design alternatives are proposed for the 216-Z-1A Tile Field.

The 216-Z-9 Trench is an engineered structure with an enclosure made of steel framework and concrete roof panels. The enclosure structure is not designed to support loads greater than the weight of a few occupational workers. Because of the high plutonium and americium

concentrations in the trench, an accidental collapse of the enclosure structure would be unacceptable from a worker risk and contamination-control standpoint; therefore, special drilling alternatives are identified for this site. The sample design alternatives are presented in Table 7-5 and are evaluated in Section 7.4.2.

Table 7-5. Sampling Design Alternatives. (8 Pages)

Sample Collection Methodology	Key Features of Design	Basis for Sampling Design			
216-Z-1A Tile Field Alternative I – Borehole Drilling in Vicinity of Well 299-W18-159					
Borehole characterization	Install one vadose borehole in close proximity to the 299-W18-159 borehole, which is near the center of the tile field. Refer to Figures 7-1 and 7-2. Soil samples will be collected in specific strata at the following intervals:	The 299-W18-159 borehole spectral gamma logging results indicate that the soils in the vicinity of this borehole have higher contamination levels than any other borehole that was logged. The borehole will be drilled from the surface to the water table for borehole soil sampling.			
	 Highest contaminant concentration layer (H₁): Collect one sample at 3.7 m (12 ft). Collect one sample at the onset of native soils beneath the tile field gravel bed, presumed to be at 7.6 m (25 ft). Collect samples at 10.7 m and 13.7 m (35 ft and 45 ft). 	The radiological contamination concentrations in this region are above the TRU definition (PNNL 1998). The 3.7-m (12-ft) sample is within the sand layer of the most highly contaminated region of the tile field (PNNL 1999b). The sand is more likely to yield a sample than the gravel layer beneath it. The 7.6-m (25-ft) region is expected to contain TRU-contaminated soils, but at significantly lower concentrations than the 3.7-m (12-ft) depth. The two deeper samples will complete a vertical contaminant concentration profile within this highly contaminated layer. None of the samples collected within the H ₁ layer will be analyzed for radiological COCs because there is no radiological data gap in this depth interval.			
	 Low contaminant concentration sand layer (H₂): Collect one sample at the onset of this formation, presumed to be 17 m (58 ft). 	Historical data show TRU contamination to a depth of approximately 17.7 m (58 ft). This region is expected to delineate the shift to low radiological concentrations. The sample will be analyzed for all COCs to obtain contaminant concentrations at this change in lithology.			

Table 7-5. Sampling Design Alternatives. (8 Pages)

Sample Collection Methodology	Key Features of Design	Basis for Sampling Design
	 Low contaminant concentration gravel layer (H₃): Collect one sample at the onset of this formation, presumed to be 26.5 m (87 ft). 	One sample in this layer will be used to determine the concentration changes from the H ₂ layer above. The sample will be analyzed for all COCs.
	 Low contaminant concentration Plio-pleistocene layer: Collect one sample at the onset of this formation, presumed to be 37.2 m (122 ft). 	The sample in this layer will be used to determine the changes from the H ₃ layer above. The sample will therefore be analyzed for all COCs.
	 Low contaminant concentration Ringold E Formation (R_E): Collect one sample at the onset of this formation, presumed to be 47 m (138 ft). 	The Ringold E Formation consists of gravels and sand. The sample in this layer will be used to determine the changes from the Plio-pleistocene layer above. The sample will be analyzed for all COCs to obtain contaminant concentrations at this change in lithology.
	 Low contaminant concentration Ringold E Formation (R_E): Collect one sample just above the water table (approximately 63 m [207 ft]). 	One sample will be used to determine the concentrations just above the water table. The sample will be analyzed for all COCs.
	 Collect bulk density and grain-size distribution samples at major changes in lithology. Collect moisture samples with the other physical property samples. Specific intervals to be defined in SAP. 	Soil physical properties (e.g., moisture content, grain-size distribution, and bulk density) will be used to support modeling.
Borehole geophysical logging	Geophysically log the borehole.	Log the vertical distribution of radiological contaminants to confirm analytical data and refine preliminary conceptual contaminant distribution model.
		Perform neutron moisture logging to support contaminant transport modeling.
216-Z-1A Tile Field	Alternative II – No Further Characterizat	ion Alternative
No action	Determine whether the existing characterization data identifies the TRU and greater than Class C decision as the RI/FS decision-making risk driver.	Avoid unnecessary cost and worker exposure for collection of soil samples.

Table 7-5. Sampling Design Alternatives. (8 Pages)

Sample Collection Methodology	Key Features of Design	Basis for Sampling Design
216-Z-9 Trench Alte	rnative III – Conventional Drilling Throu	gh the Trench
Borehole characterization	Stabilize the soils atop the 216-Z-9 Trench by pumping shotcrete through the vent risers in the trench roof. Spray fixative coating over all internal surfaces within the enclosure. Dismantle and dispose the enclosure structure. Install a soil ramp over the trench to provide access for conventional drilling through the trench. Figure 7-3 shows a plan view of the 216-Z-9 Trench. Figure 7-4 shows section views of the 216-Z-9 Trench and enclosure structure.	installed into trench to give access to conventional drilling equipment. To support this operation, the contaminated soil at the top of the trench would be stabilized with shotcrete. All internal surfaces of the enclosure would be sprayed with a fixative. The enclosure would be dismantled and disposed. A soil ramp would be installed into the trench, providing access for borehole drilling. Because of the contaminants and concentrations within the trench, dismantling and disposing the enclosure would likely cost several million dollars. Rough order-of-magnitude drilling and analytical costs are estimated to be nearly \$1,000,000.
	Install one vadose borehole within the trench boundaries at the location with the highest contamination potential. Location will be based upon process knowledge of the trench construction. Borehole will be drilled to the water table. Soil samples will be collected in specific strata at the following intervals:	Soil samples will be used to determine type and concentration of COCs beneath the trench in the vadose zone. Sampling provides data for remedial action decision making, to confirm the preliminary conceptual contaminant distribution model, and to support contaminant transport modeling.
	 Soils within the crib structure: Collect one sample at approximately 5.5 m (18 ft). 	Extreme contamination expected in this region. This sample will only be analyzed for chemical constituents because the TRU/radiological status is known.
	 Highest contaminant concentration layer (H₁): Collect one sample at approximately 7.6 m (25 ft). 	TRU contamination levels are expected through layer H ₁ based on historical data (Smith 1973). This sample will only be analyzed for chemical constituents because the TRU/radiological status is known.
	 Highest contaminant concentration layer (H₂): Collect one sample at the onset of this layer, presumed to be 20 m (69 ft). 	TRU contamination levels may be present through layer H ₂ based on historical data (Smith 1973). This sample will be analyzed for all COCs to confirm the vertical extent of the TRU contamination and to fill the chemical constituent data gap.

Table 7-5. Sampling Design Alternatives. (8 Pages)

Sample Collection Methodology	Key Features of Design	Basis for Sampling Design
	Moderate-to-low contaminant concentration fine-grained Pliopleistocene layer: Collect one sample at the onset of the Pliopleistocene layer, presumed to be at 32 m (105 ft).	This region is expected to mark the onset of moderate radiological concentrations. Analyze for all COCs to obtain contaminant concentrations at this change in lithology.
	 Low contaminant concentration Ringold E Formation (R_E): Collect one sample at the onset of the R_E layer, presumed to be at 37 m (121 ft). 	The Ringold E Formation consists of gravel and sand and is expected to mark the onset of low radiological concentrations. The sample in this layer will be used to determine the changes from the Plio-pleistocene layer above and will be analyzed for all COCs to obtain contaminant concentrations at this change in lithology.
	 Low contaminant concentration Ringold E Formation (R_E): Collect one sample at the midpoint of the R_E layer at 52 m (170 ft). 	Because the Ringold E Formation is very deep, one sample is collected at the midpoint to avoid a large spatial data gap. Analyze for all COCs.
	Low contaminant concentration Ringold E Formation (R _E): Collect one sample just above the water table (approximately 67 m [220 ft]).	One sample will be used to determine the concentrations just above the water table. Analyze for all COCs.
	Collect bulk density and grain-size distribution samples at major changes in lithology. Moisture samples will be collected with the other physical samples. Specific intervals will be defined in the SAP.	Soil physical properties (e.g., moisture content, grain-size distribution, and bulk density) will be used to support contaminant transport modeling.
Borehole geophysical logging	Perform borehole geophysical logging from the surface to groundwater.	Logging will provide a continuous profile that confirms the vertical distribution of transuranic contaminants.
	Perform neutron moisture logging from surface to groundwater.	Collect soil moisture data to support contaminant transport modeling.

Table 7-5. Sampling Design Alternatives. (8 Pages)

Sample Collection Methodology	Key Features of Design	Basis for Sampling Design
216-Z-9 Trench Alte	rnative IV – Angle Drilling	
Borehole characterization	Drill two angle boreholes adjacent to the trench to capture samples from the soils beneath the trench. Because of the angled drilling geometry, it is not possible to collect samples from the soils immediately beneath the trench. Drill placement will be chosen to maximize the capture of samples under the footprint of the trench. However, practical factors, such as access requirements must be factored into selection of drilling locations:	Use of angle drill rig allows collection of soil samples from beneath the trench without special access provisions. Two boreholes are used to optimize the collection of samples beneath the trench. Refer to Figure 7-5 for conceptual angle drilling borehole configurations at 216-Z-9-Trench. Drill boreholes to allow soil sampling with depth and to support geophysical logging.
	 Highest contaminant concentration layers (H₁ and H₂): Borehole A: Collect one sample at the onset of this layer, presumed to be 20 m (69 ft). 	TRU contamination levels may be present through both layers H ₁ and H ₂ based on historical data (Smith 1973). This sample will be analyzed for all COCs to confirm the vertical extent of the TRU contamination and to fill the chemical constituent data gap.
	 Moderate-to-low contaminant concentration fine-grained Pliopleistocene layer: Borehole A: Collect one sample at the onset of the Pliopleistocene layer, presumed to be at 32 m (105 ft). Borehole B: Collect one sample at the onset of the Pliopleistocene layer, presumed to be at 32 m 	This region is expected to mark the onset of moderate radiological concentrations. Analyze for all COCs to obtain contaminant concentrations at this change in lithology.
	 (105 ft). Low contaminant concentration Ringold E Formation (R_E): Borehole A: Collect one sample at the onset of the R_E layer, presumed to be at 37 m (121 ft). Borehole B: Collect one sample at the onset of the R_E layer, presumed to be at 37 m (121 ft). 	The Ringold E Formation consists of gravel and sand and is expected to mark the onset of low radiological concentrations. One sample in this layer will be used to determine the changes from the Plio-pleistocene layer above. The sample will be analyzed for all COCs to obtain contaminant concentrations at this change in lithology.
	 Low contaminant concentration Ringold E Formation (R_E): Borehole B: Collect one sample at the midpoint of the R_E layer at 52 m (170 ft). 	Because the Ringold E Formation is very deep, one sample is collected at the midpoint to avoid a large spatial data gap.

Table 7-5. Sampling Design Alternatives. (8 Pages)

Sample Collection Methodology	Key Features of Design	Basis for Sampling Design
	 Low contaminant concentration Ringold E Formation (R_E): Borehole B: Collect one sample just above the water table (approximately 67 m [220 ft]). 	One sample will be used to determine the concentrations just above the water table. The sample will be analyzed for all COCs.
·	 Collect bulk density and grain- size distribution samples at major changes in lithology. Collect moisture samples with the other physical property samples. Specific intervals to be defined in SAP. 	Soil physical properties (e.g., moisture content, grain-size distribution, and bulk density) will be used to support contaminant transport modeling.
Borehole geophysical logging	Perform borehole geophysical logging in both boreholes.	Logging will provide a continuous profile that confirms the vertical distribution of transuranic contaminants.
	Perform neutron moisture logging in both boreholes.	Collect soil moisture data to support contaminant transport modeling.
216-Z-9 Trench Alter	rnative V – Drive Casing Sampling Throu	gh an Enclosure Riser with Pile Driver
Drive casing sampling	Install drive casing with pile driver through an existing riser, or through a new one. Sample using a liner inside casing. Withdraw casing liner with pile driver and crane. Sampling locations to be	Pile driver may be used to remotely install drive casing through a riser in the enclosure roof without putting a vertical load on the trench roof. A substantial contamination control system and sleeving will be required during operation.
	determined after casing liner has been retrieved.	Use of liner inside the casing will maximize soil retention during retrieval of the liner.
	Remove outer drive casing after geophysical logging. Soil samples will be collected in specific strata at the following intervals until refusal:	This operation would require significant coordination with PHMC and DOE and may require a structural analysis of enclosure roof and/or creation of new access riser.
	Soils within the crib structure: Collect one sample at approximately 5.5 m (18 ft).	Extreme contamination expected in this region. This sample will only be analyzed for chemical constituents because the TRU/radiological status is known.
	Highest contaminant concentration layer (H ₁): Collect one sample at approximately 7.6 m (25 ft).	TRU contamination levels are expected through layer H ₁ based on historical data (Smith 1973). This sample will only be analyzed for chemical constituents because the TRU/radiological status is known.

Table 7-5. Sampling Design Alternatives. (8 Pages)

Sample Collection Methodology	Key Features of Design	Basis for Sampling Design
	 Highest contaminant concentration layer (H₂): Collect one sample at the count of this layer, presumed to be 20 m (69 ft). 	TRU contamination levels may be present through both layers H ₁ and H ₂ based on historical data (Smith 1973). This sample will be analyzed for all COCs to confirm the vertical extent of the TRU contamination and to fill the chemical constituent data gap.
		Drive casing is not expected to penetrate below this elevation.
Geophysical logging in drive casing	Perform borehole geophysical logging in drive casing.	Logging will provide a continuous profile that confirms the vertical distribution of transuranic contaminants.
	Perform neutron moisture logging in drive casing.	Collect soil moisture data to support contaminant transport modeling.
216-Z-9 Trench Alter Through an Enclosu	rnative VI – GeoProbe/Cone Penetrom e te re Riser	r Push Rods for Geophysical Logging
Sample soils through GeoProbe rods	Install an outer support pipe through enclosure riser. Install portable GeoProbe unit atop enclosure roof. Push rods through available riser until refusal.	coordination with PHMC and DOE, a structural analysis of the enclosure roof,
		A substantial contamination control system will be required during operation.
	Sample through upper trench and collect continuous soil sample or discrete samples with GeoProbe rods until refusal.	GeoProbe rods can be pushed for continuous sampling or can be installed and retrieved for discrete sampling.
Sample vapors through GeoProbe/ cone penetrometer rods	Sample carbon tetrachloride vapors at specified depth intervals until refusal.	Use GeoProbe rods outfitted with vapor sampling ports.
Geophysical logging in GeoProbe/cone	Perform borehole geophysical logging in GeoProbe/cone penetrometer rods.	Logging will provide a continuous profile that confirms the vertical distribution of transuranic contaminants.
penetrometer rods	Perform neutron moisture logging in GeoProbe/cone penetrometer rods.	Collect soil moisture data to support contaminant transport modeling.

Sample Collection Methodology	Key Features of Design	Basis for Sampling Design
216-Z-9 Trench Alte	rnative VII – No Further Characterization	n Alternative
No action	Determine whether the existing characterization data identifies the TRU and greater than Class C decision as the RI/FS decision-making risk driver.	Avoid unnecessary cost and worker exposure for collection of soil samples.

Table 7-5. Sampling Design Alternatives. (8 Pages)

PHMC = Project Hanford Management Contractor

7.4.2 Evaluation of Alternative Sampling Designs

7.4.2.1 Alternative I – Borehole Drilling in Vicinity of Well 299-W18-159. The Alternative I sampling design for the 216-Z-1A Tile Field follows the focused sampling concept (Ecology 1995). The sampling intervals shown in Table 7-5 provide a useful vertical profile of contaminants through the waste site. It was determined that sufficient radiological data exist in the highest contamination concentration interval (H_1) . Therefore, the COC list was revised to eliminate the radiological constituents in the H_1 layer. Because this alternative fills the data gaps and enables confirmation of historical radiological data, it is the recommended alternative.

7.4.2.2 Alternative II – No Further Characterization. Alternative II applies to the 216-Z-1A Tile Field. It is based on the observation that the TRU-contaminated and greater than Class C status of the site could be the RI/FS risk driver for this site and that further characterization efforts may not affect the outcome of remedial decision making. This alternative offers potential cost savings and as low as reasonably achievable (ALARA) benefits; however, it does not provide waste inventory data that would support selection of certain remedial actions (notably the engineered multimedia barrier). Therefore, this alternative is not recommended for further evaluation

7.4.2.3 Alternative III – Conventional Drilling Through the Trench. This alternative provides a vertical profile of COCs to verify the preliminary conceptual contaminant distribution model. The disadvantages of this alternative are the high costs with little gain to the RI/FS process, as the expense associated with this alternative only adds data from the region immediately beneath the waste site, which is not a particularly sensitive data gap. In addition, this alternative would require extreme contamination-control measures. For these reasons, Alternative III is not recommended for further evaluation.

7.4.2.4 Alternative IV – Angle Drilling. Alternative IV involves collecting samples under the trench without the need for decommissioning the existing structure. Angle drilling does not provide an optimized vertical contaminant profile but does provide good characterization in the lower portion of the vadose zone. The cost of this alternative is expected to be significantly less than the cost of Alternative III.


7-13

+ 288-W18-252 ♦ Borehole Location 200-PW-1 Waste Sites Roads Aw Railroads Aw Fences Planned Borehole 70 200 100 BHI:man 11/20/00 /home/manye/a wi_z_bombols.aml_216-Z-IA_1 Plotted 22-MAR-2001 Ray I

Figure 7-1. Plan View of the 216-Z-1A Tile Field.

Remedial Investigation DQO Summary Report - 200-PW-1 OU Phase I Representative Waste Sites April 2001

Figure 7-2. Conceptual Diagram of Borehole in the 216-Z-1A Tile Field.



Scale: 1"=30' Horizontal & Vertical


288-W15-203_288-W15-206 200-PW-1 Waste Sites Borehole Location ∴ ∴ Railroads ✓ Fences

Figure 7-3. Plan View of the 216-Z-9 Trench.


BHI:msa 11/20/00 /home/masye/umls/pw1_x_bombols.temi_216-2-9_3 Plottet 26-MAR-2001 Rev 1

100

Figure 7-4. Section View of the 216-Z-9 Trench.



NORTH - SOUTH CROSS SECTION



DIMENSIONS IN METERS




Figure 7-5. Conceptual Diagram of the Angle Drilling Boreholes.

TO THE WAY SHE WAS EVALUATED BY DEFINITION OF THE CONTROL OF

at by Hoger and Marcon each have not to the All Total No.

- 7.4.2.5 Because this alternative fills identified data gaps beneath the waste site without a major project preparation activity and is a proven technology, Alternative IV is the proposed alternative for the 216-Z-9 Trench.
- 7.4.2.6 Alternative V Drive Casing Sampling Through an Enclosure Riser with Pile Driver. Alternative V would require substantial contamination controls and coordination with DOE, FH, and the ERC. The advantage of this alternative is that it is a relatively low-cost approach for sampling the upper trench zone and it also avoids placing stress on the trench roof. The disadvantages include the potential need for a new opening in the trench enclosure and the possible loss of sample media during casing extraction. This alternative may be evaluated further for collection of samples in the upper region of the trench.
- 7.4.2.7 Alternative VI GeoProbe/Cone Penetrometer Push Rods for Geophysical Logging Through an Enclosure Riser. Alternative VI is similar to Alternative IV but would place loads on the enclosure roof that may be unacceptable; consequently, a structural analysis would be required for the enclosure roof. Modifications may be required to the enclosure prior to implementation. In addition, a guard pipe would need to be installed to provide lateral support for the GeoProbe rods in the 6.1-m (20-ft) unsupported zone between the bottom of the GeoProbe unit and the onset of trench soil. For these reasons, Alternative VI is not considered further.
- 7.4.2.8 Alternative VII No-Further Characterization Alternative. Alternative VII applies to the 216-Z-9 Trench and is based on the observation that the TRU and greater than Class C status of the site could be the RI/FS risk driver for this site, and that further characterization efforts may not affect the outcome of remedial decision making. This alternative offers potential cost savings and ALARA benefits; however, this alternative does not provide waste inventory data that would support selection of certain remedial actions (notably the engineered multimedia barrier). Therefore, Alternative VII is not recommended for further evaluation.

7.4.3 Proposed Sampling Designs

The proposed sampling designs incorporate a single borehole through the most highly contaminated portion of the 216-Z-1A Tile Field and two angle boreholes under the 216-Z-9 Trench. These designs provide safe, reliable, and cost-effective sampling methods that satisfy the identified data needs. The sampling designs for these two sites are integrated because the chemical contamination data from the upper 18.3 m (60 ft) of the 216-Z-1A Tile Field will be used to fill a data gap in the upper region of the 216-Z-9 Trench. This is necessary because the angle-drilling concept applied to the 216-Z-9 Trench does not permit the collection of soil samples from the upper 18.3 m (60 ft) of the site (see Figure 7-5).

The process history for these two sites was evaluated to determine the degree of similarity in the waste streams before the 216-Z-1A Tile Field chemical data could be applied to the 216-Z-9 Trench. The review of historical data and an interview with Z Plant operating personnel indicated that the waste streams differed between the two sites, principally in waste

¹ M. L. Yates, personal interview on February 27, 2001, with Mr. Thurman Cooper, PFP Chemist.

Rev. 0

discharge concentrations. The same chemicals were released to both sites; however, the 216-Z-9 Trench received the more highly concentrated discharge waste streams. The only known exception is that cadmium-nitrate was deliberately released to the 216-Z-9 Trench for criticality control near the end of the trench's operating life. Cadmium concentrations were reported in samples from the 216-Z-9 Trench (Smith 1973).

Because the chemical discharges to both sites involved the same chemistry (with the exception of the cadmium-nitrate), the use of the 216-Z-1A chemical data from the upper regions of the site is considered to be appropriate but may be at lower concentrations than in the 216-Z-9 Trench. The chemical analytical data obtained from both sites will be analyzed. Extrapolations may be necessary with the 216-Z-1A data for use in the uppermost region of the 216-Z-9 Trench.

The sampling designs proposed for the 216-Z-1A Tile Field and 216-Z-9 Trench are presented in Table 7-6.

Table 7-6. Proposed Sampling Designs. (4 Pages)

Sample Collection Methodology	Key Features of Design	Basis for Sampling Design
216-Z-1A Tile Field	Alternative I–Borehole Drilling in Vicinia	y of Well 299-W18-159
Borehole characterization	Install one vadose borehole in close proximity to the 299-W18-159 borehole, which is near the center of the tile field. Refer to Figures 7-1 and 7-2. Soil samples will be collected in specific strata at the following intervals:	The 299-W18-159 borehole spectral gamma logging results indicate that the soils in the vicinity of this borehole have higher contamination levels than any other borehole that was logged. The borehole will be drilled from the surface to the water table for borehole soil sampling.
	Highest contaminant concentration layer (H ₁): The transport of 2.7 are transported to the contaminant concentration.	The radiological contamination concentrations in this region are above the TRU definition (PNNL 1998).
	 Collect one sample at 3.7 m (12 ft). Collect one sample at the onset of native soils beneath the tile field gravel bed, presumed to be at 	The 3.7-m (12-ft) sample is within the sand layer of the most highly contaminated region of the tile field (PNNL 1999b). The sand is more likely to yield a sample than the gravel layer beneath it.
	7.6 m (25 ft). - Collect samples at 10.7 m and 13.7 m (35 ft and 45 ft).	The 7.6-m (25-ft) region is expected to contain TRU-contaminated soils, but at significantly lower concentrations than the 3.7 m (12 ft) depth.
	en e	The two deeper samples will complete a vertical contaminant concentration profile within this highly contaminated layer.
		None of the samples collected within the H ₁ layer will be analyzed for radiological COCs because there is no radiological data gap in this depth interval.

Remedial Investigation DQO Summary Report - 200-PW-1 OU Phase I Representative Waste Sites April 2001

Table 7-6. Proposed Sampling Designs. (4 Pages)

Sample Collection Methodology	Key Features of Design	Basis for Sampling Design
	 Low contaminant concentration sand layer (H₂): Collect one sample at the onset of this formation, presumed to be 17 m (58 ft). 	Historical data shows TRU contamination to a depth of approximately 17.7 m (58 ft). This region is expected to delineate the shift to low radiological concentrations. The sample will only be analyzed for the chemical COCs to fill that data gap.
	 Low contaminant concentration gravel layer (H₃): Collect one sample at the onset of this formation, presumed to be 26.5 m (87 ft). 	One sample in this layer will be used to determine the concentration changes from the H ₂ layer above. The sample will be analyzed for all COCs to obtain contaminant concentrations at this change in lithology.
	Low contaminant concentration Pliopleistocene layer: Collect one sample at the onset of this formation, presumed to be 37.2 m (122 ft).	The sample in this layer will be used to determine the changes from the H ₃ layer above. The sample will be analyzed for all COCs to obtain contaminant concentrations at this change in lithology.
	 Low contaminant concentration Ringold E Formation (R_E): Collect one sample at the onset of this formation, presumed to be 47 m (138 ft). 	The Ringold E Formation consists of gravels and sand. The sample in this layer will be used to determine the changes from the Pliopleistocene layer above. The sample will be analyzed for all COCs to obtain contaminant concentrations at this change in lithology.
	Low contaminant concentration Ringold E Formation (R _E): Collect one sample just above the water table (approximately 63 m [207 ft]).	One sample will be used to determine the concentrations just above the water table. The sample will be analyzed for all COCs.
	Collect bulk density and grain-size distribution samples at major changes in lithology. Collect moisture samples with the other physical property samples. Specific intervals to be defined in SAP.	Soil physical properties (e.g., moisture content, grain-size distribution, and bulk density) will be used to support modeling.
	Geophysically log the borehole.	Log the vertical distribution of radiological contaminants to confirm analytical data and refine preliminary conceptual contaminant distribution model.
		Perform neutron moisture logging to support contaminant transport modeling.

Table 7-6. Proposed Sampling Designs. (4 Pages)

Sample Collection Methodology	Key Features of Design	Basis for Sampling Design
216-Z-9 Trench Alter	rnative III – Angle Drilling	
Borehole characterization	Drill two angle boreholes adjacent to the trench to capture samples from the soils beneath the trench. Because of the angled drilling geometry, it is not possible to collect samples from the soils immediately beneath the trench. Drill placement will be chosen to maximize the capture of samples under the footprint of the trench. However, practical factors, such as access requirements must be factored into selection of drilling locations.	tracial access provisions. Two boreholes are made to optimize the collection of samples beneath the trench. Refer to Figure 7-5 for conceptual angle drilling borehole configurations at
	 Highest contaminant concentration layers (H₁ and H₂): Borehole A: Collect one sample at the onset of this layer, presumed to be 20 m (69 ft). 	TRU contamination levels may be present through both layers H ₁ and H ₂ based on historical data (Smith 1973). This sample will be analyzed for all COCs to confirm the vertical extent of the TRU contamination and to fill the chemical constituent data gap.
	Moderate-to-low contaminant concentration fine-grained Plio-pleistocene layer: Borehole A: Collect one sample at the onset of the Plio-pleistocene layer, presumed to be at 32 m (105 ft). Borehole B: Collect one sample at the onset of the Plio-pleistocene	This region is expected to mark the onset of moderate radiological concentrations. Analyze for all COCs to obtain contaminant concentrations at this change in lithology.
	layer, presumed to be at 32 m (105 ft).	
	 Low contaminant concentration Ringold E Formation (R_E): Borehole A: Collect one sample at the caset of the R_E layer, presumed to be at 37 m (121 ft). Borehole B: Collect one sample at the onset of the R_E layer, presumed to be at 37 m (121 ft). 	The Ringold B Formation consists of gravel and sand find is expected to mark the onset of low radiological concentrations. One sample in this layer will be used to determine the changes from the Plio-pleistocene layer above. The sample will be analyzed for all COCs to obtain contaminant concentrations at this change in lithology.
	 Low contaminant concentration Ringold E formation (R_E): Borehole B: Collect one sample at the midpoint of the R_E layer, at 52 m (170 ft). 	Because the Ringold E Formation is very deep, one sample is collected at the midpoint to avoid a large spatial data gap.

Sample Collection Key Features of Design **Basis for Sampling Design** Methodology One sample will be used to determine the Low contaminant concentration Ringold E Formation (R_E): concentrations just above the water table. The sample will be analyzed for all COCs. - Borehole B: Collect one sample just above the water table (approximately 67 m [220 ft]). Collect bulk density and Soil physical properties (e.g., moisture content, grain-size distribution samples at grain-size distribution, and bulk density) will be used to support contaminant transport major changes in lithology. Collect moisture samples with the modeling. other physical property samples. Specific intervals to be defined in SAP. Geophysical Perform borehole geophysical logging Logging will provide a continuous profile that logging in both boreholes. confirms the vertical distribution of transuranic contaminants. Perform neutron moisture logging in Collect soil moisture data to support both boreholes. contaminant transport modeling.

Table 7-6. Proposed Sampling Designs. (4 Pages)

7.5 POTENTIAL SAMPLE DESIGN LIMITATIONS

Potential sample design limitations are as follows:

- The 216-Z-9 Trench is not accessible for installation of conventional drilling equipment. Alternate drilling methods/approaches (e.g., angle drilling) must be used to protect the concrete enclosure roof from unacceptable loads.
- Contamination levels in both waste sites are significant and will require employment of substantial contamination controls to ensure the health and safety of workers and protection of the environment and equipment. Such controls may restrict the movement of workers. Samples with high contamination levels may be reduced in volume to permit shipment to laboratories. However, this may hinder the ability of the laboratories to meet quality assurance/quality control requirements.
- Drilling impediments (e.g., boulders) may be encountered and/or insufficient sample volumes may be retrieved from the split-spoon samplers. The list of analytes will be prioritized in the SAP to account for insufficient sample volume.
- Drilling will generate excessive heat and may volatilize the VOAs that are present within the soil. This may affect the accuracy of the VOA measurements.
- Because the potential exists for significant concentrations of radiological COCs, samples may need to be analyzed in an onsite laboratory. In this case, expected impacts include high

analytical costs, degradation of detection limits, reduced analyte lists, and long turnaround times. The presence of TRU-contaminated soil would also significantly impact waste handling and management. Sample volumes may be reduced if the radiation levels for the samples are too high.

- Analysis of VOA contaminants imposes sample hold-time limitations. To overcome these
 limits, prior planning and coordination are recommended to avoid violating the hold-time
 limits.
- The sampling intervals developed in this DQO summary report may be adjusted in the SAP to account for refinements to the sampling designs.

8.0 REFERENCES

- 10 CFR 61, "Licensing Requirements for Land Disposal of Radioactive Waste," Code of Federal Regulations, as amended.
- 40 CFR 141, "Federal Primary Drinking Water Standards," Code of Federal Regulations, as amended.
- 40 CFR 191, "Environmental Radiation Protection Standards for Management and Disposal of Spent Nuclear Fuel, High-Level, and Transuranic Radioactive Wastes," Code of Federal Regulations, as amended.
- Agnew, S. F., J. Boyer, R. S. Corbin, T. B. Duran, J. R. Fitzpatrick, K. S. Jurgensen, T. P. Ortiz, and B. L. Young, 1997, *Hanford Tank Chemical and Radionuclide Inventories: HDW Model*, LA-UR-96-3860, Rev. 4, Los Alamos National Laboratory, Los Alamos, New Mexico.
- ANL, 1993, Manual for Implementing Residual Radioactive Material Guidelines Using RESRAD, Version 5.0, RESRAD v5.82, Argonne National Laboratory, Argonne, Illinois.
- ARH, 1976, Z Plant Liquid Waste Disposal Through the 241-Z Vault, ARH-CD-323, Atlantic Richfield Hanford, Richland, Washington.
- Bauer, R. G., R. Price, and R. Randall, 2000, Proof-of-Principle Demonstration of a Passive Neutron Tool for Detection of TRU-Contaminated Soil at the 216-Z-1A Tile Field, BHI-01436, Rev. 0, Bechtel Hanford, Inc., Richland, Washington.
- BHI, 1995, DNAPL Investigation Report, BHI-00431, Rev. 0, Bechtel Hanford, Inc., Richland, Washington.
- BHI, 1998, Hanford Site Atlas, BHI-01119, Rev. 1, Bechtel Hanford, Inc., Richland, Washington.
- BHI, 1999, Hydrogeologic Conceptual Model for the Carbon Tetrachloride and Uranium/Technetium Plumes in the 200 West Area: 1994 Through 1999 Update, BHI-01311, Rev. 0, Bechtel Hanford, Inc., Richland, Washington.
- BHI-EE-01, Environmental Investigations Procedures, Bechtel Hanford, Inc., Richland, Washington.
- Borsheim, G. L., and B. C. Simpson, 1991, An Assessment of the Inventories of the Ferrocyanide Watchlist Tanks, WHC-SD-WM-ER-133, Westinghouse Hanford Company, Richland, Washington.

- Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (CERCLA), 42 U.S.C. 9601, et seq.
- Curren, E. F., 1972, 200 Areas Disposal Sites for Radioactive Liquid Wastes, ARH-947, Atlantic Richfield Hanford Company, Richland, Washington.
- DOE, 1999, Final Hanford Comprehensive Land-Use Plan Environmental Impact Statement, DOE/EIS-0222-F, U.S. Department of Energy, Washington, D.C.
- DOE Guide 435.1-1, Chapter 3, Transuranic Waste Requirements, as amended, U.S. Department of Energy, Washington, D.C.
- DOE-RL, 1992, Z Plant Source Aggregate Area Management Study Report, DOE/RL-91-58, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington.
- DOE-RL, 1997a, Hanford Sitewide Groundwater Remediation Strategy, DOE/RL-94-95, Rev. 1, U.S. Department of Energy, Richland Operations Office, Richland, Washington.
- DOE-RL, 1997b, Waste Site Grouping for 200 Areas Soil Investigations, DOE/RL-96-81, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington.
- DOE-RL, 1999, 200 Areas Remedial Investigation/Feasibility Study Implementation Plan Environmental Restoration Program, DOE/RL-98-28, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington.
- Ecology, 1995, Washington State Department of Ecology Toxics Cleanup Program Guidance on Sampling and Data Analysis Methods, Publication No. 94-49, Washington State Department of Ecology, Olympia, Washington.
- Ecology, EPA, and DOE, 1998, Hanford Federal Facility Agreement and Consent Order (Tri-Party Agreement), 2 vols., as amended, Washington State Department of Ecology, U.S. Environmental Protection Agency, and U.S. Department of Energy, Olympia, Washington.
- EPA, 1983, Methods of Analysis of Water and Waste, EPA-600/4-79-020, U.S. Environmental Protection Agency, Office of Research and Development, Cincinnati, Ohio.
- EPA, 1986, Test Methods for Evaluating Solid Waste: Physical/Chemical Methods, SW-846, 3rd edition, Office of Solid Waste and Emergency Response, U.S. Environmental Protection Agency, Washington, D.C.
- EPA, 1994a, Guidance for Data Quality Objectives Process, EPA QA/G-4, U.S. Environmental Protection Agency, Washington, D.C.

- EPA, 1994b, Guidance Manual for the Integrated Exposure Uptake Biokinetic Model for Lead in Children, EPA/540/R-93-081, Publication No. 9285.7, U.S. Environmental Protection Agency, Washington, D.C.
- Fecht, K. R., G. V. Last, and K. R. Price, 1977, Evaluation of Scintillation Probe Profiles from 200 Area Crib Monitoring Wells, ARH-ST-156, Atlantic Richfield Hanford Company, Richland, Washington.
- FH, 1999, Radionuclide Inventory of Liquid Waste Disposal Sites on the Hanford Site, HW-1744, Fluor Hanford, Inc., Richland, Washington.
- FH, 2000, Submittal of Documentation in Fulfillment of Milestone M-15-37B, letter FH-000279, to U.S. Department of Energy, Richland Operations Office, dated June 15, 2000, Fluor Hanford, Inc., Richland, Washington.
- GE, 1994, Hanford Engineer Works Technical Manual (T/B Plants), Parts A, B, and C, HW-10475, General Electric Company, Richland, Washington.
- GE, 1951a, Process Waste Disposal Summary 200 Areas (September 1949 through December 1950), HW-20583, General Electric Company, Richland, Washington.
- GE, 1951b, *Uranium Recovery Technical Manual*, HW-19140, General Electric Company, Richland, Washington.
- GE, 1955, Radioactive Contaminants in Liquid Wastes Discharged to Ground at Separation Facilities Through June 1955, HW-38562, General Electric Company, Richland, Washington.
- Gerber, M. S., 1997, History and Stabilization of the Plutonium Finishing Plant (PFP) Complex, Hanford Site, HNF-EP-0924, Fluor Daniel Hanford, Inc., Richland, Washington.
- HEW, 1945, History of Operations (1 January 1944 to 20 March 1945), OUT-1462, Hanford Engineering Works, Richland, Washington.
- Kaplan, D. I., and R. J. Serne, 2000, Geochemical Data Package for the Hanford Immobilized Low-Activity Tank Waste Performance Assessment (ILAW PA), PNNL-13037, Rev. 1, Pacific Northwest National Laboratory, Richland, Washington.
- Kasper, R. B., 1982, 216-Z-12 Transuranic Crib Characterization: Operational History and Distribution of Plutonium and Americium, RHO-ST-44, Rockwell Hanford Operations, Richland, Washington.
- LMHC, 1999, 241-Z-361 Sludge Characterization Data Quality Objectives, HNF-4225, Rev. 0, Lockheed Martin Hanford Corporation, Richland, Washington.

- Ludowise, J. D., 1978, Report on Plutonium Mining Activities at 216-Z-9 Enclosed Trench, RHO-ST-21, Rockwell Hanford Operations, Richland, Washington.
- Maxfield, H. L., 1979, 200 Areas Waste Sites Handbook, 3 vols., RHO-CD-673, Rockwell Hanford Operations, Richland, Washington.
- PNL, 1994, Hydrostratigraphy and Recharge Distributions from Direct Measurements of Hydraulic Conductivity Using the UFA Method, PNL-9424, Pacific Northwest Laboratory, Richland, Washington.
- PNNL, 1998, Composite Analysis for Low-Level Disposal in the 200 Area Plateau of the Hanford Site, PNNL-11800, Pacific Northwest National Laboratory, Richland, Washington.
- PNNL, 1999a, Hanford Site Groundwater Monitoring for Fiscal Year 1998, PNNL-12086, Pacific Northwest National Laboratory, Richland, Washington.
- PNNL, 1999b, Results of 1998 Spectral Gamma-Ray Monitoring of Boreholes at the 216-Z-1A Tile Field, 216-Z-9 Trench, and 216-Z-12 Crib, PNNL-11978, Pacific Northwest National Laboratory, Richland, Washington.
- PNNL, 2000, Subsurface Transport Over Multiple Phases (STOMP), PNNL-12034, Pacific Northwest National Laboratory, Richland, Washington.
- Price, S. M., M. K. Additon, and R. B. Kasper, 1979, Distribution of Plutonium and Americium Beneath the 216-Z-1A Crib: A Status Report, RHO-ST-17, Rockwell Hanford Operations, Richland, Washington.
- Rohay, V. J., 1994, 1994 Conceptual Model of the Carbon Tetrachloride Contamination in the 200-West Area at the Hanford Site, WHC-SD-EN-TI-248, Rev. 0, Westinghouse Hanford, Inc., Richland, Washington.
- Rohay, V. J., 2000, Performance Evaluation Report for Soil Vapor Extraction Operations at the Carbon Tetrachloride Site, BHI-00720, Rev. 4, Bechtel Hanford, Inc., Richland, Washington.
- Smith, A. E., 1973, Nuclear Reactivity Evaluations of 216-Z-9 Enclosed Trench, ARH-2915, Atlantic Richfield Hanford, Richland, Washington.
- WAC 173-340, "Model Toxics Control Act Cleanup," Washington Administrative Code, as amended.
- WDOH, 1983, Hanford Guidance for Radiological Cleanup, WDOH/320-015, Washington State Department of Health, Olympia, Washington.

Rev. 0

- WHC, 1991, Tank Waste Discharge Directly to Soil at the Hanford Site, WHC-MR-0227, Westinghouse Hanford Company, Richland, Washington.
- WHC, 1992, Hydrogeologic Model for the 200-West Groundwater Aggregate Area, WHC-SD-EN-TI-014, Rev. 0, Westinghouse Hanford Company, Richland, Washington.
- WHC, 1993, Groundwater Impact Assessment Report for the 216-Z-20 Crib, 200 West Area, WHC-EP-0674, Westinghouse Hanford Company, Richland, Washington.

DISTRIBUTION

U.S. Department of Energy	
Richland Operations Office	
B. L. Foley	H0-12
ERC Team	
K. A. Anselm, CHI	H9-03
R. G. Bauer, CHI (5)	H9-03
L. R. Curry, BHI	H0-19
R. J. Fabre, BHI	X5-50
B. H. Ford, BHI	H0-21
M. N. Jarayssi, BHI	H0-19
J. D. Ludowise, CHI	H9-03
G. B. Mitchem, BHI	H0-19
R. W. Ovink, CHI	H9-03
V. J. Rohay, CHI	H0-19
K. M. Singleton, CHI	H9-02
R. B. Sitsler, BHI	X5-60
W. S. Thompson, BHI	H9-03
C. D. Wittreich, CHI	H9-03
M. L. Yates, CHI	H9-01
<u>PNNL</u>	
D 11 (11 14 14 1	07.40
B. K. (Keith) Hampton (FDH)	S7-40
J. M. Zachara, PNNL	K8-96
Document and Information Services (3)	H0-09
DOE-RL Public Reading Room	H2-53
Hanford Technical Library	P8-55